

DATE \_\_\_\_\_ BY \_\_\_\_\_  
 SURVEYED \_\_\_\_\_ PLOTTED \_\_\_\_\_  
 PLAN NOTE BOOK \_\_\_\_\_ CHECKED \_\_\_\_\_  
 NO. \_\_\_\_\_ DATE \_\_\_\_\_ FILE NAME \_\_\_\_\_

DATE \_\_\_\_\_ BY \_\_\_\_\_  
 SURVEYED \_\_\_\_\_ PLOTTED \_\_\_\_\_  
 PROFILE NOTE BOOK \_\_\_\_\_ CHECKED \_\_\_\_\_  
 NO. \_\_\_\_\_ DATE \_\_\_\_\_ FILE NAME \_\_\_\_\_

PAVEMENT SCHEDULE

STATION	TO	STATION	LT/RT	SIDE	BITUMINOUS MATERIALS (PRIME COAT) (GAL)	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS (TON)	LEVELING BINDER (HAND METHOD), N50 (TON)	LEVELING BINDER (MACHINE METHOD), N50 (TON)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ YD)	TEMPORARY RAMP (SQ YD)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 (TON)	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) (SQ YD)	PAVEMENT REMOVAL (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL, 3" (SQ YD)	AGGREGATE WEDGE SHOULDER, TYPE B (TON)	HOT-MIX ASPHALT SHOULDERS, 8" (SQ YD)
847+50.00		847+55.00							24							
847+50.00		848+40.00						12								
847+50.00		852+44.00					82							1427		
847+50.00		849+87.30	RT		47	0.11	0.18	15			30				10	
847+50.00	TO	850+87.30	LT		67	0.15	0.26	21			43				15	
849+87.30	TO	852+44.00	RT		51	0.12	0.19	16			33					190
850+87.30	TO	852+44.00	LT		31	0.07	0.12	10			20					120
852+38.00	TO	852+44.00										21.5				
852+44.00	TO	852+68.25											70			
854+06.08	TO	854+09.00											8			
854+09.00	TO	854+15.00										21.5				
854+09.00	TO	855+65.70	RT		31	0.07	0.12	10			20					120
854+09.00	TO	856+65.70	LT		51	0.12	0.19	16			33					190
855+65.70	TO	857+00.00	RT		26	0.06	0.10	9			17				6	
856+65.70	TO	857+00.00	LT		7	0.02	0.03	2			4				1	
854+09.00	TO	857+00.00						80						841		
856+10.00	TO	857+00.00														
856+95.00	TO	857+00.00							24							
TOTAL					311	0.7	1.2	261	24	48	200	43	78	2,268	32	620

EARTHWORK SCHEDULE

STATION		SIDE	CUT VOLUME (CU YD)	FILL VOLUME (CU YD)
FROM	TO			
847+50.00	857+00.00	LT	195	435
847+50.00	857+00.00	RT	320	500
TOTAL			515	935

MAINTENANCE OF TRAFFIC

STAGE	LOCATION		SIDE	HMA BASE COURSE WIDENING, 8" (SQ YD)	SHORT TERM PAVEMENT MARKING		TEMPORARY PAVEMENT MARKING-LINE 4"	TEMPORARY PAVEMENT MARKING-LINE 6"	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	TEMPORARY CONCRETE BARRIER (FOOT)	RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)	TEMPORARY BRIDGE TRAFFIC SIGNALS (EACH)	
					WIDTH (IN)	WHITE (FOOT)	WHITE (FOOT)	YELLOW (FOOT)							
	STATION	TO	STATION	LT/RT	(SQ YD)	(IN)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)
PRESTAGE I	851+36.52	TO	852+76.47	LT	43										
	853+98.29	TO	855+14.13	LT	33										
	849+45.00					24	12		24						
STAGE I	849+54.53	TO	851+69.00			4	214		71						
	851+69.00	TO	854+84.00			4	315		105						
	854+84.00	TO	856+94.85			4	211		70						
	857+55.00					24	12		24						
	851+18.30	TO	855+35.12			4	417		139						
	849+32.00					24	12		24						
STAGE II	849+54.00	TO	851+69.00			4	215		72						
	851+69.00	TO	854+84.00			4	315		105						
	854+84.00	TO	856+97.00			4	213		71						
	857+57.00					24	12		24						
	847+50.00	TO	857+00.00	LT					950						
	847+50.00	TO	857+00.00	RT					950						
	847+50.00	TO	857+00.00	CL				238							
STAGE I	851+23.00											1			
	851+23.00	TO	855+30.00							410					
	855+30.00											1			
STAGE II	851+35.00												1		
	851+35.00	TO	855+18.00							390					
	855+18.00												1		
	847+50.00	TO	857+00.00											1	
TOTAL					76		1,948	1,900	238	729	410	390	2	2	1

PAVEMENT MARKING SCHEDULE

LOCATION		SIDE	TYPE	PAVEMENT MARKING REMOVAL (SQ FT)	PAINT PAVEMENT MARKING-LINE 4"	PAINT PAVEMENT MARKING-LINE 6"	
STATION	TO				STATION	LT/RT	WHITE (FOOT)
847+50.00	TO	857+00.00	LT	SOLID	317	*1,900	
847+50.00	TO	857+00.00	RT	SOLID	317	*1,900	
847+50.00	TO	857+00.00	CL	10' DASH, 30' SKIP	119	* 476	
TOTAL					753	3,800	476

\* QUANTITIES SHOWN IS FOR TWO APPLICATIONS TO PAINT THE PAVEMENT MARKING LINES.



USER NAME = kkhan  
 DESIGNED DB  
 DRAWN DB  
 CHECKED AS  
 DATE OCTOBER 14, 2011

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES  
 SN 006-0183 SHEET 1 OF 2

F.A.P. RTE. 587 SECTION (22 BR)BR COUNTY BUREAU 61 SHEETS 6 SHEET NO. 6 CONTRACT NO. 66995  
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT