

SUMMARY OF QUANTITIES

Specialty_Item	PAY ITEM #	DESCRIPTION	UNIT	TOTAL QUANTITIES	0011	0004	0004
					BRIDGE HENDERSON 80% FED. 20% STATE	ROADWAY HENDERSON 80% FED. 20% STATE	ROADWAY HENDERSON 100% STATE
	40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	120		120	
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	75		75	
	40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	3.5		3.5	
	40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	406		406	
	40600990	TEMPORARY RAMP	SQ YD	64		64	
	40603080	HOT - MIX ASPHALT BINDER COURSE, IL - 19.0, N50	TON	164		164	
	40603335	HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	260		260	
	42001300	PROTECTIVE COAT	SQ YD	815	815		
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	160		160	
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	106.7		106.7	
	44000100	PAVEMENT REMOVAL	SQ YD	370		370	
	44000152	HOT - MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	2180		2180	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50		50	
	44000400	GUTTER REMOVAL	FOOT	1045		1045	
	44004250	PAVED SHOULDER REMOVAL	SQ YD	1950		1950	
	48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	275		275	
	48203029	HOT - MIX ASPHALT SHOULDERS, 8"	SQ YD	1950		1950	

FILE NAME = Summary of Quantities.dgn

USER NAME = lababidism

DESIGNED -

REVISED -

DRAWN -

REVISED -

PLOT SCALE = 100.000' / 1" =

CHECKED -

REVISED -

PLOT DATE = 10/21/2011

DATE -

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S.
RTE.
1190

SECTION
(125BY)BR

COUNTY
KNOX

TOTAL SHEETS
94

SHEET NO.
5

CONTRACT NO. 68087

ILLINOIS FED. AID PROJECT