

SUMMARY OF QUANTITIES

Specialty_Item	PAY ITEM #	DESCRIPTION	UNIT	TOTAL QUANTITIES	0011 BRIDGE HENDERSON 80% FED. 20% STATE	0004 ROADWAY HENDERSON 80% FED. 20% STATE	0004 ROADWAY HENDERSON 100% STATE
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		
	50105220	PIPE CULVERT REMOVAL	FOOT	96		96	
	50200100	STRUCTURE EXCAVATION	CU YD	212	212		
	50300225	CONCRETE STRUCTURES	CU YD	69.8	69.8		
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	318.3	318.3		
	50300260	BRIDGE DECK GROOVING	SQ YD	650	650		
	50300280	CONCRETE ENCASEMENT	CU YD	4.2	4.2		
	50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	662	662		
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	70,140	70,140		
	50800515	BAR SPLICERS	EACH	660	660		
	51201700	FURNISHING STEEL PILES HP 12 X 74	FOOT	355	355		
	51202305	DRIVING PILES	FOOT	355	355		
	51203700	TEST PILE STEEL HP 12 X 74	EACH	2	2		
	51500100	NAME PLATES	EACH	1	1		
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTION 15"	EACH	2		2	
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTION 18"	EACH	2		2	
	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTION 24"	EACH	4		4	

FILE NAME =
Summary of Quantities.dgn

USER NAME = lalobidiam

DESIGNED -

REVISED -

DRAWN -

REVISED -

PLOT SCALE = 100.000' / in.

CHECKED -

REVISED -

PLOT DATE = 10/21/2011

DATE -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1190	(125BY)BR	KNOX	94	6
CONTRACT NO. 68087			ILLINOIS FED. AID PROJECT	