

GUARDRAIL										
LOCATION				CALCULATED LENGTH	TRAFFIC BARRIER TERMINAL, TYPE 6 (43.75')	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	NUMBER / LENGTH OF 12.5' SECTIONS OF STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS		TERMINAL MARKER - DIRECT APPLIED	GUARDRAIL MARKERS, TYPE A
							# OF SEC'S	FT		
NE	STA. 148+56	TO	STA. 150+12	156	1	1	5	62.5	1	2
SE	STA. 151+23	TO	STA. 153+69	246	1	1	12	150	1	3
NW	STA. 147+75	TO	STA. 150+21	246	1	1	12	150	1	3
SW*	STA. 151+30	TO	STA. 152+36	106	1	1	1	12.5	1	2
TOTAL				4	4	30	375	4	10	

* FLARED SECTION

GUARDRAIL AGGREGATE EROSION CONTROL 8"							
LOCATION				LENGTH	WIDTH	AREA	TOTAL
				FT	FT	SQ YD	TON
LT	STA. 148+62	TO	STA. 150+19	157	3	52.3	25.0
	STA. 151+23	TO	STA. 153+68	245	3	81.7	40.0
RT	STA. 147+68	TO	STA. 150+12	244	3	81.3	40.0
	STA. 151+30	TO	STA. 152+37	107	3	35.7	20.0
TOTAL							125.0

AGG. SHLDRS TY B 8"							
LOCATION				LENGTH	WIDTH	AREA	AGG. SHLDRS 8"
	STA.	TO	STA.	FT	FT	SQ YD	SQ YD
LT	STA. 142+00	TO	STA. 142+63	63	4.0	28.0	28
	STA. 142+97	TO	STA. 145+60	263	4.0	116.9	117
RT	STA. 142+00	TO	STA. 142+50	50	4.0	22.2	22
	STA. 142+85	TO	STA. 145+24	239	4.0	106.2	106
TOTAL							275

AGGREGATE FOR TEMPORARY ACCESS*				
LOCATION	AREA	THICKNESS	TOTAL	
	SQ YD	IN	TON	
RT	STA. 153+00	208	6	71
TOTAL			75	

* AREA IS MEASURED IN CADD

DRIVEWAY PAVEMENT REMOVAL		
LOCATION		AREA
		SQ YD
STA. 142+72	- 104' RT	50
TOTAL		50

AGGREGATE SURFACE COURSE, TY B*				
LOCATION		AREA	THICKNESS 3"	TOTAL
		SQ FT	FT	TON
LT	STA. 142+75	1330	3	25
RT	STA. 142+67	1635	3	31
	STA. 152+53	2680	3	51
	STA. 154+38	535	3	10
TOTAL				120

* AREAS ARE MEASURED IN CADD

GUARDRAIL REMOVAL				
LOCATION				LENGTH
				FT
LT	STA. 142+96	TO	STA. 150+33	737
	STA. 150+96	TO	STA. 151+60	64
RT	STA. 142+96	TO	STA. 150+33	737
	STA. 150+95	TO	STA. 151+60	65
TOTAL				1603

PAVEMENT REMOVAL					
LOCATION			LENGTH	WIDTH	AREA
			FT	FT	SQ YD
STA. 149+65	To	STA. 150+34	69	22	169
STA. 150+96	To	STA. 151+77	81	22	198
TOTAL					370

REMOVING INLETS			
LOCATION		OFFSET, RT/LT	EACH
STA. 142+60		40' LT	1
STA. 151+29		18.5' LT	1
STA. 151+32		17.6' RT	1
TOTAL			3

GUTTER REMOVAL				
LOCATION				LENGTH
				FT
LT	STA. 151+25	To	STA. 156+50	525
RT	STA. 151+30	To	STA. 156+50	520
TOTAL				1045