

BRIDGE APPROACH PAVEMENT CONNECTOR					
LOCATION			LENGTH	WIDTH	AREA
			FT	FT	SQ YD
STA. 149+65	To	STA. 149+85	20	36	80
STA. 151+57	To	STA. 151+77	20	36	80
<b>TOTAL</b>					<b>160</b>

CONCRETE GUTTER, TYPE A (SPECIAL)				
LOCATION				LENGTH
				FT
LT	STA. 153+75	To	STA. 156+50	275
RT	STA. 155+75	To	STA. 156+50	75
<b>TOTAL</b>				<b>350</b>

TEMPORARY CONCRETE BARRIER				
LOCATION				FT
STAGE I	STA. 147+25	TO	STA. 153+75	650
<b>TOTAL</b>				<b>650</b>

RELOCATE TEMPORARY CONCRETE BARRIER				
LOCATION				FT
STAGE II	STA. 147+25	TO	STA. 153+75	650
<b>TOTAL</b>				<b>650</b>

TRAFFIC CONTROL AND PROTECTION, STANDARD 701201				
LOCATION				L SUM
JOB SITE				1
<b>TOTAL</b>				<b>1</b>

TRAFFIC CONTROL AND PROTECTION, STANDARD 701321				
LOCATION				EACH
JOB SITE				1
<b>TOTAL</b>				<b>1</b>

TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	
LOCATION	L SUM
JOB SITE	1
<b>TOTAL</b>	<b>1</b>

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL DAYS
JOB SITE	60
<b>TOTAL</b>	<b>60</b>

MOBILIZATION	
LOCATION	L SUM
JOB SITE	1
<b>TOTAL</b>	<b>1</b>

IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE, NARROW), TEST LEVEL 3		
LOCATION	EACH	
STAGE II	STA. 147+20	1
	STA. 153+80	1
<b>TOTAL</b>		<b>2</b>

IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE, NARROW), TEST LEVEL 3		
LOCATION	EACH	
STAGE I	STA. 147+20	1
	STA. 153+80	1
<b>TOTAL</b>		<b>2</b>

TEMPORARY SOIL RETENTION SYSTEM						
LOCATION		TOP WIDTH	DEPTH	OFFSET	BOTTOM WIDTH	AREA
		FT	FT	FT	FT	SQ FT
STA. 142+76	TO STA. 143+05	29.00	10.00	51' RT	9.00	190.00
STA. 143+00	TO STA. 143+32	32.00	11.00	37' LT	9.00	226.00
<b>TOTAL</b>						<b>416.00</b>

CONSTRUCTION LAYOUT	
LOCATION	L SUM
JOB SITE	1
<b>TOTAL</b>	<b>1</b>

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
JOB SITE	9
<b>TOTAL</b>	<b>9</b>

TEMPORARY BRIDGE TRAFFIC SIGNALS	
LOCATION	EACH
JOB SITE	1
<b>TOTAL</b>	<b>1</b>

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH				
LOCATION		LENGTH	WIDTH	AREA
		FT	FT	SQ YD
STA. 010+00	TO STA. 010+80	80.00	12.00	106.67
<b>TOTAL</b>			<b>106.70</b>	

MOWING	
LOCATION	UNIT
JOB SITE	26
<b>TOTAL</b>	<b>26</b>

CHANGEABLE MESSAGE SIGN	
LOCATION	CAL MO
2 BOARDS FOR 1 WEEK EACH	0.50
<b>TOTAL</b>	<b>0.50</b>