

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTR. CODE	
				90% FED. 10% STATE	
				BRIDGE	
				0014	
				RURAL	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	39820.0	39820.0	
50800515	BAR SPLICERS	EACH	80.0	80.0	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	248.0	248.0	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24.0	24.0	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	24.0	24.0	
52100520	ANCHOR BOLTS, 1"	EACH	48.0	48.0	
58700300	CONCRETE SEALER	SQ FT	865.0	865.0	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	84.0	84.0	
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE NARROW) TEST LEVEL 3	EACH	1.0	1.0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6.0	6.0	
67100100	MOBILIZATION	L SUM	1.0	1.0	
70100410	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416	EACH	1.0	1.0	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0	1.0	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6.0	6.0	