

| CODE NO. | ITEM | UNIT | URBAN TOTAL QUANTITY | CONSTR. CODE |
|------------|--|-------|----------------------|----------------------|
| | | | | 90% FED 10% STATE |
| | | | | BRIDGE |
| | | | | 0014 |
| | | | | RURAL |
| Z0012142 | BRIDGE DECK SCARIFICATION 2 1/4" | SQ YD | 6901.0 | 6901.0 |
| Z0012754 | STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES) | SQ FT | 80.0 | 80.0 |
| Z0016001 | DECK SLAB REPAIR (FULL DEPTH, TYPE I) | SQ YD | 5.0 | 5.0 |
| Z0016002 | DECK SLAB REPAIR (FULL DEPTH, TYPE II) | SQ YD | 322.0 | 322.0 |
| Z0019300 | DRY GROUT SOLIDS | CU FT | 300.0 | 300.0 |
| Z0019307 | HOLES DRILLED | EACH | 4.0 | 4.0 |
| Z0029090 | DIAMOND GRINDING (BRIDGE SECTION) | SQ YD | 7158.0 | 7158.0 |
| Z0030332 | IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 | EACH | 1.0 | 1.0 |
| Z0031200 | JACKING AND CRIBBING | EACH | 12.0 | 12.0 |
| Z0046304 | PIPE UNDERDRAINS FOR STRUCTURES 4" | FOOT | 95.0 | 95.0 |
| * Z0049100 | RAISED PAVEMENT MARKER REFLECTOR REPLACEMENT | EACH | 108.0 | 108.0 |
| X2070304 | POROUS GRANULAR EMBANKMENT, SPECIAL | CU YD | 191.0 | 191.0 |
| * X7800620 | URETHANE PAVEMENT MARKING - LINE 5" | FOOT | 11829.0 | 11829.0 |

*** SPECIALTY ITEM**

| | | | | | | | | | | |
|--------------------------------------|---------------------|------------|-----------|---|---------------------------|--------------|----------|--------------|-----------|---------|
| FILE NAME = | USER NAME = sparksg | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| c:\pwork\pvidot\sparksg\d0282050\067 | 7F01-sh1-500.dgn | DRAWN - | REVISED - | | 72 | (B4-10-1)BDR | SANGAMON | 35 | 6 | |
| PLOT SCALE = 100.0000' / in. | | CHECKED - | REVISED - | | CONTRACT NO. 72F01 | | | | | |
| PLOT DATE = Nov-01-2011 11:48:57AM | | DATE - | REVISED - | | ILLINOIS FED. AID PROJECT | | | | | |
| | | | | | SCALE: | SHEET | OF | SHEETS | STA. | TO STA. |