

PAVMENT MARKING SCHEDULE														
LOCATION	STATION		TO STATION	LENGTH (FT)	URETHANE PVT MKG- LINE 5"		PREF. PLASTIC PVT. MKG. TY. B INLAID-LINE 5"	PVT. MARKING REMOVAL (SQ FT)	PAINT PVT MARKING- LINE 5"		RAISED REFL PVT MKR. REFLECTOR REM (EACH)	RAISED REFL PVT MKR. REFLECTOR REPLACEMENT (EACH)	SHORT-TERM PVT MKG (FT)	WORK ZONE PVT. MARKING REM. (SQ FT)
					WHITE (FT)	YELLOW (FT)			WHITE (FT)	YELLOW (FT)				
	202+52.0 44' LT	TO	209+96.00 56' RT	752					752				75	25
	180+21.0 44' RT	TO	183+76.00 44' RT	355						355			36	12
	183+76.0 44' RT	TO	192+30.00 56' LT	862						862			86	28
	192+30.0 56' LT	TO	202+52.00 56' LT	1,022						1,022			102	34
	202+52.0 56' LT	TO	209+96.00 44' RT	752						752			75	25
WB	183+76.0 68' LT	TO	185+47.00 68' LT	171						171			17	6
	185+47.0 68' LT	TO	188+47.00 72' LT	300						300			30	10
	188+47.0 72' LT	TO	204+85.00 72' LT	1,638						1,638			164	54
	204+85.0 72' LT	TO	206+85.00 68' LT	200						200			20	7
	206+85.0 68' LT	TO	213+65.00 68' LT	680						680			68	22
	183+76.0 56' LT	TO	185+47.00 56' LT	171						171			17	6
	185+47.0 56' LT	TO	188+47.00 60' LT	300						300			30	10
	188+47.0 60' LT	TO	204+85.00 60' RT	1,638						1,638			164	54
	204+85.0 60' LT	TO	206+85.00 56' LT	200						200			20	7
	206+85.0 56' LT	TO	211+37.00 56' LT	452						452			45	15
	211+37.0 56' LT	TO	213+65.00 44' LT	228						228			23	8
I-72 STAGE III														
EB REMOVAL	180+21.0 68' RT	TO	182+50.00 56' RT	229				76						
	182+50.0 56' RT	TO	183+76.00 56' RT	126				42						
	183+76.0 56' RT	TO	186+32.00 38' RT	256				84						
	188+03.0 6' RT	TO	188+31.00 0' RT	29				10						
	190+82.0 38' LT	TO	192+30.00 44' LT	148				49						
	192+30.0 44' LT	TO	202+52.00 44' LT	1,022				337						
	202+52.0 44' LT	TO	203+81.00 38' LT	129				43						
	205+97.0 0' RT	TO	206+25.00 6' RT	29				10						
	207+73.0 38' RT	TO	209+96.00 56' RT	223				74						
	180+21.0 44' RT	TO	183+76.00 44' RT	355				117						
	183+76.0 44' RT	TO	185+23.00 38' RT	147				49						
	187+75.0 0' LT	TO	188+03.00 6' LT	29				10						
	189+73.0 38' LT	TO	192+30.00 56' LT	257				85						
	192+30.0 56' LT	TO	202+52.00 56' LT	1,022				337						
	202+52.0 56' LT	TO	206+53.00 38' LT	401				132						
	206+22.0 0' RT	TO	206+50.00 6' RT	29				10						
	208+67.0 38' RT	TO	209+96.00 44' RT	129				43						
WB REMOVAL	183+76.0 68' LT	TO	185+47.00 68' LT	171				56						
	185+47.0 68' LT	TO	188+47.00 70' LT	29				10						
	188+47.0 70' LT	TO	204+85.00 70' LT	1,638				541						
	204+85.0 70' LT	TO	206+85.00 68' LT	200				66						
	206+85.0 68' LT	TO	213+65.00 68' LT	680				224						
	183+76.0 56' LT	TO	185+47.00 56' LT	29				10						
	185+47.0 56' LT	TO	188+47.00 60' LT	300				99						
	188+47.0 60' LT	TO	204+85.00 60' LT	1,638				541						
	204+85.0 60' LT	TO	206+85.00 56' LT	200				66						
	206+85.0 56' LT	TO	211+37.00 56' LT	452				149						
	211+37.0 56' LT	TO	213+65.00 56' LT	228				75						
EB	180+21.0 68' RT	TO	208+97.00 68' RT	2,876	2,876								288	95
	180+21.0 56' RT	TO	209+96.00 56' RT	2,975			744						298	98
	180+21.0 44' RT	TO	209+96.00 44' RT	2,975		2,975							298	98
WB	183+76.0 68' LT	TO	213+65.00 68' LT	2,989	2,989								299	99
	183+76.0 56' LT	TO	213+65.00 56' LT	2,989			747						299	99
	183+76.0 44' LT	TO	213+65.00 44' LT	2,989		2,989							299	99
EB	180+21.0 56' RT	TO	193+23.00 56' RT	1,302						33	33			
	201+41.0 56' RT	TO	209+96.00 56' RT	855						21	21			
WB	183+76.0 56' LT	TO	193+38.00 56' LT	962						24	24			
	201+57.0 56' LT	TO	213+65.00 56' LT	1,208						30	30			
TOTALS =					5,865	5,964	1,491	9,818	11,086	11,493	108	108	4,037	1,332

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.				
c:\pwork\pwork\sparksgw\10282050\0672\F01-sht-schedule.dgn	DRAWN -	REVISED -	72			(84-10-1)BDR	SANGAMON	35	8					
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 72F01											
PLOT DATE = Nov-01-2011 11:51:41AM	DATE -	REVISED -	ILLINOIS FED. AID PROJECT											
						SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.		