

SUMMARY OF QUANTITIES

PAY CODE	ITEM	UNITS	0011	
			80% FED.	20% STATE
			QUANTITY	
20100500	TREE REMOVAL, ACRES	ACRE	1.00	
20200100	EARTH EXCAVATION	CU YD	9835	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	90	
20300100	CHANNEL EXCAVATION	CU YD	383	
20400800	FURNISHED EXCAVATION	CU YD	25374	
21000310	GRANULAR EMBANKMENT, SPECIAL	CU YD	91	
25000200	SEEDING, CLASS 2	ACRE	4.5	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	405	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	405	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	405	
25100115	MULCH, METHOD 2	ACRE	4.5	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	900	
28000305	TEMPORARY DITCH CHECKS	FOOT	1242	
28000400	PERIMETER EROSION BARRIER	FOOT	4244	
28000500	INLET AND PIPE PROTECTION	EACH	4	
28100107	STONE RIPRAP, CLASS A4	SQ YD	2098	
28200200	FILTER FABRIC	SQ YD	3378	
28300400	AGGREGATE DITCH	TON	581	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	110	
35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	4486	
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	418	
35400520	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 12"	SQ YD	154	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	138	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	660	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	427	
40600990	TEMPORARY RAMP	SQ YD	93	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	528	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	194	
40701951	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/2"	SQ YD	3905	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2062	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	30	
50300300	PROTECTIVE COAT	SQ YD	1943	

SUMMARY OF QUANTITIES

PAY CODE	ITEM	UNITS	0011	
			80% FED.	20% STATE
			QUANTITY	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	1034	
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	1202	
44000400	GUTTER REMOVAL	FOOT	878	
44004250	PAVED SHOULDER REMOVAL	SQ YD	653	
44213200	SAW CUTS	FOOT	2021	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	873	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	989	
48203051	HOT-MIX ASPHALT SHOULDERS, 13 1/2"	SQ YD	635	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	
50105220	PIPE CULVERT REMOVAL	FOOT	352	
50200100	STRUCTURE EXCAVATION	CU YD	154.9	
50300100	FLOOR DRAINS	EACH	10.0	
50300225	CONCRETE STRUCTURES	CU YD	213.0	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	588.6	
50300260	BRIDGE DECK GROOVING	SQ YD	1574	
50300280	CONCRETE ENCASEMENT	CU YD	5.6	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	
50600505	STUD SHEAR CONNECTORS	EACH	5544	
50800105	REINFORCEMENT BARS	POUND	14220	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	177260	
50800515	BAR SPLICERS	EACH	1774	
51201610	FURNISHING STEEL PILES HP12X63	FOOT	448	
51202305	DRIVING PILES	FOOT	448	
51203610	TEST PILE STEEL HP12X63	EACH	2	
51204650	PILE SHOES	EACH	16	
51500100	NAME PLATES	EACH	1	
51603000	DRILLED SHAFT IN SOIL	CU YD	44	
51604000	DRILLED SHAFT IN ROCK	CU YD	14.6	
52100520	ANCHOR BOLTS, 1"	EACH	24	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	24	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	176	
54215559	METAL END SECTIONS 24"	EACH	4	

PRINTED DATE: 5/11/2011
 FILE NAME: c:\projects\vide\p1b 46, item 25 - d7 various design work, order 07, conch\drawings\Sheet's 03, R.06, 500, 1.dgn



USER NAME = USER#
 PLOT SCALE = 1:8000 / IN.
 PLOT DATE = 5/11/2011

DESIGNED - JEH, ADG
 DRAWN - JEH, ADG
 CHECKED - DF, PAT
 DATE - 05-11-2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF
 QUANTITIES**

SHEET NO 1 OF 2 SHEETS

F.A.P. RTE. 91	SECTION (58R)B-1	COUNTY COLES	TOTAL SHEETS 91	SHEET NO 3
CONTRACT NO 74244				
ILLINOIS FED. AID PROJECT				