

80% FED.  
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		FAP 325	FAP 325	COLES COUNTY	FAP 325	MOULTRIE
				RURAL IL 16 0005	URBAN IL 16 0005	URBAN US 45 0005	RURAL 0014	RURAL IL 16 0005
<del>Z0049799</del>	PROTECTING OR RESETTING SURVEY MARKERS	EACH	4	1	1	1		1
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	10	3				7
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	20534	8119	2402	2171		7842
40600300	AGGREGATE (PRIME COAT)	TON	410	162	48	43		157
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	4860	2383			6	2471
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	120					120
40600990	TEMPORARY RAMP	SQ YD	318		29	182	85	22
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	9919	4965			13	4941
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	4198	357	2017	1824		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	281	118				163
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	114691	55989				58702
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	52344	6616	24016	21712		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	152				152	
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	2527	757	465			1305
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	496	84	108			304
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	1087	27	773			287
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5197	2475				2722
48203100	HOT-MIX ASPHALT SHOULDERS	TON	3801	1811				1990
63200310	GUARDRAIL REMOVAL	FOOT	125					125
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.4	0.1	0.07	0.02	0.41