

80% FED.
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT		0005
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	334	334
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	84	84
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15271	15271
40600300	AGGREGATE (PRIME COAT)	TON	305	305
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3207	3207
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	599	599
40600990	TEMPORARY RAMP	SO YD	474	474
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	6804	6804
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	77	77
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	20418	20418
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SO YD	35	35
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	1219	1219
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	22	22
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	400	400
44201835	CLASS D PATCHES, TYPE I, 16 INCH	SO YD	20	20
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SO YD	903	903
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SO YD	65	65
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SO YD	326	326
48101200	AGGREGATE SHOULDERS, TYPE B	TON	793	793
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	16	16
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	7530	7530
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	837	837
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	73472	73472
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	314	314
X4060995	TEMPORARY RAMP, SPECIAL	SO YD	138	138
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	55338	55338

*SPECIALTY ITEM

FILE NAME =	USER NAME = administrator	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\ps_work\p\p\dot\swartzra\d08148615\077415-sht-sec.dgn		DRAWN -	REVISED -			752	(23-2)RS-1,(W,V)RS-2	FAYETTE	13	3
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -			CONTRACT NO. 74415				
PLOT DATE = 10/27/2011		DATE -	REVISED -			SCALE: NA	SHEET 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT