



TYPICAL SECTION AT MAILBOX TURNOUT
NOTE: SEE STANDARD 406201 FOR MAILBOX TURNOUT DETAILS

NOTES

THE COST OF THE ASPHALT MATERIALS, AND AGGREGATE (PRIME COAT) FOR ENTRANCES AND PUBLIC ROADS AND APPROACHES SHALL BE INCLUDED IN THE PAY ITEM INCIDENTAL HOT-MIX ASPHALT SURFACING.

THE COST OF EXCAVATION IS INCLUDED IN THE PAY ITEM INCIDENTAL HOT-MIX ASPHALT SURFACING.

IF THERE IS NOT EXISTING HOT-MIX ASPHALT SHOULDER THEN THE ENTRANCE TAPER STARTS AT THE EDGE OF EXISTING PAVEMENT.

THE COST OF THE BITUMINOUS MATERIALS AND AGGREGATE (PRIME COAT) FOR ENTRANCES AND PUBLIC ROAD APPROACHES SHALL BE INCLUDED IN THE PAY ITEM INCIDENTAL HOT-MIX ASPHALT SURFACING.

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	
			TON	TON
LT	54+07	PRA	3.2	
RT	56+30	FE		2.1
RT	64+76	PRA	3.6	
RT	78+90	FE		1.8
RT	88+46	PE		2.2
LT	91+13	PRA	2.7	
RT	99+67	CE	2.1	
RT	100+30	CE	2.1	
RT	101+21	PE		2.2
LT	104+40	PE		1.4
LT	104+61	PE		2.3
LT	110+06	PE		1.8
LT	111+42	FE		1.8
RT	111+94	CE		3.6
LT	112+10	PE		1.4
RT	112+32	PE		1.8
LT	112+94	PRA	3.0	
RT	114+61	CE	4.2	
LT	115+86	PRA	4.0	
RT	115+94	CE	4.0	

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	
			TON	TON
LT	117+85	CE		3.1
RT	118+58	CE	3.3	
LT	118+78	PRA	3.5	
RT	119+23	CE	2.1	
RT	120+66	PRA	5.3	
RT	122+87	PE		1.7
LT	124+54	PE		1.6
LT	124+81	PE		1.7
LT	126+12	CE		2.3
RT	126+61	CE	1.8	
LT	126+89	PE		1.8
RT	129+92	CE	3.5	
RT	131+15	CE	1.5	
RT	132+22	CE	2.7	
LT	132+70	PRA	6.8	
RT	133+27	PE		1.2
RT	133+86	CE		3.6
RT	133+97	PE		1.2
LT	134+44	PE		1.5
LT	135+69	PE		3.0

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	
			TON	TON
LT	136+09	PE		1.3
LT	137+65	PE		3.6
LT	138+17	PE		1.7
LT	139+62	PE		2.0
LT	140+75	PE		1.8
LT	142+67	PE		2.4
LT	145+62	PE		2.7
RT	146+08	FE		1.4
LT	146+48	PE	2.0	
RT	151+48	FE		1.2
LT	152+38	PE		4.0
RT	164+80	PE	2.1	
RT	172+09	FE		3.0
RT	173+52	PE		2.7
LT	0+12	FE		2.5
LT	7+59	PE		2.1
LT	12+50	PE	1.9	
LT	28+87	PE		3.5
LT	31+44	PE	3.6	
RT	104+53	PE		3.5

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	
			TON	TON
LT	105+40	PRA	3.2	
RT	105+80	CE	5.4	
TOTALS:			77	84

FE=FIELD ENTRANCE PRA - PUBLIC ROAD APPROACH
PE=PRIVATE ENTRANCE MBT - MAILBOX TURNOUT
CE=COMMERCIAL ENTRANCE

FILE NAME =	USER NAME = administrator	DESIGNED - 08-03-99	REVISED -
ca:\pw\work\pw\dot\swartz\va0148615\077415-shd-details.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 10/27/2011	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**RURAL ENTRANCE SCHEDULE AND MAILBOX TURNOUT DETAILS
WITH SHOULDERS**

SCALE: NA SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
752	(23-2)RS-1, (W.V)RS-2	Fayette	13	9
CONTRACT NO. 74415			ILLINOIS FED. AID PROJECT	