

SUMMARY OF QUANTITIES			90% FED 10% STATE CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			90% FED. 10% STATE CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 SHELBY CO.	0005 CUMBERLAND CO.	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 SHELBY CO.	0005 CUMBERLAND CO.
20400800	FURNISHED EXCAVATION	CU YD	46		46	63500105	DELINEATORS	EACH	248	99	149
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	83078	35020	48058	64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	183214	78796	104418
40600300	AGGREGATE (PRIME COAT)	TON	831	350	481	66101150	HOT-MIX ASPHALT SHOULDER CURB	FOOT	1418		1418
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	2	4
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2080		2080	67100100	MOBILIZATION	L SUM	1	1	
40600990	TEMPORARY RAMP	SQ YD	691	118	573	70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2		2
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	33299	14777	18522	70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.5	0.5
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	21353	8874	12479	70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.5	0.5
44213100	PAVEMENT FABRIC	SQ YD	738	530	208	70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	0.5	0.5
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	227733	85677	142056	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	41	17	24
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	5600	5600		70300100	SHORT TERM PAVEMENT MARKING	FOOT	66836	28367	38469
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	19124	18241	883	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	213096	88645	124451
44000300	CURB REMOVAL	FOOT	1418		1418	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5496	2364	3132
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	3321	1199	2122	* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	104		104
44201011	CLASS B PATCHES, TYPE III, 13 INCH	SQ YD	271	183	88	* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	92		92
44201013	CLASS B PATCHES, TYPE IV, 13 INCH	SQ YD	467	347	120	* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	36		36
44201299	DOWEL BARS 1 1/2"	EACH	7920	3010	4910	* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	190194	78795	111399
44213200	SAW CUTS	FOOT	20425	8000	12425	* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	22902	9850	13052
44213204	TIE BARS 3/4"	EACH	198	142	56	* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2343	1027	1316
48101200	AGGREGATE SHOULDERS, TYPE B	TON	6461	2710	3751	* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	205	61	144
48203100	HOT-MIX ASPHALT SHOULDERS	TON	30076	12056	18020	* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	39	14	25
60260100	INLETS TO BE ADJUSTED	EACH	6		6	* X0323583	SPEED INDICATOR SIGN	CAL DA	180	77	103
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	10000	2925	7075	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	11467	2867	8600
* 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	1363		1363	* X6311217	TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL)	EACH	2		2
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	25	12	13	X6350120	DELINEATOR REMOVAL	EACH	495	197	298
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2		2	* Z0008758	AERIAL SPEED CHECK MARKING	FOOT	48		48
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4		4	Z0034105	MATERIAL TRANSFER DEVICE	TON	54,652	23,651	31,001
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	3		3	Z0076600	TRAINEES	HOUR	500	200	300
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	6	4	2						
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	38	14	24						
63200310	GUARDRAIL REMOVAL	FOOT	15123	4141	10982						
* 63400105	GUARD POSTS	EACH	9	3	6						

\*SPECIALTY ITEM

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw\work\p\dot\teasleyck\10264695\07	4467-ght-seq.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	57	.	.	32	3
	PLOT SCALE = 50.0000 1/4 in.	CHECKED -	REVISED -					CONTRACT NO. 74467				
	PLOT DATE = 9/29/2011	DATE -	REVISED -					ILLINOIS FED. AID PROJECT				