



GUARDRAIL SCHEDULE

STATIONING		DIRECTION	SIDE	LENGTH (FEET)	STEEL PLATE BEAM GUARDRAIL, TYPE A (FEET)	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 2 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 6B (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL) (EACH)	GUARDRAIL MARKER, TYPE A (EACH)	TERMINAL MARKER - DIRECT APPLIED (EACH)
FROM	TO										
5835+30.25	5837+30.25	NB	DL	200.00	37.5	1	1	-	1	2	1
5835+87.50	5839+81.25	SB	DL	393.75	287.5	1	-	1	-	6	1
SHEET TOTALS:					325.0	2	1	1	1	8	2

GUARDRAIL REMOVAL

STATIONING		DIRECTION	SIDE	LENGTH (FEET)
FROM	TO			
5833+09	5837+77	NB	DL	468
5835+95	5839+40	SB	DL	345
SHEET TOTAL:				813

- TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT: STA 5835+30.25 TO STA 5835+80.25
- TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL): STA 5835+80.25 TO 5836+80.25
- STEEL PLATE BEAM GUARDRAIL, TYPE A: STA 5836+80.25 TO 5837+17.75
- TRAFFIC BARRIER TERMINAL, TYPE 2: STA 5837+17.75 TO STA 5837+30.25

HMA SURFACE REMOVAL - BUTT JOINT

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PLAN SHEET STA 5820+00 TO STA 5850+00	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cs:\pv_work\pwidot\teasleyck\d0264695\07	4467-shr-plan.dgn	DRAWN -	REVISED -			57	87-IRS-1	•	32	17
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 74467				
	PLOT DATE = 9/29/2011	DATE -	REVISED -			ILLINOIS FED. AID PROJECT				