

SUMMARY OF QUANTITIES			TOTAL QUANTITIES URBAN	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		20% STATE 80% FED.	CITY 100%	80% FED. 20% STATE BRIDGE 058-0037
20049799	PROTECTING OR RESETTING SURVEY MARKERS	EACH	21	21		
20200100	EARTH EXCAVATION	CU YD	174	174		
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	548	548		
35300610	PORTLAND CEMENT CONCRETE BASE COURSE 11 1/2"	SQ YD	123	123		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2332	2284	48	
40600300	AGGREGATE (PRIME COAT)	TON	10	10		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600990	TEMPORARY RAMP	SQ YD	173	84	89	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	3917	3837	80	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	46633	45680	953	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1123	1123		
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	157	157		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	161	161		
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	54	54		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	31	31		
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	25	25		
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	61	61		
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	110	110		
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	36	36		
50102400	CONCRETE REMOVAL	CU YD	19.1			19.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	19.1			19.1
50300300	PROTECTIVE COAT	SQ YD	52			52
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2640			2640
50800515	BAR SPLICERS	EACH	16			16
52000110	PREFORMED JOINT STRIP SEAL	FOOT	167			167
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	1097	1097		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	4096	4096		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2		2
67100100	MOBILIZATION	L SUM	1	1		
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1		

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\swartzw\d0212489\d774500-sht-soq.dgn		DRAWN -	REVISED -			716	(127R,RS-2)(130R-2,RS-1)	MACON	98	4	
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -			CONTRACT NO. 74500					
PLOT DATE = 10/11/2011		DATE -	REVISED -			SCALE: NA	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	