

SUMMARY OF QUANTITIES (Cont'd)			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED. STATE 20% STATE	CITY 100%	80% FED. 20% STATE BRIDGE 058-0037
			URBAN	0005	0005	0014
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	28			28
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1			1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	26612	26612		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	893	893		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	23018	22928	90	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4239	4050	189	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3313	2851	462	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	369	312	57	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	16585	15889	696	
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1590			1590
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	89			89
78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	14			14
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	544	544		
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	28			28
78200300	PRISMATIC CURB REFLECTOR	EACH	85	85		
78300100	PAVEMENT MARKING REMOVAL	SO FT	924			924
88600100	DETECTOR LOOP, TYPE I	FOOT	2832	2320	512	
80325022	AGGREGATE BACKFILL	TON	870	870		
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	4628	4628		
50800530	MECHANICAL SPLICERS	EACH	128			128
X7010200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316 (SPECIAL)	EACH	1			1
X7801000	WET REFLECTIVE PAVEMENT THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	893	893		
X7801004	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21427	21337	90	
X7801006	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4239	4050	189	
X7801012	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3231	2769	462	
X7801024	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	355	298	57	
Z0012500	CONCRETE CURB REPAIR	FOOT	56	56		
Z0018004	DRAINAGE SCUPPERS, DS-12	EACH	12			12
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
Z0070202	SURVEY MARKER VAULT	EACH	4	4		

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\swartzw\d0212489\d77508-shr-soq.dgn		DRAWN -	REVISED -		SCALE: NA	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	716	(127R,RS-2)(130R-2,RS-1)	MACON	98	5
		CHECKED -	REVISED -		CONTRACT NO. 74500								
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								