

AGGREGATE BACKFILL SCHEDULE

LOCATION	AREA SQ FT	DEPTH FT.	AREA SQ YD	QTY TON
IL 48				
54+27.46 TO 59+87.96 MEDIAN	4037.72	1.21	180.70	370.43
Total =				370.4

CONCRETE MEDIAN SURFACE REMOVAL SCHEDULE

LOCATION	AREA SQ FT
IL 48	
54+27.46 TO 59+87.96 MEDIAN	4627.78
Total =	
4,627.8	

COMBINATION CONCRETE CURB & GUTTER,
TYPE B-6.06 SCHEDULE

LOCATION	LENGTH FOOT
IL 48	
54+33.45 TO 59+82.06 MEDIAN	1,097.0
Total =	
1,097.0	

CONCRETE MEDIAN SURFACE, 4" SCHEDULE

LOCATION	AREA SQ FT
IL 48	
54+27.46 TO 59+87.96 MEDIAN	4095.67
Total =	
4,095.7	

EPOXY PAVEMENT MARKING SCHEDULE		LENGTH	EPOXY PAVEMENT MARKING-LINE 4" (YELLOW)	EPOXY PAVEMENT MARKING-LINE 12" (YELLOW)	EPOXY PAVEMENT MARKING-LINE 24" (WHITE)
STATION TO	STATION	FEET	FOOT	FOOT	FOOT
IL 48					
910+22.58	TO 912+46.00	223.42	446.8		
912+46.00	TO 915+29.50	283.50	1,143.6	89.1	14.1
PROJECT TOTALS		507	1,590	89	14

CURB & GUTTER REMOVAL SCHEDULE

LOCATION	LENGTH FEET
IL 48	
54+27.46 TO 59+87.96 MEDIAN	1122.9
Project Total =	
1,122.9	

CONCRETE CURB REPAIR SCHEDULE

LOCATION	TYPE	QUANTITY (FOOT)
IL 48		
49+50.00 TO 53+60.10	B6.12	56.0
TOTAL =		56.0