

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE 0011		CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FED. 20% STATE 0011	
20200100	EARTH EXCAVATION	CU YD	1301	1301		*6300025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	62.5	62.5	
20300100	CHANNEL EXCAVATION	CU YD	192	192		*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
20400800	FURNISHED EXCAVATION	CU YD	117	117		63200310	GUARDRAIL REMOVAL	FOOT	895	895	
*25000200	SEEDING, CLASS 2	ACRE	1	1		66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	10	10	
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	99	99		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	99	99		67100100	MOBILIZATION	L SUM	1	1	
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	99	99		70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
*25100115	MULCH, METHOD 2	ACRE	4	4		70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
25100630	EROSION CONTROL BLANKET	SQ YD	429	429		70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	241	241		70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
28000305	TEMPORARY DITCH CHECKS	FOOT	163	163		70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6	
28000400	PERIMETER EROSION BARRIER	FOOT	526	526		70300100	SHORT TERM PAVEMENT MARKING	FOOT	504	504	
28100107	STONE RIPRAP, CLASS A4	SQ YD	246	246		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1809	1809	
28100203	STONE RIPRAP, CLASS A2	TON	10	10		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	675	675	
28200200	FILTER FABRIC	SQ YD	246	246		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1109	1109	
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	528	528		70400100	TEMPORARY CONCRETE BARRIER	FOOT	350	350	
35501317	HOT-MIX ASPHALT BASE COURSE, 8 1/4"	SQ YD	519	519		70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	325	325	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.7	0.7		72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	6	6	
40600300	AGGREGATE (PRIME COAT)	TON	4	4		*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2140	2140	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	174	174		*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	13	13	
40600990	TEMPORARY RAMP	SQ YD	29	29		*78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	526	526		*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	227	227		78300100	PAVEMENT MARKING REMOVAL	SQ FT	80	80	
44000100	PAVEMENT REMOVAL	SQ YD	126	126		*78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	13	13	
44004250	PAVED SHOULDER REMOVAL	SQ YD	264	264		X7200200	WIDE LOAD SIGNING	L SUM	1	1	
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	421	421		Z0026407	TEMPORARY SHEET PILING	SQ FT	2933	2933	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	93	93		Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1		Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
50800105	REINFORCEMENT BARS	POUND	28690	28690		Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1	1	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	18490	18490		+ Z0076600	TRAINEES	HOOR	500	500	
51500100	NAME PLATES	EACH	1	1							
54003000	CONCRETE BOX CULVERTS	CU YD	192.6	192.6							
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	887.5	887.5							

* SPECIALTY ITEM + 0842

FILE NAME =	USER NAME = tharpr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 680	SECTION 47-1BR	COUNTY ST. CLAIR	TOTAL SHEETS 44	SHEET NO. 3
ct:\pwork\pdat\tharpr1\dms24868\0876889-sh4-500.dgn		DRAWN -	REVISED -							
PLOT SCALE = 50,0000' / 1"		CHECKED -	REVISED -							
PLOT DATE = 10/20/2011		DATE -	REVISED -		SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT
										CONTRACT NO. 76388