

PAVEMENT MARKINGS AND PAVEMENT MARKERS													
LOCATION		INLAID					GROOVED			PAVEMENT MARKERS			
		4" SOLID YELLOW	4" SKIP-DASH WHITE	4" SOLID WHITE	8" SOLID WHITE	8" SKIP-DASH WHITE	4" SOLID YELLOW	4" SKIP-DASH WHITE	4" SOLID WHITE	ONEWAY RAISED REFLECTIVE PAVEMENT MARKERS, CRYSTAL	ONEWAY RAISED REFLECTIVE PAVEMENT MARKERS, CRYSTAL (BRIDGE)		
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH			
IL ROUTE 15													
657+54.70	TO	687+88.92	EB	3008.5	758.6	3059.0				76			
668+50.00	TO	686+51.78	WB	1827.5	450.5	1776.0				44			
686+51.78	TO	689+93.06	WB				341.5	85.3	341.5		8		
687+88.92	TO	691+29.80	EB				341.5	85.3	341.5		8		
691+29.80	TO	704+00.23	EB	1296.0	317.6	1244.0				32			
689+93.06	TO	702+54.26	WB	1235.0	315.3	1286.5				32			
702+54.26	TO	711+95.53	WB				942.5	235.3	943.5		24		
704+00.23	TO	712+62.22	EB				860.0	215.5	857.5		24		
711+95.53	TO	723+70.20	WB	1242.1	293.9	1257.0				193.0			
712+62.22	TO	723+80.50	EB	1118.3	279.6	1118.3				126.3			
723+70.20	TO	724+64.60	WB				94.5	23.7	94.5		4		
723+80.50	TO	724+76.80	EB				96.5	24.1	96.5		4		
724+64.60	TO	755+60.38	WB	3096.0	774.0	3096.0					76		
724+76.80	TO	744+60.00	EB	1995.4	495.8	1995.4					50		
SUBTOTAL				14818.8	3685.2	14832.2	193.0	126.3	2676.5	669.1	2675.0	370	72
PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE, 4"						33,336.5							
PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE, 8"						319.5							
PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE, 4"						6,020.5							
GROOVING FOR RECESSED PAVEMENT MARKING 5"						6,020.5							
RAISED REFLECTIVE PAVEMENT MARKERS						370							
RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE)						72							
RAISED REFLECTIVE PAVEMENT MARKERS ARE SPACED AT 2 EACH FOR EVERY 80' ALONG LANE LINES.													

MARKERS AND DELINEATORS					
LOCATION		GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKER, TYPE C	DELINEATORS	
				EACH	EACH
IL ROUTE 15					
EASTBOUND					
698+24.23	TO	705+05.00	LT.	5	
691+81.00	TO	705+28.00	RT.	7	
705+05.00	TO	708+85.00	LT.		4
705+28.00	TO	709+08.00	RT.		4
708+99.06	TO	709+46.02	LT.	1	
709+22.36	TO	710+14.00	RT.	1	
709+90.00	TO	711+21.00	LT.		2
710+14.00	TO	711+46.00	RT.		2
711+60.78	TO	724+02.60	RT.	9	
711+21.00	TO	718+25.00	LT.		4
718+74.68	TO	723+51.55	LT.	5	
WESTBOUND					
690+03.00	TO	703+57.00	LT.	7	
699+00.00	TO	701+15.00	RT.		1
701+15.00	TO	703+80.00	RT.	4	
703+57.00	TO	707+36.00	LT.		4
703+80.00	TO	707+59.00	RT.		4
707+36.00	TO	709+25.00	LT.	1	
707+57.00	TO	709+49.00	RT.	1	
709+25.00	TO	710+53.00	LT.		2
709+49.00	TO	710+79.00	RT.		2
710+53.00	TO	718+09.84	LT.	7	
710+79.00	TO	714+70.14	RT.	4	
715+20.00	TO	723+69.93	RT.		5
RAMP					
18+00.00	TO	21+98.42	LT.		6
SUBTOTAL				52	24
GUARDRAIL MARKERS, TYPE A				52	
BARRIER WALL MARKER, TYPE C				24	
DELINEATORS				16	
DELINEATORS SPACED AT 175 FT INTERVALS ON IL 15 CURVE AND AT 175 FT TO 70 FT INTERVALS ON RAMP. GUARDRAIL MARKERS AND BARRIER WALL MARKERS ARE SPACED AT 80 FT FOR THE FIRST 400 FT, SPACED AT 175 FT INTERVALS ON IL 15 CURVE AND AT 400 FT INTERVALS ON TANGENT SECTION.					

PAVEMENT MARKING REMOVAL						
LOCATION		4" SKIP DASH WHITE (SQ FT)	4" SOLID YELLOW (SQ FT)	4" SOLID WHITE (SQ FT)	8" SOLID WHITE (SQ FT)	8" SKIP DASH WHITE (SQ FT)
657+55.00	TO 700+00.00	EB	354	1415	1415	
673+50.00	TO 755+60.00	WB	684	2737	2737	130
723+81.00	TO 744+60.00	EB	173	693	693	
SUBTOTAL			1211	4845	4845	130
TOTAL			11,052			

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL			
LOCATION		EACH*	
657+55.00	TO 700+00.00	EB	53
673+50.00	TO 755+60.00	WB	103
723+81.00	TO 744+60.00	EB	26
TOTAL			182
*IT IS ASSUMED TO BE ONE PAVEMENT MARKER EVERY 80' OF PAVEMENT MARKING.			

CHANGEABLE MESSAGE SIGN		
LOCATION	CHANGEABLE MESSAGE SIGN (MONTH)	
IL ROUTE 15		
EASTBOUND	24	
WESTBOUND	24	
TOTAL		48

FILE NAME = D876884-sht-schedule.dgn	USER NAME = thompersd	DESIGNED GC	REVISED -
	MODEL NAME = \$MODELNAME\$	DRAWN RDT	REVISED -
	PLOT SCALE = 20.000' / IN.	CHECKED JAP	REVISED -
	PLOT DATE = 10/20/2011	DATE 10-19-11	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 5 OF 5 SHEETS STA. ----- TO STA. -----

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	27-1-VHB-1	ST. CLAIR	277	12
CONTRACT NO. 76884				
ILLINOIS FED. AID PROJECT				