

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 ALTON 3P	0005 MADISON COUNTY 3P	0004 MADISON COUNTY 3R	0021 SIGNALS				
72000100	SIGN PANEL - TYPE 1	SQ FT	36			36					
73000100	WOOD SIGN SUPPORT	FOOT	60			60					
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1360.2	923.4	62.4	374.4					
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	112989	88012	11257	13720					
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1756	1756							
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	817	693		124					
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1740	1580	80	80					
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	62.4	62.4							
78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	2160	2160							
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	96	96							
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	967	663	70	234					
78200300	PRISMATIC CURB REFLECTOR	EACH	480	418	62						
78200410	GUARDRAIL MARKERS, TYPE A	EACH	48	8	40						
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	2	6						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	778	622	70	86					
80300100	LOCATING UNDERGROUND CABLE	FOOT	345	295	50						
88600600	DETECTOR LOOP REPLACEMENT	FOOT	6263	5493	770						
X4421000	PARTIAL DEPTH PATCHING	TON	917.9	603.2	75.4	239.3					
X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SQ FT	2160	2160							
X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	72	72							
X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 2.5"	FOOT	62.4	62.4							
64300260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2		2						
Z0041700	PLUG EXISTING STORM SEWERS	EACH	5			5					
Z0076600	TRAINEES	HOUR	2000	2000							

FILE NAME =	USER NAME = karjassl	DESIGNED -	REVISED -
et:\pw_work\pwwdot\karjassl\d0280664\d0280664\2-shr\plan.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0000' / in.		CHECKED -	REVISED -
PLOT DATE = 9/12/2011		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	(132-2,3,4 133-1)RS	MADISON	122	6
CONTRACT NO. 76B80			ILLINOIS FED. AID PROJECT	