

SHORT TERM PM AND WORK ZONE PM REMOVAL

LOCATION/DESCRIPTION	SHORT TERM PAVEMENT MARKING	WORKZONE P.M.
	(FT)	(SQ FT)
START PROJECT TO WORDEN AVE.	648	54
WORDEN AVE. TO KENDALL AVE/JACKSON ST.	600	50
KENDALL AVE/JACKSON ST TO RODGER ST.	1776	148
RODGERS SIDEROADS	96	8
RODGERS ST. TO HAP SOUTHBOUND RAMPS	1020	85
SOUTHBOUND RAMPS TO HAP	96	8
SOUTHBOUND RAMPS TO NORTHBOUND RAMPS (HAP)	672	56
NORTHBOUND RAMPS TO HAP	96	8
NORTHBOUND RAMPS HAP TO SN 060-0199	768	64
SN 060-0199 TO SN 060-0091	540	45
SN 060-0091 TO FOSTERBURG ROAD	780	65
FOSTERBURG ROAD	288	24
FOSTERBURG ROAD TO GRASS MEDIAN	1344	112
START OF GRASS MEDIAN TO PARK ROAD INTERSECTION	2340	195
PARK ROAD INTERSECTION	384	32
PARK ROAD INTERSECTION TO POWDER MILL ROAD INT.	624	52
POWDER MILL ROAD INT.	372	31
POWDER MILL ROAD INT. TO STANLEY ROAD INT.	432	36
STANLEY ROAD INT.	480	40
STANLEY INT. TO SN 060-0190 & 060-0187	204	17
SN 060-0190 & 060-0187 TO THELMA & FRANKLIN ST.	312	26
THELMA/FRANKLIN ST. INTERSECTION.	204	17
3R IMPROVEMENT (STA. 469+00 TO STA. 500+00)	1680	140
TOTAL	15756	1313

TRENCH BACKFILL

LOCATION	TRENCH BACKFILL (CY)
STA. 474+20 RT TO STA. 476+53 RT	52
STA. 479+53 RT TO STA. 485+44 RT	132
TOTAL	184

REMOVING AND FILLING MANHOLES

LOCATION/DESCRIPTION	REMOVING MANHOLES (EACH)	FILLING MANHOLES (EACH)
STA. 474+20.4 8.0 RT	1	1
STA. 474+82.4 8.2 RT	1	1
STA. 475+42.4 8.3 RT	1	1
STA. 475+97.6 8.4 RT	1	1
STA. 476+53 8.2 RT	1	1
STA. 476+96.9 3.3 RT	1	1
STA. 476+98.2 8.2 RT	1	1
STA. 477+94.6 8.3 RT	1	1
STA. 479+53.2 8.1 RT	1	1
STA. 480+38.9 8.2 RT	1	1
STA. 481+24.2 8.3 RT	1	1
STA. 482+09.1 8.3 RT	1	1
STA. 483+00.1 8.3 RT	1	1
STA. 483+83.2 8.3 RT	1	1
STA. 484+64.6 8.3 RT	1	1
STA. 485+43.5 8.3 RT	1	1
STA. 486+22.1 7.8 RT	1	1
TOTAL	17	17

STORM SEWER REMOVAL 12"

LOCATION	STORM SEWER REMOVAL 12" (FT)
STA. 474+20 RT TO STA. 476+53 RT	233
STA. 479+53 RT TO STA. 485+44 RT	591
TOTAL	824

BI-DIRECTIONAL SIGNING

STATION (SIDE)	SIZE (SQ FT)	SIGN PANEL TYPE 1 (SQ FT)	WOOD SIGN SUPPORT (FT)	SIGN DESCRIPTION
STA. 469+00 (RT)	6	6	10	R3-9B
STA. 476+00 (RT)	6	6	10	R3-9B
STA. 480+50 (RT)	6	6	10	R3-9B
STA. 482+50 (LT)	6	6	10	R3-9B
STA. 488+50 (LT)	6	6	10	R3-9B
STA. 497+50 (LT)	6	6	10	R3-9B
TOTAL	36	36	60	

REVISIED SHEET 4/13/11