

**INDEX OF SHEETS**

- 1 COVER SHEET
- 2 INDEX OF SHEETS, HIGHWAY STANDARD AND GENERAL NOTES
- 3 SUMMARY AND SCHEDULE OF QUANTITIES
- 4 DETAILED LOCATION MAP AND BUILDING REMOVAL KEY
- 5 PARCEL AND REMOVAL DETAILS
- 6 UTILITY LOCATION PLAN

**HIGHWAY STANDARDS**

| STANDARD NO. | DESCRIPTION  |
|--------------|--|
| 000001-06    | STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS                                 |
| 001006       | DECIMAL OF AN INCH AN OF A FOOT  |
| 280001-06    | TEMPORARY EROSION CONTROL SYSTEMS  |
| 701001-02    | OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5 m) AWAY                        |
| 701006-03    | OFF-RD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24" (600 mm) FROM EDGE OF PAVEMENT |
| 701801-05    | SIDEWALK, CORNER OR CROSSWALK CLOSURE  |
| 701901-02    | TRAFFIC CONTROL DEVICES  |

**GENERAL NOTES**

1. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E., OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS :
  - AMEREN CIPS (ELECTRIC)
  - AMEREN IP (GAS)
  - AT&T ILLINOIS (COMMUNICATIONS)
  - CITY OF EAST ST. LOUIS (SAN. SEWER)
  - ILLINOIS AMERICAN WATER CO. (WATER)
  - METRO (COMMUNICATIONS)
  - PAETEC (COMMUNICATIONS)
  - QWEST SOLUTIONS CENTER (COMMUNICATIONS)

MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY \* .  
NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
2. DURING THE BUILDING REMOVAL, NO SOIL SHALL BE DISTURBED DURING THE REMOVAL PROCESS. ALL REMOVAL OPERATIONS SHALL BE CONFINED TO AREAS WITH CONCRETE OR BITUMINOUS SURFACE TREATMENTS.
3. THE PERIMETER EROSION BARRIER IS TO BE PLACED AROUND PERIMETER OF EACH LOCATION AT THE DIRECTION OF THE RESIDENT ENGINEER.
4. THE CONTRACTOR WILL BE RESPONSIBLE FOR MAINTAINING ENTRANCES/ EXITS TO EACH SITE, AS WELL AS CLEANING OF THE ROADS LEADING TO SAID ENTRANCES/ EXITS TO EACH LOCATION. NO COMPENSATION WILL BE MADE FOR THIS WORK.
5. THE BUILDING FOOTING/BASEMENT SHALL BE FILLED BACK TO EXISTING GRADE WITH ACCEPTABLE FILL ACCORDING TO STANDARD SPECIFICATION ARTICLE 205.06. THIS COST IS TO BE INCLUDED IN THE BUILDING REMOVAL OF THAT NUMBER AND NO ADDITIONAL COMPENSATION WILL BE MADE.
6. ALL "STATE PROPERTY" SIGNS SHALL BE REMOVED AND RETURNED TO THE MRB COMPLEX, ATTENTION TO CHAD SANDERS.

|  |                            |             |             |   |  |             |              |           |                     |                           |  |
|--|----------------------------|-------------|-------------|---|--|-------------|--------------|-----------|---------------------|---------------------------|--|
| FILE NAME =<br>D8TRI-76F30-shr-gennote.dgn | USER NAME = pimerno        | DESIGNED OP | REVISED -   | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>INDEX OF SHEETS, HIGHWAY STANDARD AND GENERAL NOTES</b> | F.A.U. RTE. | SECTION      | COUNTY    | TOTAL SHEETS        | SHEET NO.                 |  |
|  | PLOT SCALE = 2.0000' / in. | CHECKED DBM | REVISED -   |   |  | 9214        | 82-1-12DM    | ST. CLAIR | 6                   | 2                         |  |
| PLOT DATE = 11/30/2011                     | DATE 11-30-11              | REVISED -   | SCALE: NONE |   | SHEET NO. 1 OF 1 SHEETS                                    |             | STA. TO STA. |           | FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT |  |
|  |                            |             |             |   |  |             |              |           | CONTRACT NO. 76F30  |                           |  |