

30/20 100/55

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	UNION COUNTY STP FUNDING	
				CONST. CODE 0040	SN 091-7090 (P)
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	25		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	406		
25000115	SEEDING, CLASS 1B	ACRE	0.1		
25000350	SEEDING, CLASS 7	ACRE	0.1		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9		
25000500	PHOSOPHORUS FERTILIZER NUTRIENT	POUND	9		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9		
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.2		
25100115	MULCH, METHOD 2	ACRE	0.1		
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	12		
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	13		
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	103		
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 19.0.N105	TON	71		
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D".N105	TON	18		
42300100	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 5 INCH	SQ YD	58		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	592		
44000100	PAVEMENT REMOVAL	SQ YD	206		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	54		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	99		
44000600	SIDEWALK REMOVAL	SQ FT	539		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		
50200100	STRUCTURE EXCAVATION	CU YD	681		
50800205	REINFORCEMENT BARS (EPOXY COATED)	POUND	1080		

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	UNION COUNTY STP FUNDING	
				CONST. CODE 0040	SN 091-7090 (P)
50901720	BICYCLE RAILING	FOOT	55		
54003000	CONCRETE BOX CULVERTS	CU YD	14.1		
54011004	PRECAST CONCRETE BOX CULVERTS 10' X 4'	FOOT	86		
54248510	CONCRETE COLLAR	CU YD	5.7		
550A0120	STORM SEWER, CLASS A, TYPE 1 24"	FOOT	11		
550A0190	STORM SEWER, CLASS A, TYPE 1 48"	FOOT	64		
55101200	STORM SEWER REMOVAL 24"	FOOT	6		
55101900	STORM SEWER REMOVAL 48"	FOOT	18		
60224030	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 15 FRAME AND LID	EACH	1		
60224446	MANHOLES, TYPE A, 7' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		
60224459	MANHOLES, TYPE A, 8' -DIAMETER, TYPE 1 FRAME , CLOSED LID	EACH	1		
60404800	FRAMES AND GRATES, TYPE 11	EACH	1		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-G.24	FOOT	99		
67100100	MOBILIZATION	L SUM	1		
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	40		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	16		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	103		
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	103		
Z0055905	TEMPORARY CONSTRUCTION FENCE	FOOT	200		

△ REVISED 1-5-12

FILE NAME =	USER NAME = dederdingg	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pkidot\dederdingg\d0265173\	8255_sht_091-7046.plndgn	DRAWN -	REVISED -					885	13B-1	UNION	14	3
	PLOT SCALE = 50.0000 // in.	CHECKED -	REVISED -					CONTRACT NO. 78255				
	PLOT DATE = 10/20/2011	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	ILLINOIS FED. AID PROJECT