

# CONSTRUCTION PLANS

## FOR

# LITCHFIELD MUNICIPAL AIRPORT

## LITCHFIELD, MONTGOMERY COUNTY, ILLINOIS

### REPLACE MRL'S ON RUNWAY 9-27

SCOPE OF WORK

THIS PROJECT CONSISTS OF THE REMOVAL AND REPLACEMENT OF THE MEDIUM INTENSITY LIGHTING SYSTEM ON RUNWAY 9-27 AND TAXIWAY A. INCLUDED WITH THIS WORK WILL BE REMOVAL AND REPLACEMENT OF THE REILS ON RUNWAY END 9, REMOVAL OF REILS ON RUNWAY END 27, AND THE ASSOCIATED CABLING, DUCT WORK AND VAULT WORK.

ADDITIVE ALTERNATE NO. 1

INSTALLATION OF A LIGHTED L-807 PRIMARY WIND CONE WITH THE ASSOCIATED CABLING, POWER AND CONTROL WORK.


ADDITIVE ALTERNATE NO. 2

ADDITION OF OBSTRUCTION LIGHTING AND LIGHTNING PROTECTION TO THE EXISTING AIRPORT ROTATING BEACON TOWER.

ILL. PROJ.: 3LF-4130  
 A.I.P. PROJ.: 3-17-0063-B18  
 LATITUDE: 39° 09' 59"  
 LONGITUDE: 89° 40' 29"  
 ELEVATION: 690.0' M.S.L.  
 DATE: OCT. 28, 2011




LOCATION OF COUNTY



LOCATION



COVERING ELECTRICAL DESIGN



REVISED 11/23/11



Hanson Professional Services Inc.  
**ELECTRICAL ENGINEER**

Submitted by: *Kevin N. Lightfoot* ENG'R

Date Submitted November 23, 2011

Lics. Exp. Date November 30, 2013



Hanson Professional Services Inc.  
**CIVIL ENGINEER**

Submitted by: *Charles A. Hagloch* ENG'R

Date Submitted November 23, 2011

Lics. Exp. Date November 30, 2013

LITCHFIELD AIRPORT AUTHORITY

Approved: *Will O'Neil* CHAIRMAN  
 Date: 11-23-11

Approved: *James A. Wright* SECRETARY  
 Date: 11-22-2011

REVISION	DATE

LITCHFIELD MUNICIPAL AIRPORT  
 LITCHFIELD, ILLINOIS

Hanson Project No. 11A00800	Filename G-001-CVR.dwg	LAYOUT	10/27/11
Scale NOT TO SCALE	Date 10/28/2011	DRAWN	BAK
		REVIEWED	CAH
			11/04/11

**HANSON**  
 Hanson Professional Services Inc.  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2886  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide

REPLACE MRL'S ON  
 RUNWAY 9-27  
 COVER SHEET

NOV 22, 2011 5:42 PM HAGL000382  
 p:\s\proj\306\hanson\dom\hanson\_projects\documents\11\11A00800\CAD\Airport\Sheet\G-001-CVR

REVISION	DATE	REVISED AS PER	COMMENTS
	11/22/11		

**SUMMARY OF QUANTITIES – BASE BID**

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR108108	1/C #8 5 KV UG CABLE	L.F.	1,050	
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	10,300	
AR109200	INSTALL ELECTRICAL EQUIPMENT	L.S.	1	
AR110554	EXTEND 4-WAY DUCT	L.F.	20	
AR110013	3" DIRECTIONAL BORE	L.F.	50	
AR110610	ELECTRICAL HANDHOLE	EACH	1	
AR125410	MITL – STAKE MOUNTED	EACH	23	
AR125415	MITL – BASE MOUNTED	EACH	2	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	1	
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	1	
AR125505	MIRL, STAKE MOUNTED	EACH	30	
AR125510	MIRL, BASE MOUNTED	EACH	10	
AR125540	MI THRESHOLD LIGHT STAKE MTD	EACH	8	
AR125610	REILS	PAIR	1	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	53	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	14	
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	2	
AR125907	REMOVE REILS	PAIR	2	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150520	MOBILIZATION	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR800503	ENHANCED THRESHOLD LIGHT STAKE MT	EACH	8	

**SUMMARY OF QUANTITIES – ADDITIVE ALTERNATE NO. 1**

AS107812	L-807 WC-12' INTERNALLY LIT	EACH	1	
AS108660	3/C #10 600 V UG CABLE IN UD	L.F.	300	

**SUMMARY OF QUANTITIES – ADDITIVE ALTERNATE NO. 2**

AT800591	UPGRADE AIRPORT ROTATING BEACON	L.S.	1	
----------	---------------------------------	------	---	--

**INDEX TO SHEETS**

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	EXISTING ELECTRICAL PLAN STA. 10+00 TO STA. 23+00
5	EXISTING ELECTRICAL PLAN STA. 23+00 TO STA. 37+00
6	EXISTING ELECTRICAL PLAN STA. 37+00 TO STA. 49+00
7	EXISTING ELECTRICAL PLAN FOR TAXIWAY A & VAULT
8	PROPOSED ELECTRICAL PLAN STA. 10+00 TO STA. 23+25
9	PROPOSED ELECTRICAL PLAN STA. 23+25 TO STA. 30+00
10	PROPOSED ELECTRICAL PLAN STA. 30+00 TO STA. 37+00
11	PROPOSED ELECTRICAL PLAN STA. 37+00 TO STA. 49+00
12	PROPOSED ELECTRICAL PLAN FOR TAXIWAY A & VAULT
13	ELECTRICAL DETAILS SHEET 1
14	ELECTRICAL DETAILS SHEET 2
15	ELECTRICAL DETAILS SHEET 3
16	ELECTRICAL DETAILS SHEET 4
17	L-807 WIND CONE ELEVATION DETAIL
18	REIL DETAILS TYPE L-849I, POWERED BY 6.6 AMP SERIES CIRCUIT
19	AIRPORT ROTATING BEACON UPGRADE DETAILS AND NOTES
20	ELECTRICAL NOTES SHEET 1
21	ELECTRICAL NOTES SHEET 2
22	ELECTRICAL LEGEND AND ABBREVIATIONS
23	EXISTING ELECTRICAL ONE-LINE DIAGRAM FOR AIRPORT ROTATING BEACON
24	PROPOSED ELECTRICAL ONE-LINE DIAGRAM FOR AIRPORT ROTATING BEACON
25	AIRPORT ROTATING BEACON LIGHTING CONTACTOR PANEL DETAILS
26	EXISTING ELECTRICAL ONE-LINE FOR VAULT, RWY 9-27 REILS & NDB
27	PROPOSED FLOOR PLAN FOR VAULT
28	PROPOSED ELECTRICAL ONE-LINE DIAGRAM FOR VAULT & WIND CONE
29	WIND CONE LIGHTING CONTACTOR PANEL DETAILS
30	RUNWAY 9-27 LIGHTING CONTROL SCHEMATIC
31	HIGH VOLTAGE WIRING SCHEMATIC
32	CCR GROUND BUS RISER & LEGEND PLATE SCHEDULE
33	GROUNDING DETAILS
34	GROUNDING NOTES

**LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS**

A.I.P. PROJ.: 3-17-0063-B18

IL PROJ.: 3LF-4130

Hanson Project No.	11A0080D	LAYOUT	KNL/BAK	11/01/11
Filename	G-002-FLP.dwg	DRAWN	BAK	11/01/11
Scale	NOT TO SCALE	REVIEWED	CAH	11/04/11
Date	10/28/2011			

**HANSON**  
 © Copyright Hanson Professional Services Inc. 2011  
**Hanson Professional Services Inc.**  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2986  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide

REPLACE MIRL'S ON  
RUNWAY 9-27

SUMMARY OF QUANTITIES  
AND INDEX TO SHEETS



**UTILITY NOTE**

THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT. ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. **CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123.** CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.

**HAUL ROUTE AND PARKING**

THE CONTRACTOR WILL USE THE DESIGNATED HAUL ROUTE AND EQUIPMENT PARKING AREA AS SHOWN ON THIS SHEET. THE PROPOSED PARKING AREA WILL BE 200' X 200'. THE CONTRACTOR WILL BE REQUIRED TO MAINTAIN THE PROPOSED HAUL ROUTE AND PARKING AREA THROUGHOUT THE COURSE OF THE PROJECT. ANY AREAS DAMAGED OUTSIDE OF THESE AREAS WILL BE REPAIRED BY THE CONTRACTOR AND AT THE CONTRACTOR'S OWN EXPENSE. AT THE CONCLUSION OF THE PROJECT THE CONTRACTOR WILL GRADE, FERTILIZE, SEED AND MULCH THE HAUL ROUTE AND PARKING AREA AS NEEDED TO RESTORE IT TO ITS' ORIGINAL STATE. RESTORATION OF THE HAUL ROUTE AND PARKING AREA WILL BE CONSIDERED INCIDENTAL TO THE PROJECT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

**CONTRACTOR RESPONSIBILITIES**

THE CONTRACTOR'S EQUIPMENT PARKING AND STORAGE AREA WILL BE AS SHOWN ON THIS SHEET. THE CONTRACTOR'S EMPLOYEES WILL PARK THEIR VEHICLES IN THIS AREA. ONLY CONTRACTOR VEHICLES WILL BE ALLOWED OUTSIDE THIS AREA.

THE CONTRACTOR AND HIS EMPLOYEES WILL BE RESTRICTED TO THE WORK AREA AND ALL OTHER AREAS OF THE AIRPORT ARE "OFF LIMITS" TO THEM.






THE CONTRACTOR SHALL KEEP RUNWAY 18-36 OPEN AT ALL TIMES AND MAINTAIN CONTINUOUS TAXIWAY ACCESS TO ALL HANGARS AND ADMINISTRATIVE AREAS.

ALL WORK PERFORMED SHALL BE DONE IN A ORDERLY AND EFFECTIVE MANNER TO MINIMIZE RUNWAY CLOSURE.

**BARRICADES AND TRAFFIC CONES**

IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO PLACE AND MAINTAIN BARRICADES AND TRAFFIC CONES AS DIRECTED BY THE AIRPORT MANAGER. THE BARRICADES WILL BE EQUIPPED WITH RED FLASHING OR RED STEADY-BURN LIGHTS AND 20" SQUARE ORANGE FLAGS. THE BARRICADES, THEIR MAINTENANCE, PLACEMENT AND REMOVAL WILL BE CONSIDERED AS AN INCIDENTAL ITEM TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

**LEGEND**


-  EXISTING IMPROVEMENTS
-  PROPOSED IMPROVEMENTS
-  EXISTING BUILDINGS
-  PROPOSED HAUL ROUTE AND EQUIPMENT PARKING AREA
-  PROPOSED BARRICADES OR TRAFFIC CONES

**HEIGHT OF CONSTRUCTION EQUIPMENT**

THE MAXIMUM ANTICIPATED HEIGHT OF THE CONSTRUCTION EQUIPMENT WILL BE 70 FEET, WHICH IS EXPECTED TO BE A CRANE OR A BUCKET TRUCK TO WORK ON THE BEACON TOWER. THE MAXIMUM ANTICIPATED HEIGHT OF THE CONSTRUCTION EQUIPMENT AT ALL OTHER LOCATIONS WILL BE 25 FEET, WHICH IS EXPECTED TO BE A CONCRETE TRUCK OR A LINE TRUCK. THE CRANE OR BUCKET TRUCK SHALL BE USED DURING THE DAYLIGHT HOURS AND VFR CONDITIONS ONLY AND SHALL BE LOWERED WHEN NOT IN USE, DURING THE HOURS BETWEEN SUNSET AND SUNRISE, AND/OR DURING IFR WEATHER CONDITIONS. WHEN IN USE, THE CRANE OR BUCKET TRUCK SHALL BE MARKED WITH THE 3' SQUARE CHECKERED FLAG.

**NOTE**

ALL CONSTRUCTION/OPERATIONS ARE TO BE PERFORMED IN ACCORDANCE WITH FAA ADVISORY CIRCULAR (AC) 150/5370-2F "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION" AND AC 150/5300-13 "AIRPORT DESIGN".



**DETAIL OF CROSS FOR CLOSED RUNWAY**

**NOTE:**

COST OF CONSTRUCTING, PLACING, MAINTAINING AND REMOVING CROSSES WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED. THE CROSSES WILL BE YELLOW IN COLOR AND SHALL BE MADE OF A SUITABLE MATERIAL AS APPROVED BY THE AIRPORT MANAGER. THE CROSSES WILL BE PLACED OVER THE NUMERALS AND SECURED IN A MANNER APPROVED BY THE MANAGER. THE PROPOSED CROSSES WILL BE PLACED EACH DAY THE RUNWAY IS CLOSED AND REMOVED WHEN THE RUNWAY IS RE-OPENED. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE PLACEMENT AND REMOVAL OF THE CROSSES. NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

**J.U.L.I.E. INFORMATION**

COUNTY \_\_\_\_\_ MONTGOMERY  
 CITY \_\_\_\_\_ LITCHFIELD  
 TOWNSHIP \_\_\_\_\_ SOUTH LITCHFIELD  
 SECTION NO. \_\_\_\_\_ 5 & 8  
 ADDRESS \_\_\_\_\_ LITCHFIELD MUNICIPAL AIRPORT  
 P.O. BOX 381  
 US ROUTE 66  
 LITCHFIELD, IL 62056

**PROPOSED SAFETY PLAN**

GENERAL - THE LITCHFIELD MUNICIPAL AIRPORT IS COMPRISED OF A 3,900FT BY 75FT EAST-WEST (9-27) RUNWAY AND A 4,000FT BY 75FT NORTH-SOUTH (18-36) RUNWAY. THE PROPOSED CONSTRUCTION WILL NECESSITATE CLOSING RUNWAY 9-27 FOR THE DURATION OF THIS PROJECT. ONCE ALL THE ELECTRICAL WORK HAS BEEN COMPLETED ON RUNWAY 9-27 AND CONNECTING TAXIWAY "A" RUNWAY 9-27 WILL BE RE-OPENED. ALL WORK INCLUDED IN OPENING AND CLOSING THE RUNWAY WILL BE CONSIDERED INCIDENTAL TO THE PROJECT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

IDENTIFICATION - WHEN THE CONTRACTORS VEHICLES AND EQUIPMENT ARE ON THE AIRPORT THEY SHALL BE PROPERLY MARKED WITH THREE (3)' FOOT SQUARE CHECKERED FLAGS (INTERNATIONAL ORANGE AND WHITE). THE CONTRACTOR WILL ALSO PROVIDE WORKERS WITH SOME TYPE OF TAG OR GARMENT TO IDENTIFY THE PERSON AS BEING PART OF THE CONSTRUCTION CREW.

RADIO CONTROL - THE CONTRACTOR WILL BE REQUIRED TO BE IN TWO-WAY RADIO CONTACT (122.8 MHz.) WITH THE AIRPORT UNICOM. THIS WILL KEEP THE CONTRACTOR IN CONSTANT CONTACT WITH THE AIRPORT AND ENABLE THE AIRPORT TO IMMEDIATELY CONTACT THE CONTRACTOR IN CASE OF AN AERONAUTIC EMERGENCY THAT WOULD REQUIRE ACTION BY THE CONTRACTOR AND/OR HIS PERSONNEL.

**150-ENGINEER'S FIELD OFFICE NOTES**

THE CONTRACTOR WILL FURNISH A WIRELESS PHONE TO THE RESIDENT ENGINEER FOR HIS EXCLUSIVE USE FOR THE DURATION OF THIS PROJECT. THE RESIDENT ENGINEER WILL USE THIS PHONE FOR PROJECT BUSINESS ONLY. THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL CHARGES ASSOCIATED WITH THIS CELL PHONE.

THE PROPOSED ENGINEER'S FIELD OFFICE WILL BE PAID FOR UNDER ITEMS: AR150510 ENGINEER'S FIELD OFFICE \_\_\_\_ 1 L.S.



**EROSION CONTROL**

THIS PROJECT WILL DISTURB LESS THAN 1 ACRE OF LAND, THEREFORE NO N.P.D.E.S. PERMIT WILL BE REQUIRED.

**CRITICAL POINT DATA**

- POINT NO. 1**  
 AIRPORT ROTATING BEACON  
 LATITUDE: 39° 09' 55.41"  
 LONGITUDE: 89° 40' 07.77"  
 ELEVATION: 686.0 M.S.L.
- POINT NO. 2**  
 PROPOSED WIND CONE  
 LATITUDE: 39° 09' 56.96"  
 LONGITUDE: 89° 40' 34.73"  
 ELEVATION: 685.0 M.S.L.

- POINT NO. 3**  
 15' FROM TAXIWAY "B" EDGE ON  
 RUNWAY 18-36 CENTERLINE  
 LATITUDE: 39° 10' 01.96"  
 LONGITUDE: 89° 40' 20.57"  
 ELEVATION: 686.7 M.S.L.



**SCOPE OF WORK**

**BASE BID**  
 THIS PROJECT CONSISTS OF THE REMOVAL AND REPLACEMENT OF THE MEDIUM INTENSITY LIGHTING SYSTEM ON RUNWAY 9-27 AND TAXIWAY A. INCLUDED WITH THIS WORK WILL BE REMOVAL AND REPLACEMENT OF THE REILS ON RUNWAY END 9, REMOVAL OF REILS ON RUNWAY END 27, AND THE ASSOCIATED CABLING, DUCT WORK AND VAULT WORK.

**ADDITIVE ALTERNATE NO. 1**  
 INSTALLATION OF A LIGHTED L-807 PRIMARY WIND CONE WITH ASSOCIATED CABLING, POWER AND CONTROL WORK.

**ADDITIVE ALTERNATE NO. 2**  
 ADDITION OF OBSTRUCTION LIGHTING AND LIGHTNING PROTECTION TO THE EXISTING AIRPORT ROTATING BEACON TOWER.

**AIRPORT SECURITY NOTE**


AIRPORT SECURITY WILL BE MAINTAINED AT ALL TIMES. THE CONTRACTOR WILL CLOSE AND LOCK THE EXISTING GATE IN THE HAUL ROUTE AT THE END OF EACH WORKING DAY.


**CERTIFIED PAYROLLS**

THE RESIDENT ENGINEER **CANNOT** FORWARD CONSTRUCTION REPORTS TO THE ILLINOIS DIVISION OF AERONAUTICS FOR PROCESSING UNTIL ALL **CERTIFIED PAYROLLS** FOR THE PERIOD HAVE BEEN RECEIVED.

**MATERIAL CERTIFICATION**

COMPLETED WORK **CANNOT** BE PLACED ON A CONSTRUCTION REPORT UNTIL ALL MATERIAL CERTIFICATIONS FOR THAT PAY ITEM HAVE BEEN RECEIVED, REVIEWED AND ACCEPTED BY THE RESIDENT ENGINEER.

REVISION 11/22/11 REVISED AS PER I.D.A. COMMENTS					
<b>LITCHFIELD MUNICIPAL AIRPORT LITCHFIELD, ILLINOIS</b>	I.L. PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18				
Hanson Project No. 11A0080D File Name G-003-SFY.dwg Scale 1" = 500' Date 10/28/2011	LAYOUT CAH 10/27/11 DRAWN BAK 06/22/11 REVIEWED CAH/KNL 10/27/11	 © Copyright Hanson Professional Services Inc. 2011 <b>Hanson Professional Services Inc.</b> 1525 South Sixth Street Springfield, Illinois 62703-2986 Ph: (217) 788-2450 Fax: (217) 788-2503 www.hanson-inc.com Offices Nationwide			
REPLACE MRL'S ON RUNWAY 9-27	PROPOSED SAFETY PLAN				
3					
3 of 34 sheets					



**AIRFIELD LIGHTING REMOVAL NOTES**

- ALL WORK, POWER OUTAGES, AND/OR SHUT DOWN OF EXISTING SYSTEMS SHALL BE COORDINATED WITH THE AIRPORT DIRECTOR/MANAGER. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).
- CONTRACTOR SHALL EXAMINE THE SITE TO DETERMINE THE EXTENT OF THE WORK. CONTRACTOR SHALL FIELD VERIFY EXISTING SITE CONDITIONS. CONTRACTOR SHALL FIELD VERIFY RESPECTIVE CIRCUITS AND POWER SOURCES PRIOR TO REMOVING OR DISCONNECTING THE RESPECTIVE AIRFIELD LIGHTING, NAVAIDS, OR OTHER DEVICE.
- CONTRACTOR SHALL COMPLY WITH THE REQUIREMENTS OF FAA AC NO. 150/5370-2F (OR MOST CURRENT ISSUE) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".
- CONTRACTOR SHALL COMPLY WITH THE APPLICABLE REQUIREMENTS OF NFPA 70E - STANDARD FOR ELECTRICAL SAFETY IN THE WORKPLACE.
- THE EXISTING AIRFIELD (RUNWAY & TAXIWAY) LIGHTS, TAXI GUIDANCE SIGNS AND THEIR ISOLATED TRANSFORMERS DESIGNATED FOR REMOVAL SHALL BE REMOVED AND TURNED OVER TO THE AIRPORT MANAGER. REMOVAL OF THE EXISTING AIRFIELD LIGHTS WILL BE PAID FOR UNDER ITEM AR125901 REMOVE STAKE MOUNTED LIGHT, PER EACH AND AR125902 REMOVE BASE MOUNTED LIGHT, PER EACH. REMOVAL OF THE TAXI GUIDANCE SIGNS WILL BE PAID FOR UNDER ITEM AR125904 REMOVE TAXI GUIDANCE SIGN PER EACH.
- THE EXISTING AIRFIELD LIGHTING CABLES WILL BE ABANDONED IN PLACE UNLESS IT CONFLICTS WITH THE INSTALLATION OF A PROPOSED LIGHT OR CABLE, PAVEMENT, OR OTHER WORK, THEN IT SHALL BE REMOVED AT NO ADDITIONAL COST TO THE CONTRACT.
- ALL ABOVEGROUND JUMPERS SHALL BE IN A DUCT WITH ALL CONNECTIONS SEALED. THE CONTRACTOR SHALL SECURE, IDENTIFY AND PLACE ALL TEMPORARY EXPOSED WIRING IN CONDUIT, DUCT, OR UNIT DUCT TO PREVENT ELECTROCUTION AND FIRE IGNITION SOURCES AS PER THE REQUIREMENTS OF FAA 150/5370-2F, OPERATION SAFETY ON AIRPORTS DURING CONSTRUCTION, SECTION 218 b (1)(f) .
- THE CONTRACTOR IS REQUIRED TO FILL IN ALL HOLES AND DEPRESSIONS RESULTING FROM THE LIGHT AND/OR SIGN REMOVAL WITH EARTH MATERIAL. THE AREAS SHALL BE COMPACTED TO PREVENT FUTURE SETTLEMENT AND FERTILIZED, SEEDED, AND MULCHED IN ACCORDANCE WITH ITEMS 901 AND 908 RESPECTIVELY. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE LIGHT REMOVAL AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- NO CONNECTION TO AN ACTIVE LIGHTING CIRCUIT WILL BE BROKEN UNTIL THE CIRCUIT HAS BEEN TURNED OFF IN ACCORDANCE WITH NOTE 1.

**REIL REMOVAL NOTES**

- ALL WORK, POWER OUTAGES, AND/OR SHUT DOWN OF EXISTING SYSTEMS SHALL BE COORDINATED WITH THE AIRPORT DIRECTOR/MANAGER. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).
- CONTRACTOR SHALL FIELD VERIFY EXISTING SITE CONDITIONS. CONTRACTOR SHALL FIELD VERIFY RESPECTIVE CIRCUITS AND POWER SOURCES PRIOR TO REMOVING OR DISCONNECTING REILS.
- EXISTING REILS THAT ARE DESIGNATED FOR REMOVAL SHALL BE REMOVED AND SHALL BE TURNED OVER TO THE AIRPORT. THE CONCRETE LIGHT BASES SHALL BE REMOVED AND DISPOSED OF LEGALLY OFF THE AIRPORT SITE.
- THE HOLE LEFT FROM THE LIGHT OR BASE REMOVAL SHALL BE FILLED IN WITH EARTH AND COMPACTED TO PREVENT FUTURE SETTLEMENT. THE EARTH MATERIAL WILL COME FROM OFF-SITE. THE DISTURBED AREAS SHALL BE FERTILIZED, SEEDED AND MULCHED IN ACCORDANCE WITH ITEMS 901 AND 908 RESPECTIVELY. THIS WORK SHALL BE CONSIDERED AS AN INCIDENTAL ITEM TO THE REIL REMOVAL AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- THE EXISTING AIRFIELD LIGHTING CABLES ASSOCIATED WITH LIGHT AND/OR REIL REMOVALS SHALL ALSO BE REMOVED TO ACCOMMODATE NEW WORK, AND ABANDONED IN PLACE ELSEWHERE.
- POWER FOR THE REIL SYSTEM ON EACH RUNWAY END SHALL BE DISCONNECTED AT THE RESPECTIVE POWER SOURCE PRIOR TO DISCONNECTING AND REMOVING THE RESPECTIVE REIL SYSTEM. POWER FOR THE EXISTING REIL SYSTEMS LOCATED ON RUNWAY 9-27 IS UNDERSTOOD TO BE POWERED FROM THE AIRPORT ELECTRICAL VAULT. CONTRACTOR SHALL FIELD VERIFY TO CONFIRM RESPECTIVE POWER SOURCE FOR EACH REIL SYSTEM.
- REMOVAL OF REILS WILL BE PAID FOR UNDER ITEM AR125907 "REMOVAL REILS" PER PAIR.
- NO CONNECTION TO AN ACTIVE LIGHTING, NAVAID, OR OTHER CIRCUIT SHALL BE BROKEN UNTIL THE CIRCUIT HAS BEEN TURNED OFF IN ACCORDANCE WITH NOTE 1.

THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.


ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123. CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.

**SUMMARY OF QUANTITIES - BASE BID**

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	53
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	14
AR125904	REMOVE TAXIWAY GUIDANCE SIGN	EACH	2
AR125907	REMOVE REILS	PAIR	2

**LEGEND**

- EXISTING BASE MOUNTED RUNWAY LIGHT (TO BE REMOVED)
- EXISTING STAKE MOUNTED RUNWAY LIGHT (TO BE REMOVED)
- EXISTING BASE MOUNTED THRESHOLD LIGHT (TO BE REMOVED)
- EXISTING STAKE MOUNTED THRESHOLD LIGHT (TO BE REMOVED)
- EXISTING REILS (TO BE REMOVED)
- EXISTING PAPI (TO REMAIN IN PLACE)
- EXISTING REIL POWER CABLE (TO BE ABANDONED IN PLACE)
- EXISTING RUNWAY LIGHTING CABLE (TO BE ABANDONED IN PLACE)
- EXISTING PAPI CABLE



REVISION	DATE	REVISION AS PER I.D.A. COMMENTS
11/22/11		

**LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS**

PROJECT NO.: 3-17-0063-B18  
A.I.P. PROJ.: 31F-4130

Hanson Project No.	11A00800	FILENAME	C-141-ELE.dwg
Scale	1" = 50'	DATE	10/28/2011
LAYOUT	CAH/KNL	DATE	08/04/11
DRAWN	BAK	DATE	08/04/11
REVIEWED	CAH	DATE	11/04/11

**HANSON**  
Professional Services Inc. 2011  
1525 South Sixth Street  
Springfield, Illinois 62703-2986  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide


**REPLACE MRL'S ON  
RUNWAY 9-27**

**EXISTING ELECTRICAL PLAN  
STA. 10+00 TO STA. 23+00**

**4**  
4 of 34 sheets

NOV 22, 2011 6:41 PM H:\GLO00382  
p.w.\spt-svr306\hanson.dom\hanson\_projects\Documents\11Jobs\11A00800\CAD\Drawings\Sheet\3-17-0063-ELE.dwg






THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123. CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.

- LEGEND**
- EXISTING BASE MOUNTED RUNWAY LIGHT (TO BE REMOVED)
  - EXISTING STAKE MOUNTED RUNWAY LIGHT (TO BE REMOVED)
  - EXISTING STAKE MOUNTED TAXIWAY LIGHT
  - EXISTING GUIDANCE SIGN
  - EXISTING REIL POWER CABLE (TO BE ABANDONED IN PLACE)
  - EXISTING RUNWAY LIGHTING CABLE (TO BE ABANDONED IN PLACE)
  - EXISTING PAPI CABLE
  - EXISTING ELECTRICAL DUCT



NOV 22, 2011 6:01 PM H:\GLO00382  
 p.w.\spi-svr306\hanson.dom\hanson\_projects\Documents\11A0080D\11A0080D\CAD\Aircraft\Sheet\C-141-ELE

DATE	REVISION

**LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS**


IL. PROJ.: 31F-4130      A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
Filename	C-141-ELE.dwg
Scale	1" = 50'
Date	10/28/2011
LAYOUT	CAH/KNL 08/04/11
DRAWN	BAK 08/04/11
REVIEWED	CAH 11/04/11

**HANSON**  
 © Copyright Hanson Professional Services Inc. 2011  
**Hanson Professional Services Inc.**  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2986  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide

REPLACE MRL'S ON  
 RUNWAY 9-27

EXISTING ELECTRICAL PLAN  
 STA. 23+00 TO STA. 37+00




THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123. CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.

**LEGEND**

- EXISTING BASE MOUNTED RUNWAY LIGHT (TO BE REMOVED)
- EXISTING STAKE MOUNTED RUNWAY LIGHT (TO BE REMOVED)
- EXISTING STAKE MOUNTED TAXIWAY LIGHT (TO BE REMOVED)
- EXISTING BASE MOUNTED THRESHOLD LIGHT (TO BE REMOVED)
- EXISTING STAKE MOUNTED THRESHOLD LIGHT (TO BE REMOVED)
- EXISTING REILS (TO BE REMOVED)
- EXISTING GUIDANCE SIGN (TO BE REMOVED)
- EXISTING WIND TEE
- EXISTING PAPI (TO REMAIN IN PLACE)
- EXISTING REIL POWER CABLE (TO BE ABANDONED IN PLACE)
- EXISTING RUNWAY LIGHTING CABLE (TO BE ABANDONED IN PLACE)
- EXISTING WIND TEE CABLE
- EXISTING PAPI CABLE
- EXISTING ELECTRICAL DUCT



DATE	REVISION
11/22/11	REVISED AS PER IDA COMMENTS

**LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS**

IL PROJ.: 3LF-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
Filename	C-141-ELE.dwg
Scale	1" = 50'
Date	10/28/2011
LAYOUT	CAH/KNL 08/04/11
DRAWN	BAK 08/04/11
REVIEWED	CAH 11/04/11


**HANSON**  
 © Copyright Hanson Professional Services Inc. 2011  
**Hanson Professional Services Inc.**  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2986  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide

**REPLACE MRL'S ON  
RUNWAY 9-27**

**EXISTING ELECTRICAL PLAN  
STA. 37+00 TO STA. 49+00**

**6**


6 of 34 sheets



**EXISTING DETAIL "A"**  
NOT TO SCALE


THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. **CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123.** CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.



**LEGEND**

- EXISTING BASE MOUNTED TAXIWAY LIGHT (TO BE REMOVED)
- EXISTING STAKE MOUNTED TAXIWAY LIGHT (TO BE REMOVED)
- EXISTING BASE MOUNTED TAXIWAY LIGHT
- EXISTING STAKE MOUNTED TAXIWAY LIGHT
- EXISTING GUIDANCE SIGN
- EXISTING REIL POWER CABLE (TO BE ABANDONED IN PLACE)
- EXISTING RUNWAY LIGHTING CABLE (TO BE ABANDONED IN PLACE)
- EXISTING WIND TEE CABLE
- EXISTING PAPI CABLE
- EXISTING ELECTRICAL DUCT



REVISION	DATE

**LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS**

IL PROJ.: 3LF-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D	LAYOUT	CAH/KNL	10/20/11
Filename	C-141-ELE.dwg	DRAWN	BAK	10/20/11
Scale	1" = 50'	REVIEWED	CAH	11/04/11
Date	10/28/2011			


**HANSON**  
Professional Services Inc. 2011  
Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2986  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide

**REPLACE MRL'S ON  
RUNWAY 9-27**

**EXISTING ELECTRICAL PLAN  
FOR TAXIWAY A**

NOV 22 2011 6:04 PM H4CLO00382  
p:\s\spi-svr306\hanson.d\m\hanson\Projects\Documents\11A0080D\CAD\Aircraft\Sheet\C-141-ELE





PROPOSED TYPE L-849I, STYLE A, REIL UNIT. LOCATE 40' FROM THRESHOLD AND 40' FROM RUNWAY PAVEMENT EDGE.

PROPOSED REIL CONTROL CABLES IN 2" GRSC


PROPOSED THRESHOLD LIGHTS SEE DETAIL ON THIS SHEET

SEE PROPOSED RUNWAY END 9 TURNAROUND LIGHT DETAIL ON THIS SHEET.


PROPOSED TYPE L-849I, STYLE A, REIL UNIT. LOCATE 40' FROM THRESHOLD AND 40' FROM RUNWAY PAVEMENT EDGE. REILS POWERED BY THE RUNWAY LIGHTING SERIES CIRCUIT SHALL BE FAA TYPE L-849I (REIL POWERED BY CONSTANT CURRENT 6.6 AMP POWER SUPPLY), STYLE A (UNIDIRECTIONAL, HIGH INTENSITY, ONE BRIGHTNESS STEP).

THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123. CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.




**PROPOSED RUNWAY END 9 THRESHOLD LIGHT DETAIL**  
NOT TO SCALE



**PROPOSED RUNWAY END 9 TURNAROUND LIGHT DETAIL**  
NOT TO SCALE

- LEGEND**
- PROPOSED BASE MOUNTED RUNWAY LIGHT
  - PROPOSED STAKE MOUNTED RUNWAY LIGHT
  - PROPOSED STAKE MOUNTED THRESHOLD LIGHT
  - PROPOSED STAKE MOUNTED TAXIWAY LIGHT
  - PROPOSED REILS
  - EXISTING PAPI (TO REMAIN IN PLACE)
  - PROPOSED 1/C #8 AWG, FAA L-824, 5000 VOLT TYPE C UG CABLE IN UNIT DUCT
  - EXISTING PAPI CABLE



NOV. 22, 2011 6:25 PM H:\CLO\0382 p.w.\spi-svr306\hanson.dom\hanson\_projects\Documents\11\Jobs\11A0080D\CAD\Drawings\thresholds\11A0080D.dwg

REVISION	DATE

**LITCHFIELD MUNICIPAL AIRPORT**  
**LITCHFIELD, ILLINOIS**


IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
Filename	C-142-ELEC.dwg
Scale	1" = 50'
Date	10/28/2011
LAYOUT	CAH/KNL 10/10/11
DRAWN	BAK 10/10/11
REVIEWED	CAH 11/04/11

**HANSON**  
Professional Services Inc. 2011  
Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2986  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide

REPLACE MRL'S ON  
RUNWAY 9-27

PROPOSED ELECTRICAL PLAN  
STA. 10+00 TO STA. 23+25



**AIRFIELD LIGHTING NOTES**


- ALL WORK, POWER OUTAGES, AND/OR SHUT DOWN OF EXISTING SYSTEMS SHALL BE COORDINATED WITH THE AIRPORT DIRECTOR/MANAGER. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).
- CONTRACTOR SHALL FIELD VERIFY EXISTING SITE CONDITIONS. CONTRACTOR SHALL FIELD VERIFY RESPECTIVE CIRCUITS AND POWER SOURCES PRIOR TO REMOVING OR DISCONNECTING THE RESPECTIVE AIRFIELD LIGHTING, NAVAID, OR OTHER DEVICE.
- PROPOSED RUNWAY, THRESHOLD, AND TAXIWAY LIGHTS SHALL BE PLACED 10' (FT.) FROM THE PAVEMENT EDGE UNLESS SHOWN OTHERWISE ON THESE CONSTRUCTION DRAWINGS. PROPOSED TAXI GUIDANCE SIGNS SHALL BE LOCATED SUCH THAT THE CLOSEST SIDE OF THE SIGN IS 15' FROM THE PAVEMENT EDGE, UNLESS SHOWN OTHERWISE.
- PROPOSED RUNWAY LIGHTS, THRESHOLD LIGHTS, TAXIWAY LIGHTS, GUIDANCE SIGNS, OTHER AIRFIELD LIGHTING, SPLICE CANS, HANDHOLES, MANHOLES, ELECTRICAL DUCTS, AND CABLE SHALL BE INSTALLED AT THE LOCATIONS SHOWN AND IN COMPLIANCE WITH THE SPECIFICATIONS, SPECIAL PROVISIONS, RESPECTIVE DETAILS, AND MANUFACTURER'S RECOMMENDATIONS.
- PROPOSED CABLE FOR RUNWAY AND TAXIWAY LIGHTING SHALL BE INSTALLED APPROXIMATELY 12' FROM THE PAVEMENT EDGE. CABLES SHALL BE PLACED A MINIMUM OF 18" BELOW FINISHED GRADE.
- THE PROPOSED RUNWAY AND TAXIWAY LIGHTING CABLE SHALL BE 1/C, #8 AWG, FAA L-824, 5000 VOLT, TYPE C UNDERGROUND CABLE IN UNIT DUCT.
- IN AREAS WHERE THERE IS A CONGESTION OF CABLES OR WHERE THE PROPOSED CABLE CROSSES AN EXISTING CABLE, THE CONTRACTOR IS REQUIRED TO HAND DIG THE TRENCH NECESSARY FOR THE PROPOSED CABLE. AT OTHER LOCATIONS, THE PROPOSED CABLE MAY BE TRENCHED OR PLOWED INTO PLACE. HAND DIGGING, TRENCHING AND/OR PLOWING WILL BE CONSIDERED INCIDENTAL TO THE PROPOSED CABLES AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- PROPOSED RUNWAY LIGHTS SHALL BE FITTED WITH LENSES IN ACCORDANCE WITH THE "LIGHT LENS SCHEDULE". ALL PROPOSED TAXIWAY LIGHTS WILL BE FITTED WITH 360° BLUE LENSES.
- ALL PROPOSED RUNWAY, THRESHOLD, AND TAXIWAY LIGHTS SHALL BE TAGGED BY THE CONTRACTOR IN ACCORDANCE WITH THE LIGHT NUMBERS SHOWN ON THESE CONSTRUCTION DRAWINGS.
- SEE "TAXI GUIDANCE SIGN SCHEDULE" AND/OR DETAILS FOR INFO ON SIGN LEGENDS.
- THE CONTRACTOR SHALL SECURE, IDENTIFY AND PLACE ALL TEMPORARY EXPOSED WIRING IN CONDUIT, DUCT OR UNIT DUCT TO PREVENT ELECTROCUTION AND FIRE IGNITION SOURCES AS PER THE REQUIREMENTS OF FAA AC 150/5370-2F, SECTION 218 b (1)(f). ALL LABOR, MATERIALS, AND TIME NECESSARY TO COMPLY WITH THIS REQUIREMENT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- HOMERUN CABLES FOR A RESPECTIVE CIRCUIT THAT ARE INSTALLED IN CONDUIT OR DUCT SHALL BE RUN TOGETHER IN THE SAME RACEWAY OR DUCT.
- EXISTING AIRFIELD LIGHTING CABLES IN AREAS OF NEW WORK SHALL BE DISCONNECTED & REMOVED WHERE IN CONFLICT WITH NEW CONSTRUCTION. IN OTHER AREAS CABLES MAY BE ABANDONED IN PLACE.
- THE CONTRACTOR IS REQUIRED TO FILL IN ALL HOLES AND DEPRESSIONS RESULTING FROM THE NEW WORK, WITH EARTH MATERIAL. THE AREAS SHALL BE COMPACTED TO PREVENT FUTURE SETTLEMENT AND FERTILIZED, SEEDED, AND MULCHED IN ACCORDANCE WITH ITEMS 901 AND 908 RESPECTIVELY. THIS WORK WILL BE CONSIDERED AS AN INCIDENTAL ITEM AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- SEE "L-849I REIL INSTALLATION DETAILS" SHEET AND SPECIAL PROVISIONS SPECS FOR REQUIREMENTS ON INSTALLATION OF TYPE L-849I (REIL POWERED BY A CONSTANT CURRENT 6.6A POWER SUPPLY) REILS ON RUNWAY END 9.
- NO CONNECTION TO AN ACTIVE LIGHTING CIRCUIT WILL BE BROKEN UNTIL THE CIRCUIT HAS BEEN TURNED OFF IN ACCORDANCE WITH NOTE 1.

THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. **CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123.** CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.

**LEGEND**

- PROPOSED BASE MOUNTED RUNWAY LIGHT
- PROPOSED STAKE MOUNTED RUNWAY LIGHT
- EXISTING STAKE MOUNTED TAXIWAY LIGHT
- EXISTING GUIDANCE SIGN
- PROPOSED 1/C #8 AWG, FAA L-824, 5000 VOLT TYPE C UG CABLE IN UNIT DUCT
- EXISTING PAPI CABLE
- EXISTING ELECTRICAL DUCT



REVISION	DATE	REVISION AS PER IDA COMMENTS
	11/22/11	

**LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS**


IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
Filename	C-142-ELEC.dwg
Scale	1" = 50'
Date	10/28/2011
LAYOUT	CAH/KNL 10/26/11
DRAWN	BAK 10/26/11
REVIEWED	CAH 11/04/11

**HANSON**  
 © Copyright Hanson Professional Services Inc. 2011  
**Hanson Professional Services Inc.**  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2886  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide

REPLACE MRL'S ON  
 RUNWAY 9-27  
 PROPOSED ELECTRICAL PLAN  
 STA. 23+25 TO STA. 30+00

NOV 22, 2011 6:45 PM H:\CLO00382  
 p:\s\svr306\hanson\_dom\hanson\_projects\Documents\11A0080D\CAD\_Airport\Sheet\C-142-ELEC




THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. **CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123.** CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.

**LEGEND**

- PROPOSED STAKE MOUNTED RUNWAY LIGHT
- EXISTING STAKE MOUNTED TAXIWAY LIGHT
- ◻ EXISTING BASE MOUNTED TAXIWAY LIGHT
- PROPOSED 1/C #8 AWG, FAA L-824, 5000 VOLT TYPE C UG CABLE IN UNIT DUCT
- PROPOSED 3-1/C #10 AWG XLP-USE 600V UG CABLE IN UNIT DUCT
- EXISTING PAPI CABLE
- EXISTING TAXIWAY B ELECTRICAL CABLE
- - - EXISTING NDB CABLE
- ▬ EXISTING ELECTRICAL DUCT



NOV 22, 2011 6:12 PM H:\GLO00382  
 p:\s\spi-svr306\hanson.dom\hanson\_projects\Documents\11A0080D\CAD\_Airport\Sheet\C-142-ELEC

REVISION	DATE

**LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS**

IL PROJ.: 3LF-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
Filename	C-142-ELEC.dwg
Scale	1" = 50'
Date	10/28/2011
LAYOUT	CAH/KNL 10/26/11
DRAWN	BAK 10/26/11
REVIEWED	CAH 11/05/11

**HANSON**  
 © Copyright Hanson Professional Services Inc. 2011  
**Hanson Professional Services Inc.**  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2986  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide


**REPLACE MRL'S ON  
RUNWAY 9-27**

**PROPOSED ELECTRICAL PLAN  
STA. 30+00 TO STA. 37+00**




**TAXI GUIDANCE SIGN NOTES**

1. THE PROPOSED TAXI GUIDANCE SIGNS SHALL CONFORM TO ADVISORY CIRCULAR 150/5345 44J (OR LATEST ISSUE IN FORCE) AND BE FAA-APPROVED FOR TYPE L-858Y DIRECTION, DESTINATION, AND BOUNDARY SIGNS (BLACK LEGEND ON YELLOW BACKGROUND); TYPE L-858R MANDATORY INSTRUCTION SIGN (BLACK OUTLINE ON OUTSIDE EDGE OF WHITE LEGEND ON RED BACKGROUND); AND/OR TYPE L-858L LOCATION SIGN (YELLOW LEGEND AND BORDER ON BLACK BACKGROUND). THE SIGNS SHALL BE SIZE 1, 18-IN. SIGN FACE WITH A 12-IN. LEGEND; STYLE 2, POWERED FROM A 4.8 TO 6.6 AMP SERIES LIGHTING CIRCUIT; CLASS 2, FOR OPERATION FROM -40 DEGREES F TO 131 DEGREES F; MODE 2, TO WITHSTAND WIND LOADS OF 200 M.P.H., BASE-MOUNTED, DOUBLE-SIDED, AS SPECIFIED ON THE PLANS.




**TAXI GUIDANCE SIGN DETAIL R1-TGS1**

"NOT TO SCALE"




**TAXI GUIDANCE SIGN DETAIL R1-TGS2**

"NOT TO SCALE"



THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123. CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.




**PROPOSED RUNWAY END 27 THRESHOLD LIGHT DETAIL**

NOT TO SCALE

**LEGEND**

- PROPOSED BASE MOUNTED RUNWAY LIGHT
- PROPOSED STAKE MOUNTED RUNWAY LIGHT
- PROPOSED STAKE MOUNTED TAXIWAY LIGHT
- PROPOSED STAKE MOUNTED THRESHOLD LIGHT
- PROPOSED GUIDANCE SIGN
- EXISTING PAPI (TO REMAIN IN PLACE)
- PROPOSED 1/C #8 AWG, FAA L-824, 5000 VOLT TYPE C UG CABLE IN UNIT DUCT
- EXISTING PAPI CABLE
- EXISTING WIND TEE CABLE
- EXISTING ELECTRICAL DUCT



REVISION	DATE	REVISED AS PER I.D.A. COMMENTS
	11/22/11	


LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS

FILENAME	SCALE	DATE	LAYOUT	DRAWN	REVIEWED
11A0080D C-142-ELEC.dwg	1" = 50'	10/28/2011	CAH/KNL	BAK	CAH

**HANSON**  
Professional Services Inc. 2011  
Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2986  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide

REPLACE MRL'S ON  
RUNWAY 9-27  
PROPOSED ELECTRICAL PLAN  
STA. 37+00 TO STA. 49+00

NOV 22, 2011 6:20 PM H4GL000382  
p:\s\spc-306\hanson.dwg\hanson\Projects\Documents\11A0080D\CAD\Aircraft\Sheet\C-142-ELEC




**PROPOSED DETAIL "A"**  
NOT TO SCALE


THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. **CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123.** CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.

LIGHT LENS SCHEDULE FOR RUNWAY 9-27		
LIGHT NUMBERS	LENS	ORIENTATION
R1-1 TO R1-7	BLUE	- - -
R1-8 TO R1-15	RED / GREEN	RED SIDE FACING WEST (TOWARDS THRESHOLD)
R1-16 TO R1-25	CLEAR WHITE / AMBER	AMBER SIDE FACING WEST
R1-26 TO R1-35	CLEAR WHITE / AMBER	AMBER SIDE FACING EAST
R1-36 TO R1-43	RED / GREEN	RED SIDE FACING EAST (TOWARDS THRESHOLD)
R1-44 TO R1-53	BLUE	- - -
R1-54 TO R1-63	CLEAR WHITE/AMBER	AMBER SIDE FACING EAST
R1-64 TO R1-73	CLEAR WHITE/AMBER	AMBER SIDE FACING WEST
R1-74 TO R1-81	BLUE	- - -




- LEGEND**
- PROPOSED BASE MOUNTED TAXIWAY LIGHT
  - PROPOSED STAKE MOUNTED TAXIWAY LIGHT
  - EXISTING BASE MOUNTED TAXIWAY LIGHT
  - EXISTING STAKE MOUNTED TAXIWAY LIGHT
  - EXISTING GUIDANCE SIGN
  - PROPOSED 1/C #8 AWG, FAA L-824, 5000 VOLT TYPE C UG CABLE IN UNIT DUCT
  - - - EXISTING PAPI CABLE
  - - - EXISTING WIND TEE CABLE
  - EXISTING ELECTRICAL DUCT
  - PROPOSED ELECTRICAL DUCT




NOV 22 2011 6:26 PM H:\CLO00382 p\l\spi-svr306\hanson\Documents\Projects\Documents\11A0080D\CAD\Aircraft\Sheet\11A0080D-C-142-ELEC

<p>REVISION</p> <p>DATE</p>	<p><b>LITCHFIELD MUNICIPAL AIRPORT</b> <b>LITCHFIELD, ILLINOIS</b></p>
<p>Hanson Project No. 11A0080D                  File Name C-142-ELEC.dwg                  Scale 1" = 50'                  Date 10/28/2011</p>	
<p>LAYOUT CAH/KNL 10/17/11                  DRAWN BAK 10/20/11                  REVIEWED CAH 11/04/11</p>	
<p><b>HANSON</b>                  © Copyright Hanson Professional Services Inc. 2011                  Hanson Professional Services Inc.                  1525 South Sixth Street                  Springfield, Illinois 62703-2886                  Ph: (217) 788-2450 Fax: (217) 788-2503                  www.hanson-inc.com                  Offices Nationwide</p>	
<p>REPLACE MRL'S ON RUNWAY 9-27</p>	<p>PROPOSED ELECTRICAL PLAN FOR TAXIWAY A</p>
<p><b>12</b></p> <p>12 of 34 sheets</p>	


I.L. PROJ.: 3LF-4130 A.I.P. PROJ.: 3-17-0063-B18



**NOTES:**  
 DETAIL NUMBERS INDICATE NO. OF CABLES.  
 TRENCHES WITH MORE THAN SEVEN CABLES SHALL BE INCREASED 3" IN WIDTH FOR EACH ADDITIONAL CABLE; IF SPECIFIED ON PLANS TWO PARALLEL TRENCHES MAY BE CONSTRUCTED.  
 DEPTH OF TRENCHES SHALL BE AS SHOWN ABOVE UNLESS OTHERWISE SPECIFIED ON THE PLANS.  
 ALL DISTURBED SURFACES SHALL BE RESTORED TO THEIR ORIGINAL CONDITION. COST IS INCIDENTAL TO TRENCH.




**CABLE TRENCHES**  
(NOT TO SCALE)



**PLAN VIEW**

PER FAA AC 150/5340-30F DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS, A LIGHT BASE GROUND MUST BE INSTALLED AT EACH LIGHT FIXTURE. A LIGHT BASE GROUND SHALL BE INSTALLED AT EACH STAKE MOUNTED LIGHT AND EACH TRANSFORMER BASE/LIGHT CAN ASSOCIATED WITH RUNWAY LIGHTS, TAXIWAY LIGHTS, AND LIGHTED TAXI GUIDANCE SIGNS. THE LIGHT BASE GROUND SHALL BE A #6 AWG BARE COPPER CONDUCTOR BONDED TO THE GROUND LUG ON THE RESPECTIVE L-867 TRANSFORMER BASE/LIGHT CAN OR MOUNTING STAKE AND A 5/8-INCH DIAMETER BY 8-FOOT LONG (MINIMUM) UL LISTED COPPER CLAD GROUND ROD.

**NOTES:**  
 SEE PROPOSED LIGHTING LAYOUT SHEET FOR LIGHT LOCATIONS.




**PROFILE VIEW**


**LIGHT AND CABLE INSTALLATION DETAIL**  
(NOT TO SCALE)

**GROUND ROD**  
(NOT TO SCALE)


**NOTES:**  
 TYPE AND MINIMUM NUMBER OF GROUND RODS SHALL BE AS SPECIFIED ON THE PLAN.  
 THE RESISTANCE TO GROUND OF THE GROUNDING SYSTEM SHALL NOT EXCEED 25 OHMS.  
 COST OF GROUND RODS IS INCIDENTAL TO THE ASSOCIATED ITEMS REQUIRING GROUNDING UNLESS OTHERWISE SPECIFIED.




**MEDIUM INTENSITY LIGHT - STAKE MOUNTED**  
(NOT TO SCALE)



**MEDIUM/HIGH INTENSITY LIGHT - BASE MOUNTED**  
(NOT TO SCALE)




**PLOWED CABLE**  
(NOT TO SCALE)



**TAG DETAIL**  
(NOT TO SCALE)


**NOTE:**  
 AFFIX NON-CORROSIVE TAG TO FIXTURE FACING RUNWAY WITH SET SCREW, WIRE TIE, OR METAL BAND. NUMERALS SHALL BE ENGRAVED FOR PERMANENT READABILITY.



**TYPE A**

CONTINUOUS HEAT SHRINK TUBING PLACED OVER THE ENTIRE L-823 CONNECTOR(S) BOTH MALE AND FEMALE AT ALL 5KV JUNCTIONS. THE HEAT SHRINK TUBING SHALL BE APPROXIMATELY 18" IN LENGTH WITH 6 INCHES OF MASTIC ON BOTH ENDS AND VOID OF MASTIC IN MIDDLE OF TUBE RATED FOR 5KV.


FOR SPLICES IN LOW VOLTAGE CABLE (600V) HOMERUNS FOR EXTENSIONS TO EXISTING LOW VOLTAGE CABLES ONLY. TYPE A SPLICES SHALL BE MADE IN SPLICE CANS, HANDHOLES, MANHOLES, OR JUNCTIONS BOXES



**TYPE B**

FOR SPLICES AT JUNCTION OF HOMERUN WITH LOOP CIRCUIT AND FOR SPLICES IN HOMERUNS TO EXISTING CABLES


HEAT SHRINKABLE TUBING WITH INTERNAL ADHESIVE. HEAT SHRINKABLE TUBING SHALL EXTEND FROM THE CABLE TO AT LEAST AN INCH PAST THE COMPLETED CONNECTION.



**TYPE C**

FOR SPLICES AT RUNWAY AND TAXIWAY LIGHTS

**NOTES:**  
 SEE PROPOSED LIGHTING LAYOUT SHEET(S) FOR SPLICE TYPE.  
 INSIDE DIAMETER OF CONNECTOR SHALL PROPERLY MATCH THE OUTSIDE DIAMETER OF CABLE.



**DETAIL "B"**  
(NOT TO SCALE)

**CABLE SPLICES**  
(NOT TO SCALE)

REVISION	DATE	REVISION AS PER I.D.A. COMMENTS
	11/23/11	

LITCHFIELD MUNICIPAL AIRPORT  
 LITCHFIELD, ILLINOIS

IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
File Name	E-501.dwg
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	KNL/CAH 07/28/11
DRAWN	BAK 07/28/11
REVIEWED	CAH 11/04/11


**HANSON**  
 Professional Services Inc. 2011  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2986  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide

REPLACE MRL'S ON  
 RUNWAY 9-27


ELECTRICAL DETAILS  
 SHEET 1

NOV 23, 2011 8:39 AM HAGL000382  
 p:\s\svr\306\hanson\dom\hanson\Projects\Documents\11A0080D\CAD\Airport\Sheet\E-501







TYPICAL SECTION  
"NOT TO SCALE"



2-DUCT BANK  
"NOT TO SCALE"




3-DUCT BANK  
"NOT TO SCALE"



4-DUCT BANK  
"NOT TO SCALE"


1/2" Ø REBAR  
3' LONG IN  
EACH CORNER

4" I.D. CONDUIT  
1/2" Ø REBAR  
3' LONG IN  
EACH CORNER



HEAVY DUTY FRAME & LID SUITABLE FOR  
H-20 LOADING, NEENAH CAT. NO.  
R-6662-PP OR APPROVED EQUAL

SMOOTH TROWEL FINISH  
(SLOPE TO DRAIN)



DUCT BANK SHALL TRANSITION TO (OR BE)  
REINFORCED CONCRETE ENCASED DUCT WHERE  
ENTERING A HANDHOLE. PROVIDE REINFORCEMENT  
3 FT. MIN. BEYOND HANDHOLE. DIRECT BURY  
DUCT (WITHOUT CONCRETE ENCASEMENT) DOES  
NOT REQUIRE REBAR & CONCRETE ENCASEMENT  
AT INTERFACE TO HANDHOLE.

EXTEND NO. 4 REBAR INTO HANDHOLE  
APPROX 3". PROVIDE 90° "L" HOOK  
ON REBAR TERMINATION IN HANDHOLE.  
(TYP.) OR EXTEND REBAR EPOXY  
ANCHORED INTO HANDHOLE WITH 4"  
EMBEDMENT.


PROVIDE CONDUIT BUSHING OR BELL  
AT TERMINATION IN HANDHOLE (TYP.)

6" SCHED 40 PVC DRAIN  
PIPE. FILL WITH PEA GRAVEL  
TO ACCOMMODATE DRAINAGE.  
NOTE 6" OF CA-7 GRAVEL  
MAY BE PROVIDED. INSTEAD  
OF 6" CONCRETE FLOOR  
WITH DRAIN PIPE, AT  
CONTRACTORS OPTION.

ELECTRICAL HANDHOLE  
"NOT TO SCALE"


NOTES:

- LIDS FOR LOW VOLTAGE HANDHOLES SHALL BE LABELED "LOW VOLTAGE". LIDS FOR HIGH VOLTAGE HANDHOLES SHALL BE LABELED "HIGH VOLTAGE". COORDINATE LETTERING WITH MFR.
- HANDHOLES MAY BE CAST IN PLACE OR PRECAST. PRECAST MANUFACTURERS MUST BE ON THE IDOT (ILLINOIS DEPT. OF TRANSPORTATION) APPROVED LIST OF CERTIFIED PRECAST CONCRETE PRODUCERS.
- ALL CORING, INTERFACE, AND LABOR ASSOCIATED WITH CONDUIT, DUCT, CABLE IN UNIT DUCT, AND / OR CABLE ENTRIES WILL BE CONSIDERED INCIDENTAL TO THE INSTALLATION OF THE HANDHOLE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.




BITUMINOUS PAVEMENT DUCT MARKERS  
"NOT TO SCALE"

NOTE:  
TOP OF MARKER SHALL BE FLUSH WITH FINISHED  
PAVEMENT SURFACE. MARKER MAY BE INSTALLED IN  
A DRILLED HOLE AND SECURED WITH EPOXY GLUE.




DUCT MARKER DETAIL  
"NOT TO SCALE"


- DUCT BANK NOTES:
- DIMENSIONS FOR CONCRETE COVERAGE AND SEPARATION BETWEEN DUCTS ARE MINIMUM.
  - INCLUDE DUCT SPACERS AS MANUFACTURED BY UNDERGROUND DEVICES INC., OR APPROVED EQUAL TO MAINTAIN PROPER SEPARATION OF CONDUITS.
  - REBAR IS REQUIRED TO ACCOMMODATE FUTURE DUCT EXTENSIONS & INTERFACE AT DUCT BANK TERMINATIONS. CONCRETE ENCASED DUCT BANKS TERMINATING IN HANDHOLES REQUIRE REBAR AT TERMINATIONS.
  - CONDUITS FOR CONCRETE ENCASED DUCT SHALL BE SCHEDULE 40 PVC CONFORMING TO ITEM 110.
  - MINIMUM DEPTH OF TOP OF DUCT ENCASEMENT SHALL BE 18" BELOW FINISHED GRADE.
  - HIGH VOLTAGE AND LOW VOLTAGE CIRCUITS SHALL NOT BE INSTALLED IN THE SAME RACEWAY, CONDUIT, DUCT, HANDHOLE, OR MANHOLE.
  - HOMERUN CABLES FOR A RESPECTIVE CIRCUIT SHALL BE INSTALLED IN THE SAME RACEWAY OR DUCT.
  - DUCT INTERFACE TO HANDHOLES OR MANHOLES WILL BE CONSIDERED INCIDENTAL TO THE RESPECTIVE DUCT PAY ITEM.
- CABLE & DUCT MARKER NOTES:
- THE COST OF ALL TURF AND PAVEMENT DUCT MARKERS SHALL BE INCIDENTAL TO THE DUCT. THE COST OF ALL CABLE MARKERS SHALL BE INCIDENTAL TO THE CABLE.
  - BITUMINOUS PAVEMENT DUCT MARKER AND CONCRETE DUCT MARKER TO BE PROVIDED AT EACH END OF EACH DUCT AS SHOWN ON THE LOCATION PLAN. FOR CONCRETE PAVEMENT, THE LETTER "D" SHALL BE IMPRESSED IN THE PAVEMENT INSTEAD OF THE MARKER. THE LETTER SHALL BE FORMED AS DESCRIBED IN NOTE 4.
  - CABLE MARKERS SHALL BE PLACED AT CHANGES OF DIRECTION AND APPROXIMATELY EVERY 200' ALONG CABLE RUNS.
  - CONCRETE CABLE MARKERS AND DUCT MARKERS SHALL HAVE LETTERS 4" HIGH, 3" WIDE WITH WIDTH OF STROKE 1/2" AND 1/4" DEEP. ALL LETTERS, NUMBERS AND ARROWS TO BE IMPRESSED.



UNDERGROUND ELECTRICAL DUCT  
"NOT TO SCALE"



TURF CABLE MARKERS  
"NOT TO SCALE"



TURF DUCT MARKERS  
"NOT TO SCALE"

NOV 23, 2011 8:40 AM HAGL000382  
p:\s\spi-svr306\hanson.dom\hanson\_projects\Documents\11A0080D\CAD\Work\Sheet\E-502

REVISION	DATE

LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS

IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
Filename	E-502.dwg
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	CAH/KNL 07/28/11
DRAWN	BAK 07/28/11
REVIEWED	CAH 11/04/11

**HANSON**  
Professional Services Inc. 2011  
Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2986  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide

REPLACE MRL'S ON  
RUNWAY 9-27

ELECTRICAL DETAILS  
SHEET 2

REVISION	DATE	REVISION AS PER IDA COMMENTS
	11/23/11	

LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS

IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
File Name	E-503.DWG
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	KNL 07/28/11
DRAWN	BAK 07/28/11
REVIEWED	CAH 11/04/11



**HANSON**  
Professional Services Inc. 2011  
Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2986  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide

REPLACE MRL'S ON  
RUNWAY 9-27

ELECTRICAL DETAILS  
SHEET 3

**L-858 SIGN**





NOTES:  
SEE LIGHTING LAYOUT SHEET(S) FOR SIGN LEGEND, LOCATION, TYPE, SIZE, STYLE, AND CLASS.  
NUMBER AND SPACING OF LEGS AS PER MANUFACTURER'S REQUIREMENTS.



**GENERAL NOTES:**


- SEE LIGHTING LAYOUT SHEET FOR SIGN LEGEND, LOCATION, TYPE, SIZE, STYLE, AND CLASS.
- SEE ELECTRICAL NOTES SHEETS.

PER FAA AC 150/5340-30F DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS, A LIGHT BASE GROUND MUST BE INSTALLED AT EACH LIGHT FIXTURE. A LIGHT BASE GROUND SHALL BE INSTALLED AT EACH STAKE MOUNTED LIGHT AND EACH TRANSFORMER BASE/LIGHT CAN ASSOCIATED WITH RUNWAY LIGHTS, TAXIWAY LIGHTS, AND LIGHTED TAXI GUIDANCE SIGNS. THE LIGHT BASE GROUND SHALL BE A #6 AWG BARE COPPER CONDUCTOR CONNECTED TO THE GROUND LUG ON THE RESPECTIVE L-867 TRANSFORMER BASE/LIGHT CAN OR MOUNTING STAKE AND A 3/8-INCH DIAMETER BY 8-FOOT LONG (MINIMUM) UL LISTED COPPER CLAD GROUND ROD. ALSO BOND THE SIGN FRAME TO THE GROUND ROD WITH A #6 AWG BARE COPPER CONDUCTOR.




NOTE:  
FOR THE PURPOSE OF ENHANCING SAFETY, EACH BASE MUST HAVE INSTALLED, BY THE MANUFACTURER, AN INTERNAL AND EXTERNAL GROUND STRAP THAT IS AVAILABLE FOR THE PURPOSE OF ATTACHING A GROUND LUG THAT IS CONNECTED TO AN EARTH GROUND OR A SAFETY GROUND CONDUCTOR INSTALLED WITH THE RESPECTIVE CIRCUIT. FOR AIRPORT PROJECTS RECEIVING FEDERAL FUNDS THIS REQUIREMENT IS MANDATORY PER FAA AC 150/5345-42F.


NOV 23, 2011 8:43 AM HAGL000382  
p:\s\spi-svr306\hanson\dm\hanson\Projects\Documents\11A0080D\CAD\Airport\Sheet\E-503




**GROUNDING DETAIL FOR ADJACENT TAXIWAY LIGHTS**  
(NOT TO SCALE)



**MEDIUM/HIGH INTENSITY LIGHT -- BASE MOUNTED OPTION 1**  
(NOT TO SCALE)



**MEDIUM/HIGH INTENSITY LIGHT -- BASE MOUNTED OPTION 2**  
(NOT TO SCALE)



**GROUNDING DETAIL FOR ADJACENT RUNWAY AND TAXIWAY LIGHTS**  
(NOT TO SCALE)

**NOTES**

1. GROUNDING FOR RUNWAY LIGHTS, TAXIWAY LIGHTS, AND LIGHTED TAXI GUIDANCE SIGNS SHALL BE AS DETAILED ON THE PLANS AND AS SPECIFIED HEREIN. PER FAA AC 150/5340-30F DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS, CHAPTER 12, PART 12.6; A GROUND MUST BE INSTALLED AT EACH LIGHT FIXTURE. THE PURPOSE OF THE LIGHT BASE GROUND IS TO PROVIDE A DEGREE OF PROTECTION FOR MAINTENANCE PERSONNEL FROM POSSIBLE CONTACT WITH AN ENERGIZED LIGHT BASE OR MOUNTING STAKE THAT MAY RESULT FROM A SHORTED POWER CABLE OR ISOLATION TRANSFORMER. A LIGHT BASE GROUND SHALL BE INSTALLED AT EACH TRANSFORMER BASE/LIGHT CAN ASSOCIATED WITH RUNWAY LIGHTS, TAXIWAY LIGHTS, AND LIGHTED TAXI GUIDANCE SIGNS. A LIGHT BASE GROUND SHALL ALSO BE INSTALLED AT EACH STAKE MOUNTED LIGHT FIXTURE. A LIGHT BASE GROUND SHALL BE INSTALLED AND CONNECTED TO THE METAL FRAME OF EACH TAXI GUIDANCE SIGN AS DETAILED ON THE PLANS AND IN ACCORDANCE WITH THE RESPECTIVE TAXI GUIDANCE SIGN MANUFACTURER RECOMMENDATIONS. THE LIGHT BASE GROUND SHALL BE A #6 AWG BARE COPPER CONDUCTOR BONDED TO THE GROUND LUG ON THE RESPECTIVE L-867 TRANSFORMER BASE/LIGHT CAN OR MOUNTING STAKE AND A 5/8-INCH DIAMETER BY 8-FOOT LONG (MINIMUM) UL LISTED COPPER CLAD GROUND ROD. CONNECTIONS TO GROUND LUGS ON THE L-867 TRANSFORMER BASE/LIGHT CAN OR MOUNTING STAKE SHALL BE WITH A UL LISTED GROUNDING CONNECTOR. CONNECTIONS TO GROUND RODS SHALL BE MADE WITH EXOTHERMIC WELD TYPE CONNECTORS, CADWELD BY ERICO PRODUCTS, INC., SOLON, OHIO, (PHONE: 800-248-9353), THERMOWELD BY CONTINENTAL INDUSTRIES, INC., TULSA, OKLAHOMA (PHONE: 918-663-1440), ULTRAWELD BY HARGER, GRAYSLAKE, ILLINOIS (PHONE: 800-842-7437), OR APPROVED EQUAL. EXOTHERMIC WELD CONNECTIONS SHALL BE INSTALLED IN CONFORMANCE WITH THE RESPECTIVE MANUFACTURER'S DIRECTIONS USING MOLDS AS REQUIRED FOR EACH RESPECTIVE APPLICATION. BOLTED CONNECTIONS WILL NOT BE PERMITTED AT GROUND RODS. TOP OF GROUND RODS SHALL BE BURIED 12 INCHES MINIMUM BELOW GRADE, UNLESS SPECIFIED OTHERWISE HEREIN, FOR RESPECTIVE APPLICATIONS
2. FOR BASE MOUNTED LIGHT FIXTURES THE LIGHT FIXTURE MUST BE BONDED TO THE LIGHT BASE INTERNAL GROUND LUG VIA A #6 AWG STRANDED COPPER WIRE RATED FOR 600 VOLTS WITH GREEN XHHW OR USE INSULATION. THE GROUND WIRE LENGTH MUST BE SUFFICIENT TO ALLOW THE REMOVAL OF THE LIGHT FIXTURE FROM THE LIGHT BASE FOR ROUTINE MAINTENANCE. SEE THE LIGHT FIXTURE MANUFACTURER'S INSTRUCTIONS FOR PROPER METHODS OF ATTACHING A BONDING WIRE.
3. FOR TAXIWAY LIGHTS THAT ARE SPACED WITH LESS THAN 10 FEET OF SEPARATION BETWEEN THEM PROVIDE ONE 5/8-INCH DIAMETER BY 8-FOOT LONG GROUND ROD PER TWO ADJACENT TAXIWAY LIGHTS.
4. STEEL USED TO MANUFACTURE GROUND RODS SHALL BE 100% DOMESTIC STEEL.

REVISION	DATE	REVISION AS PER IDA COMMENTS
11/22/11		

LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS


IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
Filename	E-505.dwg
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	KNL 10/25/11
DRAWN	BAK 10/28/11
REVIEWED	CAH 11/04/11

**HANSON**  
Professional Services Inc. 2011  
Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2886  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide

REPLACE MRL'S ON  
RUNWAY 9-27


ELECTRICAL DETAILS  
SHEET 4




**LIGHTED L-807 WIND CONE**  
NOT TO SCALE

**NOTES**

1. WIND CONE SHALL BE FAA APPROVED L-807, STYLE 1B INTERNALLY LIGHTED, SIZE 2 WITH ORANGE WIND SOCK, 120 VAC, & WITH L-810 RED OBSTRUCTION LIGHT, SEE SPECIAL PROVISION SPECS. WIND CONE LIGHTING ASSEMBLY & OBSTRUCTION LIGHT SHALL HAVE LED (LIGHT EMITTING DIODE) TYPE LAMPS.
2. L-807 WIND CONE-12' INTERNALLY LIT WILL BE PAID FOR UNDER ITEM AS107812.
3. REBAR SHALL BE MANUFACTURED FROM 100% DOMESTIC STEEL.



**DETAIL B**  
NOT TO SCALE



**FOUNDATION DETAIL**  
NOT TO SCALE

ITEM AS107812 L-807 WC-12' INTERNALLY LIT IS UNDER ADDITIVE ALTERNATE NO. 1

NOV 23, 2011 8:47 AM HAGL000382  
p:\s\spi-svr306\hanson.dom\hanson\_projects\Documents\11\11A0080D\CAD\11A0080D\CAD\11A0080D\SheetE-506

REVISION	DATE

**LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS**

IL PROJ.: 3LF-4130 A.I.P. PROJ.: 3-17-0063-B18


Hanson Project No.	11A0080D
Filename	E-506.dwg
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	KNL 10/25/11
DRAWN	BAK 10/25/11
REVIEWED	CAH 11/04/11

**HANSON**  
Professional Services Inc. 2011  
Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2886  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide


REPLACE MRL'S ON  
RUNWAY 9-27

L-807 WIND CONE  
ELEVATION DETAIL





**REIL INSTALLATION DETAIL**  
NOT TO SCALE



**DETAIL "B"**  
(NOT TO SCALE)

**REIL NOTES**

- REILS FOR RUNWAY END 9 SHALL BE FAA APPROVED CONFORMING TO FAA AC 150/5345-51B "SPECIFICATION FOR DISCHARGE-TYPE FLASHING LIGHT EQUIPMENT", TYPE L-8491-REIL POWERED BY CONSTANT CURRENT 6.6 AMP POWER SUPPLY, STYLE A - UNIDIRECTIONAL, HIGH INTENSITY, ONE BRIGHTNESS STEP. SEE SPECIAL PROVISION SPECS AR125610 FOR ADDITIONAL REQUIREMENTS ON REILS.
- REILS SHALL BE AIMED AT ANGLE 10 DEGREES VERTICALLY AND TOED OUT 15 DEGREES FROM THE LINE PARALLEL TO THE RUNWAY CENTERLINE.
- ANY AND ALL TRENCHES AND DISTURBED AREAS WILL BE BACKFILLED AND RESTORED TO A SMOOTH GRADE AND SEEDED TO THE SATISFACTION OF THE ENGINEER. ALL TRENCH SETTLEMENT SHALL BE CORRECTED FOR A PERIOD OF ONE YEAR. RESTORATION, GRADING, SEEDING, AND MULCHING OF AREAS DISTURBED DURING THE REIL INSTALLATION AND ASSOCIATED CABLE WILL BE INCIDENTAL TO THE INSTALLATION OF THE REILS.
- GROUNDING FOR REILS.** GROUNDING FOR REILS SHALL CONFORM TO THE RESPECTIVE REIL MANUFACTURER'S INSTALLATION INSTRUCTIONS, AS DETAILED ON THE PLANS, AND AS SPECIFIED HEREIN. FURNISH AND INSTALL A 3/4-INCH DIAMETER BY 10-FOOT LONG COPPER CLAD GROUND ROD AT EACH REIL UNIT. GROUND RODS SHALL BE BURIED 30" MINIMUM BELOW GRADE. BOND EACH REIL UNIT HOUSING AND THE REIL BASE CAN TO THE RESPECTIVE GROUND ROD IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS WITH A #6 AWG BARE SOLID OR STRANDED (PER REIL MANUFACTURER REQUIREMENTS) COPPER GROUNDING ELECTRODE CONDUCTOR. ALL CONNECTIONS TO GROUND RODS SHALL BE EXOTHERMIC WELD AS MANUFACTURED BY CADWELD, THERMOWELD, ULTRAWELD, OR APPROVED EQUAL. CONNECTIONS TO REIL UNIT FRAMES SHALL BE AS RECOMMENDED BY THE MANUFACTURER OR WITH UL LISTED GROUNDING CONNECTORS. CONNECTION TO THE BASE / TRANSFORMER CAN SHALL BE WITH UL LISTED BOLTED CONNECTOR OR ONE-HOLE COMPRESSION LUG & 3/8" STAINLESS STEEL BOLTS, NUTS, & WASHERS.
- REFER TO PROPOSED ELECTRICAL PLANS FOR SITING AND ORIENTATION OF REIL'S.
- PRIOR TO FINAL ACCEPTANCE AND ACTIVATION, THE COMPLETED REIL INSTALLATION WILL REQUIRE, A FLIGHT CHECK TO BE SCHEDULED AND CONDUCTED BY THE FAA AND/OR ILLINOIS DIVISION OF AERONAUTICS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO HAVE A REPRESENTATIVE PRESENT TO MAKE ANY NECESSARY ADJUSTMENTS IN THE INSTALLATION AND/OR AIMING OF THE REIL UNITS.
- REILS WILL BE PAID FOR UNDER ITEM:  
AR125610 "REILS" \_\_\_\_\_ PER PAIR.

REVISION	DATE

**LITCHFIELD MUNICIPAL AIRPORT**  
**LITCHFIELD, ILLINOIS**

IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18


Hanson Project No.	11A0080D
File Name	E-508.dwg
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	KNL 09/12/11
DRAWN	BAK 09/12/11
REVIEWED	CAH 11/04/11

**HANSON**  
Professional Services Inc. 2011  
Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2986  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide


**REPLACE MRL'S ON**  
**RUNWAY 9-27**

REIL DETAILS TYPE  
L-8491, POWERED BY 6.6  
AMP SERIES CIRCUIT

NOV 23, 2011 8:55 AM HAGL000382  
p:\s\spi-svr306\hanson.dom\hanson\_projects\Documents\11A0080D\CAD\_Airport\SheetE-508



CABLE TO GROUND ROD




CABLE TO SURFACE

DETAIL NOTES

- EXOTHERMIC WELDS SHALL BE CADWELD AS MANUFACTURED BY ERICO PRODUCTS, SOLON, OHIO, ULTRAWELD AS MANUFACTURED BY HARGER LIGHTNING PROTECTION & GROUNDING EQUIPMENT, GRAYSLAKE, IL, THERMOWELD AS MANUFACTURED BY CONTINENTAL INDUSTRIES, TULSA, OKLAHOMA OR APPROVED EQUAL. VERIFY PROPER SIZES, MOLDS, TYPES, AND REQUIREMENTS FOR THE RESPECTIVE APPLICATION WITH THE MANUFACTURER, AND INSTALL PER THEIR DIRECTIONS.
- FOR APPLICATIONS TO GALVANIZED STEEL OR PAINTED STEEL, REMOVE GALVANIZING AND/OR PAINT & CLEAN THE SURFACE TO EXPOSE BARE STEEL BEFORE MAKING EXOTHERMIC WELD CONNECTION.
- VERIFY EXOTHERMIC MOLDS ARE SUITABLE FOR USE WITH THE RESPECTIVE TYPE (SOLID OR STRANDED) & SIZE CONDUCTOR.

EXOTHERMIC WELD DETAILS

NOT TO SCALE




DETAIL A

NOT TO SCALE

NOTES

- REFERENCES TO THOMPSON ARE THOMPSON LIGHTNING PROTECTION INC., 901 SIBLEY MEMORIAL HWY, ST. PAUL, MN 55188, PHONE: 651-455-7661, 800-777-1230, FAX: 651-455-2545.
- VERIFY LIGHTNING PROTECTION COMPONENTS AND CATALOG NUMBERS WITH THE RESPECTIVE LIGHTNING PROTECTION EQUIPMENT MANUFACTURER.
- CLEAN ALL CONNECTIONS TO EXPOSE BARE METAL.



LIGHTNING PROTECTION DETAIL FOR AIRPORT ROTATING BEACON

NTS

ITEM AT800591  
UPGRADE AIRPORT  
ROTATING BEACON  
IS UNDER ADDITIVE  
ALTERNATE NO. 2

AIRPORT ROTATING BEACON LOAD CENTER SCHEDULE

CKT #	DUTY	SIZE	SIZE	DUTY	CKT #
1	BLANK		30A 1P	SURGE PROTECTOR (PHASE A)	2
3	BLANK		30A 1P	SURGE PROTECTOR (PHASE B)	4
5	AIRPORT ROTATING BEACON	15A 1P		BLANK	6
7	OBSTRUCTION LIGHTS	15A 1P		BLANK	8
9	BLANK			BLANK	10
11	BLANK			BLANK	12



100 AMP, 120/240 VAC, 1 PHASE, 3 WIRE, 12 CIRCUIT LOAD CENTER WITH MAIN LUGS IN A NEMA 3R RAIN PROOF ENCLOSURE, SQUARE D CAT. NO. Q0112L125GRB WITH EQUIPMENT GROUND BAR KIT OR APPROVED EQUAL.

NOTES

- INCLUDE EQUIPT GROUND BAR KIT.
- ALL BREAKERS SHALL HAVE 10,000 AIC RATING AT 120/240 VAC.
- PHASE "A" SHALL BE SWITCHED THROUGH A LIGHTING CONTACTOR AT THE TERMINAL BUILDING. PHASE "B" SHALL BE UNSWITCHED.
- INCLUDE ENGRAVED PHENOLIC LEGEND PLATE LABELED ARB PANEL, 120/240 VAC, 1PH, 3W, FED FROM VAULT.
- SURGE PROTECTORS SHALL BE SUITABLE FOR 120VAC, 1PH, 2W PLUS GROUND, 30KA (MINIMUM) SURGE CURRENT RATING, JOSLYN MODEL 1260-21 OR LIGHTING PROTECTION CORP. MODEL LPC 11765-132, OR APPROVED EQUAL. FURNISH & INSTALL TWO SURGE PROTECTORS (ONE FOR EACH PHASE).
- LOAD CENTER SHALL BE MANUFACTURED IN THE UNITED STATES TO COMPLY WITH THE AIRPORT IMPROVEMENT PROGRAM BUY AMERICAN REQUIREMENTS. PROVIDE CERTIFICATION OF MANUFACTURE IN THE UNITED STATES WITH SHOP DRAWING SUBMITTAL.

REVISION	DATE	REVISION AS PER IDA COMMENTS
	11/23/11	

LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS

IL PROJ.: 3LF-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
File Name	E-507.dwg
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	KNL 09/12/11
DRAWN	BAK 09/12/11
REVIEWED	CAH 11/04/11

**HANSON**  
© Copyright Hanson Professional Services Inc. 2011  
Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2986  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide

REPLACE MRL'S ON  
RUNWAY 9-27

AIRPORT ROTATING  
BEACON UPGRADE  
DETAILS AND NOTES

GENERAL NOTES

- 1. ALL ELECTRICAL EQUIPMENT SHALL BE INSTALLED IN CONFORMANCE WITH NFPA 70 - NATIONAL ELECTRICAL CODE (NEC) MOST CURRENT ISSUE IN FORCE, THE RESPECTIVE EQUIPMENT MANUFACTURER'S DIRECTIONS AND ALL OTHER APPLICABLE LOCAL CODES, LAWS, ORDINANCES, AND REQUIREMENTS IN FORCE. ANY INSTALLATIONS WHICH VOID THE U.L. LISTING, ETL LISTING (OR OTHER THIRD PARTY LISTING) AND/OR THE MANUFACTURER'S WARRANTY OF A DEVICE WILL NOT BE PERMITTED.
2. CONTRACTOR SHALL KEEP A COPY OF THE LATEST NEC IN FORCE ON SITE AT ALL TIMES DURING CONSTRUCTION FOR USE AS A REFERENCE.
3. CONTRACTOR SHALL COORDINATE WORK AND ANY POWER OUTAGES AND/OR SHUT DOWN OF SYSTEMS WITH THE RESPECTIVE FACILITY OWNER PERSONNEL AND THE AIRPORT MANAGER/DIRECTOR. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).
4. THE CONTRACTOR SHALL ASCERTAIN THAT ALL LIGHTING SYSTEM COMPONENTS FURNISHED BY HIM, INCLUDING FAA APPROVED EQUIPMENT, ARE COMPATIBLE IN ALL RESPECTS WITH EACH OTHER AND THE REMAINDER OF THE NEW/EXISTING SYSTEM. ANY NONCOMPATIBLE COMPONENTS FURNISHED BY THIS CONTRACTOR SHALL BE REPLACED BY HIM AT NO ADDITIONAL COST TO THE AIRPORT SPONSOR WITH A SIMILAR UNIT, APPROVED BY THE ENGINEER (DIFFERENT MODEL OR DIFFERENT MANUFACTURER) THAT IS COMPATIBLE WITH THE REMAINDER OF THE AIRPORT LIGHTING SYSTEM.
5. IN CASE THE CONTRACTOR ELECTS TO FURNISH AND INSTALL AIRPORT LIGHTING EQUIPMENT REQUIRING ADDITIONAL WIRING, TRANSFORMERS, ADAPTORS, MOUNTINGS, ETC., TO THOSE SHOWN ON THE DRAWINGS AND/OR LISTED IN THE SPECIFICATION, ANY COST FOR THESE ITEMS SHALL BE INCIDENTAL TO THE EQUIPMENT COST.
6. THE CONTRACTOR INSTALLED EQUIPMENT (INCLUDING FAA APPROVED) SHALL NOT GENERATE ANY ELECTROMAGNETIC INTERFERENCE IN THE EXISTING AND/OR NEW COMMUNICATIONS, WEATHER, AIR NAVIGATION, AND AIR TRAFFIC CONTROL EQUIPMENT. ANY EQUIPMENT GENERATING SUCH INTERFERENCE SHALL BE REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST WITH THE EQUIPMENT MEETING THE APPLICABLE SPECIFICATIONS AND NOT GENERATING ANY INTERFERENCE.
7. WHEN A SPECIFIC TYPE, STYLE, CLASS, ETC. OF FAA APPROVED EQUIPMENT IS SPECIFIED ONLY THAT TYPE, STYLE, CLASS, WILL BE ACCEPTABLE, EVEN THOUGH EQUIPMENT OF OTHER TYPES STYLES, CLASSES, ETC. MAY BE APPROVED.
8. ANY AND ALL INSTRUCTIONS FROM THE RESIDENT ENGINEER TO THE CONTRACTOR REGARDING CHANGES IN OR DEVIATIONS FROM THE PLANS AND SPECIFICATIONS SHALL BE IN WRITING WITH COPIES SENT TO THE AIRPORT SPONSOR AND THE ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF AERONAUTICS). THE CONTRACTOR SHALL NOT ACCEPT ANY VERBAL INSTRUCTIONS FROM THE RESIDENT ENGINEER REGARDING ANY CHANGES FROM THE PLANS AND SPECIFICATIONS.
9. A MINIMUM OF THREE COPIES OF THE INSTRUCTION BOOK SHALL BE SUPPLIED WITH EACH DIFFERENT TYPE OF EQUIPMENT. THE BOOKS DESCRIBING A MORE SOPHISTICATED TYPE OF EQUIPMENT, SUCH AS REGULATORS, PAPI, REIL, ETC. AS A MINIMUM SHALL CONTAIN THE FOLLOWING:
A. A DETAILED DESCRIPTION OF THE OVERALL EQUIPMENT AND ITS INDIVIDUAL COMPONENTS.
B. THEORY OF OPERATION INCLUDING THE FUNCTION OF EACH COMPONENT.
C. INSTALLATION INSTRUCTION.
D. START-UP INSTRUCTIONS.
E. PREVENTATIVE MAINTENANCE REQUIREMENTS.
F. CHART FOR TROUBLE-SHOOTING.
G. COMPLETE POWER AND CONTROL DETAILED WIRING DIAGRAM(S), SHOWING EACH CONDUCTOR/CONNECTION/COMPONENT - "BLACK" BOXES ARE NOT ACCEPTABLE. THE DIAGRAM OF THE NARRATIVE SHALL SHOW VOLTAGE/CURRENTS/WAVE SHAPES AT STRATEGIC LOCATIONS TO BE USED WHEN CHECKING AND/OR TROUBLE-SHOOTING THE EQUIPMENT. WHEN THE EQUIPMENT HAS SEVERAL MODES OF OPERATION, SUCH AS SEVERAL BRIGHTNESS STEPS, THESE PARAMETERS SHALL BE INDICATED FOR ALL DIFFERENT MODES.
H. PARTS LIST WHICH WILL INCLUDE ALL MAJOR AND MINOR COMPONENTS SUCH AS RESISTORS, DIODES, ETC. IT SHALL INCLUDE A COMPLETE NOMENCLATURE OF EACH COMPONENT AND, IF APPLICABLE, THE NAME OF ITS MANUFACTURER AND THE CATALOG NUMBER.
I. SAFETY INSTRUCTIONS.

POWER AND CONTROL NOTES

- 1. PROVIDE LEGEND PLATES FOR ALL ELECTRICAL EQUIPMENT TO IDENTIFY FUNCTION, CIRCUIT VOLTAGE AND PHASE. WHERE THE EQUIPMENT CONTAINS FUSES, ALSO IDENTIFY THE FUSE OR FUSE LINK AMPERE RATING. WHERE THE EQUIPMENT DOES NOT HAVE SUFFICIENT AREA TO INSTALL LEGEND PLATES, THE LEGEND PLATES SHALL BE INSTALLED ON THE WALL NEXT TO THE UNIT. LEGEND PLATES SHALL BE WEATHERPROOF ENGRAVED PLASTIC OR PHENOLIC MATERIAL, 1/4" HIGH BLACK LETTERS ON A WHITE BACKGROUND UNLESS NOTED OTHERWISE. SECURE WITH WEATHERPROOF ADHESIVE AND MACHINE SCREWS. FURNISH ADDITIONAL LEGEND PLATES WHERE REQUIRED BY CODE, FOR ADDITIONAL EQUIPMENT, AS DETAILED HEREIN ON THE PLANS, AND AS NOTED IN THE SPECIAL PROVISION SPECIFICATIONS.
2. COLOR CODE ALL PHASE WIRING BY THE USE OF COLORED WIRE INSULATION AND/OR COLORED TAPE. WHERE TAPE IS USED, THE WIRE INSULATION SHALL BE BLACK. BLACK AND RED SHALL BE USED FOR PHASE CONDUCTORS ON 120/240VAC SINGLE-PHASE, THREE WIRE SYSTEMS AND BLACK, ORANGE (FOR HIGH LEG) AND BLUE SHALL BE USED FOR PHASE CONDUCTORS ON 240/120VAC THREE-PHASE, FOUR WIRE SYSTEMS. NEUTRAL CONDUCTORS, SIZE NO. 6 AWG OR SMALLER, SHALL BE IDENTIFIED BY A CONTINUOUS WHITE OR NATURAL GRAY OUTER FINISH ALONG ITS ENTIRE LENGTH. NEUTRAL CONDUCTORS LARGER THAN NO. 6 AWG SHALL BE IDENTIFIED EITHER BY A CONTINUOUS WHITE OR NATURAL GRAY OUTER FINISH ALONG ITS ENTIRE LENGTH OR BY THE USE OF WHITE TAPE AT ITS TERMINATIONS AND INSIDE ACCESSIBLE WIREWAYS. INSULATED GROUND CONDUCTORS SHALL HAVE GREEN COLORED INSULATION FOR ALL CONDUCTOR SIZES (AWG OR KCMIL).
3. ALL BRANCH CIRCUIT CONDUCTORS CONNECTED TO A PARTICULAR PHASE SHALL BE IDENTIFIED WITH THE SAME COLOR. THE COLOR CODING SHALL BE EXTENDED TO THE POINT OF UTILIZATION.
4. IN CONTROL WIRING THE SAME COLOR SHALL BE USED THROUGHOUT THE SYSTEM FOR THE SAME FUNCTION, SUCH AS 10%, 30%, 100% BRIGHTNESS CONTROL, ETC.
5. LOW VOLTAGE (600 V.) AND HIGH VOLTAGE (5000 V.) CONDUCTORS SHALL BE INSTALLED IN SEPARATE WIREWAYS.
6. NEATLY LACE WIRING IN DISTRIBUTION PANELS, WIREWAYS, SWITCHES AND JUNCTION/PULL BOXES.
7. THE MINIMUM SIZE OF PULL/JUNCTION BOXES, REGARDLESS OF THE QUANTITY AND SIZE OF THE CONDUCTORS SHOWN, SHALL BE AS FOLLOWS:
A. IN STRAIGHT PULLS THE LENGTH OF THE BOX SHALL NOT BE LESS THAN EIGHT TIMES THE TRADE DIAMETER OF THE LARGER CONDUIT. THE TOTAL AREA (INCLUDING THE CONDUIT CROSS-SECTIONAL AREA) OF A BOX END SHALL BE AT LEAST 3 TIMES GREATER THAN THE TOTAL TRADE CROSS-SECTIONAL AREA OF THE CONDUITS TERMINATING AT THE END.
B. IN ANGLE PULLS OR 'U' PULLS THE DISTANCE BETWEEN EACH CONDUIT ENTRY INSIDE THE BOX AND THE OPPOSITE WALL OF THE BOX SHALL NOT BE LESS THAN SIX (6) TIMES THE TRADE DIAMETER OF THE LARGEST CONDUIT. THIS DISTANCE SHALL BE INCREASED FOR ADDITIONAL ENTRIES BY THE AMOUNT OF THE SUM OF THE DIAMETERS OF ALL OTHER CONDUIT ENTRIES ON THE SAME WALL AS THE BOX. THE DISTANCE BETWEEN CONDUIT ENTRIES ENCLOSING THE SAME CONDUCTOR SHALL NOT BE LESS THAN SIX TIMES THE TRADE DIAMETER OF THE LARGEST CONDUIT.
8. A RUN OF CONDUIT BETWEEN TERMINATIONS AT EQUIPMENT ENCLOSURES, SQUARE DUCTS AND PULL/JUNCTION BOXES, SHALL NOT CONTAIN MORE THAN THE EQUIVALENT OF FOUR QUARTER BENDS (360 DEGREES TOTAL), INCLUDING THOSE BENDS LOCATED IMMEDIATELY AT THE TERMINATIONS, CAST, CONDUIT TYPE OUTLETS SHALL NOT BE TREATED AS PULL/JUNCTION BOXES.
9. EQUIPMENT CABINETS SHALL NOT BE USED AS PULL/JUNCTION BOXES. ONLY WIRING TERMINATING AT THE EQUIPMENT SHALL BE BROUGHT INTO THESE ENCLOSURES.
10. SPLICES AND JUNCTION POINTS SHALL BE PERMITTED ONLY IN JUNCTION BOXES, DUCTS EQUIPPED WITH REMOVABLE COVERS, AND AT EASILY ACCESSIBLE LOCATIONS.
11. CIRCUIT BREAKERS IN POWER DISTRIBUTION PANEL(S) SHALL BE THERMAL-MAGNETIC MOLDED CASE, PERMANENT TRIP WITH 100 AMPERE, MINIMUM FRAME.
12. DUAL LUGS SHALL BE USED WHERE TWO (2) WIRES, SIZE NO. 6 OR LARGER, ARE TO BE CONNECTED TO THE SAME TERMINAL.
13. ALL INTERIOR WALL MOUNTED EQUIPMENT ENCLOSURES SHALL BE MOUNTED ON HOT DIPPED GALVANIZED STEEL STRUT SUPPORT, OR STAINLESS STEEL STRUT SUPPORT, WITH CORROSION RESISTANT HARDWARE.
14. SUPPORT FOR EXTERIOR MOUNTED EQUIPMENT SHALL USE HOT DIPPED GALVANIZED STEEL STRUT SUPPORT OR STAINLESS STEEL STRUT SUPPORT WITH STAINLESS STEEL HARDWARE. PROVIDE ZINC RICH PAINT APPLIED TO FIELD CUTS OF GALVANIZED STEEL SUPPORT TO MINIMIZE THE POTENTIAL FOR CORROSION PER THE RESPECTIVE STRUT SUPPORT MANUFACTURER'S RECOMMENDATIONS.
15. CONDUITS FOR ELECTRIC SERVICE ENTRANCE AND FEEDERS SHALL BE AS DETAILED HEREIN ON THE PLANS. WHERE GALVANIZED RIGID STEEL CONDUIT IS SPECIFIED IT SHALL HAVE THREADED FITTINGS. SET SCREW TYPE FITTINGS WILL NOT BE ACCEPTABLE. CONDUITS FOR UNDERGROUND APPLICATIONS SHALL BE AS DETAILED HEREIN. CONDUITS FOR GROUNDING ELECTRODE CONDUCTORS OR INDIVIDUAL GROUNDING CONDUCTORS SHALL BE SCHEDULE 40 OR SCHEDULE 80 PVC.
16. PROVIDE LIQUID TIGHT FLEXIBLE METAL CONDUIT AT CONNECTIONS TO EQUIPMENT SUBJECT TO VIBRATION OR WHERE FLEXIBILITY IS REQUIRED. LIQUID TIGHT FLEXIBLE METAL CONDUIT AND ASSOCIATED FITTINGS SHALL BE U.L. LISTED TO MEET THE REQUIREMENTS OF NEC 350.6, SUITABLE FOR GROUNDING, SUNLIGHT RESISTANT, AND RESISTANT TO OIL, GASOLINE, AND GREASE. LIQUID TIGHT FLEXIBLE METAL CONDUIT THAT IS USED FOR FLEXIBILITY (INCLUDING CONNECTIONS TO MOTORS, TRANSFORMERS, & CONSTANT CURRENT REGULATORS) SHALL REQUIRE AN EXTERNAL BONDING JUMPER OR INTERNAL EQUIPMENT GROUNDING CONDUCTOR PER NEC 350.60. DO NOT INSTALL LIQUID TIGHT FLEXIBLE METAL CONDUIT THAT IS NOT UL LISTED. CONFIRM LIQUID-TIGHT FLEXIBLE METAL CONDUIT BEARS THE UL LABEL PRIOR TO INSTALLING IT.
17. UNLESS OTHERWISE SHOWN, ALL EXPOSED CONDUITS SHALL BE RUN PARALLEL TO OR AT RIGHT ANGLES WITH THE LINES OF THE STRUCTURE.
18. ALL STEEL CONDUITS, FITTINGS, NUTS, BOLTS, ETC. SHALL BE GALVANIZED.
19. USE CONDUIT BUSHINGS AT EACH CONDUIT TERMINATION. WHERE NO. 4 AWG OR LARGER UNDERGROUND WIRE IS INSTALLED, USE INSULATED BUSHINGS.
20. USE DOUBLE LOCK NUTS AT EACH CONDUIT TERMINATION.
21. WRAP ALL PRIMARY AND SECONDARY POWER TRANSFORMER CONNECTIONS WITH SUFFICIENT LAYERS OF INSULATING TAPE (3M SCOTCH 23 ALL-VOLTAGE SPLICING TAPE, 3M SCOTCH 130C LINERLESS RUBBER SPLICING TAPE, OR APPROVED EQUAL) AND COVER WITH VINYL ELECTRICAL TAPE (3M SCOTCH 88 VINYL ELECTRICAL TAPE OR APPROVED EQUAL) FOR FULL VALUE OF CABLE INSULATION VOLTAGE.
22. UNLESS OTHERWISE NOTED, ALL SINGLE CONDUCTOR CONTROL WIRING SHALL BE NO. 12 AWG. COPPER MINIMUM.
23. THE FOLLOWING SHALL APPLY TO RELAY/CONTACTOR PANELS/ENCLOSURES:
A. FOR INTERIOR LOCATIONS ALL COMPONENTS SHALL BE MOUNTED IN NEMA 12 (DUST TIGHT) ENCLOSURE(S) WITH VERTICALLY HINGED COVERS. FOR EXTERIOR/OUTDOOR LOCATIONS ALL COMPONENTS SHALL BE MOUNTED IN NEMA 4X STAINLESS STEEL ENCLOSURE(S) WITH VERTICALLY HINGED COVERS. ALL CONDUIT ENTRIES INTO NEMA 4, 4X ENCLOSURES SHALL HAVE NEMA 4 HUBS LISTED SUITABLE FOR THE RESPECTIVE ENCLOSURE TO MAINTAIN THE NEMA 4, 4X RATING OF THE ENCLOSURE.
B. THE ENCLOSURE(S) SHALL HAVE AMPLE SPACE FOR THE CIRCUIT COMPONENTS, TERMINAL BLOCKS AND INCOMING AND INTERNAL WIRING.
C. ALL CONTROL CONDUCTOR TERMINATIONS SHALL BE OF THE OPEN-EYE CONNECTOR/SCREW TYPE. SOLDERED CLOSED-EYE TERMINATIONS, OR TERMINATIONS WITHOUT CONNECTORS ARE NOT ACCEPTABLE.
D. WHEN THE ENCLOSURE COVER IS OPENED, ALL CIRCUIT COMPONENTS, WIRING AND TERMINALS SHALL BE EXPOSED AND ACCESSIBLE WITHOUT REMOVAL OF ANY PANELS, COVERS, ETC., EXCEPT THOSE COVERING HIGH VOLTAGE COMPONENTS.
E. ACCESS TO, OR REMOVAL OF A CIRCUIT COMPONENT OR TERMINAL BLOCK WILL NOT REQUIRE THE REMOVAL OF ANY OTHER CIRCUIT COMPONENT OR TERMINAL BLOCK.
F. EACH CIRCUIT COMPONENT SHALL BE CLEARLY IDENTIFIED INDICATING ITS CORRESPONDING NUMBER SHOWN ON THE DRAWINGS AND ITS FUNCTION.
G. A COMPLETE WIRING DIAGRAM SHALL BE MOUNTED ON THE INSIDE OF THE COVER. THE DIAGRAM SHALL REPRESENT EACH CONDUCTOR BY A SEPARATE LINE.
H. THE DIAGRAM SHALL IDENTIFY EACH CIRCUIT COMPONENT AN NUMBERING AND COLOR OF EACH TERMINAL CONDUCTOR AND TERMINAL.
I. ALL WIRING SHALL BE NEATLY TRAINED AND LACED.
J. MINIMUM WIRE SIZE SHALL BE NO. 12 AWG.
24. FURNISH & INSTALL A WEATHERPROOF WARNING LABEL FOR EACH METER SOCKET, SERVICE DISCONNECT, SAFETY SWITCH, CUTOUT, PANELBOARD, & CONTROL PANEL TO WARN PERSONS OF POTENTIAL ELECTRIC ARC FLASH HAZARDS, PER THE REQUIREMENTS OF NEC 110.16 "FLASH PROTECTION".

REVISION DATE REVISION
LITCHFIELD MUNICIPAL AIRPORT LITCHFIELD, ILLINOIS
Hanson Project No. 11A0080D E-002.dwg
Scale NOT TO SCALE Date 10/28/2011
LAYOUT KNL 08/02/11
DRAWN BAK 08/02/11
REVIEWED CAH 11/04/11
REPLACE MRL'S ON RUNWAY 9-27
ELECTRICAL NOTES SHEET 1
20 of 34 sheets
IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18

NOV 23, 2011 8:58 AM H4GL000382
p:\s\spi-svr306\hanson\dom\hanson\Projects\Documents\11A0080D\CAD\Airport\SheetE-002

**AIRFIELD LIGHTING NOTES**


1. UNLESS OTHERWISE NOTED, ALL UNDERGROUND AIRFIELD LIGHTING SERIES CIRCUIT CONDUCTORS WHETHER DEB OR IN DUCT/CONDUIT SHALL BE FAA APPROVED 5000 VOLT L-824 TYPE. ALL UNDERGROUND FIELD POWER LOW VOLTAGE (600 VOLT & BELOW) CIRCUIT CONDUCTORS WHETHER DEB OR IN DUCT/CONDUIT SHALL BE UL LISTED 600 VOLT, TYPE XLP-USE-2 COPPER CONDUCTORS. CONDUCTOR SIZES SHALL BE AS SPECIFIED, HEREIN.
2. NO COMPONENTS OF PRIMARY CIRCUIT SUCH AS CABLE, CONNECTORS AND TRANSFORMERS SHALL BE BROUGHT ABOVE GROUND AT EDGE LIGHTS, SIGNS, REIL, PAPI, ETC.
3. THERE SHALL BE NO EXPOSED POWER/CONTROL CABLES BETWEEN THE POINT WHERE THEY LEAVE THE UNDERGROUND (DEB OR L-867 BASES) AND WHERE THEY ENTER THE EQUIPMENT (SUCH AS TAXIWAY SIGNS, PAPI, REIL, ETC.) ENCLOSURES. THESE CABLES SHALL BE ENCLOSED IN RIGID CONDUIT OR IN FLEXIBLE, WATERTIGHT CONDUIT WITH BREAKABLE COUPLING(S) AT THE GRADE OR THE HOUSING COVER, AS SHOWN IN APPLICABLE DETAILS.
4. THE JOINTS OF THE L-823 PRIMARY CONNECTORS SHALL BE WRAPPED WITH AT LEAST ONE LAYER OF RUBBER OR SYNTHETIC RUBBER TAPE AND ONE LAYER OF PLASTIC TAPE, ONE-HALF LAPPED, EXTENDING AT LEAST 1-1/2 INCHES ON EACH SIDE OF THE JOINT, AS SHOWN ON ELECTRICAL DETAILS SHEET 1.
5. THE CABLE ENTRANCE INTO THE FIELD-ATTACHED L-823 CONNECTORS SHALL BE ENCLOSED BY A HEAT-SHRINKABLE TUBING WITH CONTINUOUS INTERNAL ADHESIVE, AS SHOWN ON ELECTRICAL DETAILS SHEET 1.
6. L-823 TYPE II, TWO-CONDUCTOR SECONDARY CONNECTORS SHALL BE CLASS 'A' (FACTORY MOLDED).
7. THERE SHALL BE NO SPLICES IN THE SECONDARY CABLE(S) WITHIN THE STEMS OF A RUNWAY/TAXIWAY EDGE/THRESHOLD LIGHTING FIXTURE AND THE WIREWAYS LEADING TO TAXIWAY SIGNS AND PAPI/REIL EQUIPMENT.
8. ELECTRICAL INSULATING GREASE SHALL BE APPLIED WITHIN THE L-823, SECONDARY, TWO CONDUCTOR CONNECTORS TO PREVENT WATER ENTRANCE. THESE CONNECTORS SHALL NOT BE TAPED.
9. DEB ISOLATION TRANSFORMERS SHALL BE BURIED AT A DEPTH OF TEN (10") INCHES ON A LINE CROSSING THE LIGHT AND PERPENDICULAR TO THE RUNWAY/TAXIWAY CENTERLINE AT A LOCATION TWELVE (12") INCHES FROM THE LIGHT OPPOSITE FROM THE RUNWAY/TAXIWAY.
10. A SLACK OF THREE (3") FEET, MINIMUM, SHALL BE PROVIDED IN THE PRIMARY CABLE AT EACH TRANSFORMER/CONNECTOR TERMINATION. AT STAKE-MOUNTED LIGHTS, THE SLACK SHALL BE LOOSELY COILED IMMEDIATELY BELOW THE ISOLATION TRANSFORMER.
11. DIRECTION OF PRIMARY CABLES SHALL BE IDENTIFIED BY COLOR CODING AS FOLLOWS: WHEN FACING LIGHT WITH BACK TO PAVEMENT, CABLE TO THE LEFT IS CODED RED AND CABLE TO RIGHT IS CODED BLUE. THIS APPLIES TO STAKE MOUNTED LIGHTS AND BASE MOUNTED LIGHTS WHERE THE BASE HAS ONLY ONE ENTRANCE.
12. L-867 BASES SHALL BE SIZE B, 24" DEEP, CLASS I, UNLESS OTHERWISE NOTED.
13. BASE MOUNTED BREAKABLE COUPLINGS SHALL NOT HAVE WEEP HOLES TO THE OUTSIDE. PLUGGED UP HOLES SHALL NOT BE ACCEPTABLE. IT SHALL BE A 1/4" DIAMETER, MINIMUM, OR EQUIVALENT OPENING FOR DRAINAGE FROM THE SPACE AROUND THE SECONDARY CONNECTOR INTO THE L-867 BASE.
14. THE ELEVATION OF THE BREAKABLE COUPLING GROOVE SHALL NOT EXCEED 1-1/2" ABOVE THE EDGE OF THE COVER IN CASE OF BASE MOUNTED COUPLINGS, OR THE TOP OF THE STAKE IN CASE OF STAKE MOUNTED COUPLINGS.
15. WHERE THE BREAKABLE COUPLING IS NOT AN INTEGRAL PART OF THE LIGHT FIXTURE STEM OR MOUNTING LEG, A BEAD OF SILICON SEAL SHALL BE APPLIED COMPLETELY AROUND LIGHT STEM OR WIREWAY AT BREAKABLE COUPLING TO PROVIDE A WATERTIGHT SEAL.
16. TOPS OF THE STAKES SUPPORTING LIGHT FIXTURES SHALL BE FLUSH WITH THE SURROUNDING GRADE.
17. PLASTIC LIGHTING FIXTURE COMPONENTS, SUCH AS LAMP HEADS, STEMS, BREAKABLE COUPLINGS, BASE COVERS, BRACKETS, STAKES, SHALL NOT BE ACCEPTABLE.
18. THE TOLERANCE FOR THE HEIGHT OF RUNWAY/TAXIWAY EDGE LIGHTS SHALL BE: ONE (1) INCH. IN CASE OF STAKE MOUNTED LIGHTS, THE SPECIFIED LIGHTING FIXTURE HEIGHT SHALL BE MEASURED BETWEEN THE TOP OF THE STAKE AND THE TOP OF THE LENS. IN CASE OF BASE MOUNTED LIGHTS, THE SPECIFIED LIGHTING FIXTURE HEIGHT SHALL BE MEASURED BETWEEN THE TOP OF THE BASE FLANGE AND THE TOP OF THE LENS, THUS INCLUDING THE BASE COVER, THE FRANGIBLE COUPLING, THE STEM, THE LAMP HOUSING AND THE LENS.
19. THE TOLERANCE FOR THE LATERAL SPACING (LIGHT LANE TO RUNWAY/TAXIWAY CENTERLINE) OF RUNWAY/TAXIWAY EDGE LIGHTS SHALL BE ONE (1) INCH. THIS ALSO APPLIES AT INTERSECTIONS TO LATERAL SPACING BETWEEN LIGHTS OF A RUNWAY/TAXIWAY AND THE INTERSECTING RUNWAY/TAXIWAY.

20. ENTRANCES INTO L-867 BASES SHALL HAVE CONDUIT COUPLINGS OR REDUCERS TO INTERFACE UNIT DUCT/CONDUIT TO L-867 BASE HUBS, OR SHALL BE SEALED WITH HEAT SHRINK AS SHOWN IN DETAIL "B" ON ELECTRICAL DETAILS SHEET 1.
21. GALVANIZED/PAINTED EQUIPMENT/COMPONENT SURFACES SHALL NOT BE DAMAGED BY DRILLING, FILING, ETC. DRAIN HOLES IN METAL TRANSFORMER HOUSINGS SHALL BE MADE BEFORE GALVANIZING.
22. EDGE LIGHT NUMBERING TAGS SHALL BE FACING THE PAVEMENT.
23. CABLE/SPLICE/DUCT MARKERS SHALL BE PRECAST CONCRETE OF THE SIZE SHOWN. LETTERS/NUMBERS/ARROWS FOR THE LEGEND TO BE IMPRESSED INTO THE TOPS OF THE MARKERS SHALL BE PRE-ASSEMBLED AND SECURED IN THE MOLD BEFORE THE CONCRETE IS POURED. LEGEND INSCRIBED BY HAND IN WET CONCRETE SHALL NOT BE ACCEPTABLE.
24. ALL UNDERGROUND CABLE RUNS SHALL BE IDENTIFIED BY CABLE MARKERS AT 200 FEET MAXIMUM SPACING, WITH AN ADDITIONAL MARKER AT EACH CHANGE OF DIRECTION OF THE CABLE RUN. CABLE MARKERS SHALL BE INSTALLED IMMEDIATELY ABOVE THE CABLES.
25. THERE SHALL BE NO SPLICES BETWEEN THE ISOLATION TRANSFORMERS. L-823 CONNECTORS ARE ALLOWED AT TRANSFORMER CONNECTIONS ONLY, UNLESS OTHERWISE SHOWN.
26. APPLY AN OXIDE INHIBITING, ANTI-SEIZING COMPOUND TO ALL SCREWS, NUTS AND BREAKAGE COUPLING THREADS.
27. LOCATIONS OF ENDS OF ALL UNDERGROUND DUCTS SHALL BE IDENTIFIED BY DUCT MARKERS.
28. WHERE A PARALLEL, CONSTANT VOLTAGE PAPI SYSTEM IS PROVIDED, THE "T" SPLICES SHALL BE OF THE CAST TYPE.
29. CONCRETE USED FOR SLABS, FOOTINGS, BACKFILL AROUND TRANSFORMER HOUSINGS, MARKINGS, ETC. SHALL BE 3500 PSI, AIR-ENTRAINED.
30. ALL POWER AND CONTROL CABLES IN MAN/HAND HOLES SHALL BE TAGGED. USE EMBOSSED COPPER STRIPS TO BE ATTACHED AT BOTH ENDS TO THE CABLE BY THE USE OF PLASTIC STRAPS. MINIMUM OF TWO TAGS SHALL BE PROVIDED ON EACH CABLE IN A MAN/HAND HOLE-ONE AT THE CABLE ENTRANCE AND ONE AT THE CABLE EXIT.
31. THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT. ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. **CONTACT J.U.L.I.E. FOR UTILITY INFORMATION AT 1-800-892-0123.** ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.
32. WHEN PREPARING CABLE FOR SPLICES, THE CONTRACTOR SHALL USE A CABLE STRIPPER/PENCILLER WHENEVER CABLE CONNECTIONS ARE MADE.

**GROUNDING NOTES FOR AIRFIELD LIGHTING**

1. GROUNDING FOR RUNWAY LIGHTS, TAXIWAY LIGHTS, AND LIGHTED TAXI GUIDANCE SIGNS SHALL BE AS DETAILED ON THE PLANS AND AS SPECIFIED HEREIN. PER FAA AC 150/5340-30F DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS, CHAPTER 12, PART 12.6; A GROUND MUST BE INSTALLED AT EACH LIGHT FIXTURE. THE PURPOSE OF THE LIGHT BASE GROUND IS TO PROVIDE A DEGREE OF PROTECTION FOR MAINTENANCE PERSONNEL FROM POSSIBLE CONTACT WITH AN ENERGIZED LIGHT BASE OR MOUNTING STAKE THAT MAY RESULT FROM A SHORTED POWER CABLE OR ISOLATION TRANSFORMER. A LIGHT BASE GROUND SHALL BE INSTALLED AT EACH TRANSFORMER BASE/LIGHT CAN ASSOCIATED WITH RUNWAY LIGHTS, TAXIWAY LIGHTS, AND LIGHTED TAXI GUIDANCE SIGNS. A LIGHT BASE GROUND SHALL ALSO BE INSTALLED AT EACH STAKE MOUNTED LIGHT FIXTURE. A LIGHT BASE GROUND SHALL BE INSTALLED AND CONNECTED TO THE METAL FRAME OF EACH TAXI GUIDANCE SIGN AS DETAILED ON THE PLANS AND IN ACCORDANCE WITH THE RESPECTIVE TAXI GUIDANCE SIGN MANUFACTURER RECOMMENDATIONS. THE LIGHT BASE GROUND SHALL BE A #6 AWG BARE COPPER CONDUCTOR BONDED TO THE GROUND LUG ON THE RESPECTIVE L-867 TRANSFORMER BASE/LIGHT CAN OR MOUNTING STAKE AND A 5/8-INCH DIAMETER BY 8-FOOT LONG (MINIMUM) UL LISTED COPPER CLAD GROUND ROD. CONNECTIONS TO GROUND LUGS ON THE L-867 TRANSFORMER BASE/LIGHT CAN OR MOUNTING STAKE SHALL BE WITH A UL LISTED GROUNDING CONNECTOR. CONNECTIONS TO GROUND RODS SHALL BE MADE WITH EXOTHERMIC WELD TYPE CONNECTORS, CADWELD BY ERICO PRODUCTS, INC., SOLON, OHIO, (PHONE: 800-248-9353), THERMOWELD BY CONTINENTAL INDUSTRIES, INC., TULSA, OKLAHOMA (PHONE: 918-663-1440), ULTRAWELD BY HARGER, GRAYSLAKE, ILLINOIS (PHONE: 800-842-7437), OR APPROVED EQUAL. EXOTHERMIC WELD CONNECTIONS SHALL BE INSTALLED IN CONFORMANCE WITH THE RESPECTIVE MANUFACTURER'S DIRECTIONS USING MOLDS AS REQUIRED FOR EACH RESPECTIVE APPLICATION. BOLTED CONNECTIONS WILL NOT BE PERMITTED AT GROUND RODS. TOP OF GROUND RODS SHALL BE BURIED 12 INCHES MINIMUM BELOW GRADE, UNLESS SPECIFIED OTHERWISE HEREIN, FOR RESPECTIVE APPLICATIONS.
2. FOR BASE MOUNTED LIGHT FIXTURES THE LIGHT FIXTURE MUST BE BONDED TO THE LIGHT BASE INTERNAL GROUND LUG VIA A #6 AWG STRANDED COPPER WIRE RATED FOR 600 VOLTS WITH GREEN XHHW OR USE INSULATION. THE GROUND WIRE LENGTH MUST BE SUFFICIENT TO ALLOW THE REMOVAL OF THE LIGHT FIXTURE FROM THE LIGHT BASE FOR ROUTINE MAINTENANCE. SEE THE LIGHT FIXTURE MANUFACTURER'S INSTRUCTIONS FOR PROPER METHODS OF ATTACHING A BONDING WIRE.
3. CLEAN ALL METAL SURFACES BEFORE MAKING GROUND CONNECTIONS. METALLIC SURFACES TO BE JOINED SHALL BE PREPARED BY THE REMOVAL OF ALL NON-CONDUCTIVE MATERIAL PER 2011 NATIONAL ELECTRICAL CODE ARTICLE 250-12.
4. PER FAA 150/5340-30F THE RESISTANCE TO GROUND OF THE RESPECTIVE MOUNTING STAKE OR LIGHT BASE (WITH GROUND ROD CONNECTED) MUST BE 25 OHMS OR LESS.

NOV 23, 2011 9:36 AM H:\GLO00382.pw\lspj-svr306\hanson.dcm\hanson\_projects\Documents\11\Jobs\11A0080D\CAD\Aircraft\SheetE-003

REVISION 11/23/11 REVISED AS PER IDA COMMENTS					
DATE 11/23/11					
<b>LITCHFIELD MUNICIPAL AIRPORT LITCHFIELD, ILLINOIS</b>					
I.L. PROJ.: 3LF-4130 A.I.P. PROJ.: 3-17-0063-B18					
Hanson Project No. 11A0080D	E-003.dwg	NOT TO SCALE	10/28/2011	08/02/11	08/02/11
File Name	Scale	Date	LAYOUT	KNL	BAK
Scale	Date	LAYOUT	DRAWN	BAK	08/02/11
Date	LAYOUT	DRAWN	REVIEWED	CAH	11/04/11
 © Copyright Hanson Professional Services Inc. 2011 <b>Hanson Professional Services Inc.</b> 1525 South Sixth Street Springfield, Illinois 62703-2886 Ph: (217) 788-2450 Fax: (217) 788-2503 www.hanson-inc.com Offices Nationwide					
REPLACE MRL'S ON RUNWAY 9-27			ELECTRICAL NOTES SHEET 2		
<span style="font-size: 24pt; font-weight: bold;">21</span> 21 of 34 sheets					

ELECTRICAL LEGEND - ONE-LINE DIAGRAM

	CABLE TERMINATOR/LUG
	TRANSFORMER
	DISCONNECT SWITCH
	FUSIBLE DISCONNECT SWITCH
	CIRCUIT BREAKER
	THERMAL MAGNETIC CIRCUIT BREAKER
	FUSE
	TRANSIENT VOLTAGE SURGE SUPPRESSOR OR SURGE PROTECTOR DEVICE
	GROUND - GROUND ROD, GROUNDING ELECTRODE, OR AT EARTH POTENTIAL
	INDICATING LIGHT
	MOTOR
	LOAD, MOTOR, # = HORSEPOWER
	ELECTRIC UTILITY METER BASE
	JUNCTION BOX WITH SPLICE
	EQUIPMENT, XXX = DEVICE DESCRIPTION
	GROUND BUS OR TERMINAL
	NEUTRAL BUS
	PANELBOARD WITH MAIN LUGS
	PANELBOARD WITH MAIN BREAKER
	FUSE PANEL WITH MAIN FUSE PULLOUT
	DUPLEX RECEPTACLE 120V SINGLE PHASE GROUNDING TYPE
	CONTROL STATION
	TRANSFER SWITCH
	ENGINE GENERATOR SET

ELECTRICAL LEGEND - SCHEMATIC

	NORMALLY OPEN (N.O.) CONTACT
	NORMALLY CLOSED (N.C.) CONTACT
	STARTER COIL, * = STARTER NUMBER
	OVERLOAD RELAY CONTACT
	CONTROL RELAY, * = CONTROL RELAY NUMBER
	RELAY, * = RELAY NUMBER
	TOGGLE SWITCH / 2 POSITION SWITCH
	2-POSITION SELECTOR SWITCH
	3-POSITION SELECTOR SWITCH (H-O-A SHOWN)
	2 POLE DISCONNECT SWITCH
	3 POLE DISCONNECT SWITCH
	PHOTOCELL
	TERMINAL BLOCK, * = TERMINAL NUMBER
	DEVICE TERMINAL, * = DEVICE TERMINAL NUMBER
	INTERNAL PANEL WIRING
	FIELD WIRING
	FUSE
	GROUND BUS OR TERMINAL
	NEUTRAL BUS
	GROUND, GROUND ROD, GROUND BUS
	INDUSTRIAL CONTROL RELAY OR LIGHTING CONTACTOR
	S1 CUTOUT HANDLE REMOVED
	S1 CUTOUT HANDLE INSERTED
	N.O. THERMAL SWITCH
	N.C. THERMAL SWITCH
	L-830 SERIES ISOLATION TRANSFORMER

ELECTRICAL ABBREVIATIONS

A.F.F.	ABOVE FINISHED FLOOR
A, AMP	AMPERES
ATS	AUTOMATIC TRANSFER SWITCH
AWG	AMERICAN WIRE GAUGE
BKR	BREAKER
C	CONDUIT
CB	CIRCUIT BREAKER
CKT	CIRCUIT
CR	CONTROL RELAY
CU	COPPER
DPDT	DOUBLE POLE DOUBLE THROW
DPST	DOUBLE POLE SINGLE THROW
EM	EMERGENCY
EMT	ELECTRICAL METALLIC TUBING
ENCL	ENCLOSURE
EP	EXPLOSION PROOF
ES	EMERGENCY STOP
ETL	INTERTEK - ELECTRICAL TESTING LABS
ETM	ELAPSE TIME METER
GFCI	GROUND FAULT CIRCUIT INTERRUPTER
GFI	GROUND FAULT INTERRUPTER
GND	GROUND
GRSC	GALVANIZED RIGID STEEL CONDUIT
HID	HIGH INTENSITY DISCHARGE
HOA	HAND OFF AUTOMATIC
HP	HORSEPOWER
HPS	HIGH PRESSURE SODIUM
J	JUNCTION BOX
KVA	KILOVOLT AMPERE(S)
KW	KILOWATTS
LC	LIGHTING CONTACTOR
LTFMC	LIQUID TIGHT FLEXIBLE METAL CONDUIT (UL LISTED)
LTG	LIGHTING
LP	LIGHTING PANEL
MAX	MAXIMUM
MCB	MAIN CIRCUIT BREAKER
MCM	THOUSAND CIRCUAR MIL
MDP	MAIN DISTRIBUTION PANEL
MFR	MANUFACTURER
MH	METAL HALIDE
MIN	MINIMUM
MLO	MAIN LUGS ONLY
NEC	NATIONAL ELECTRICAL CODE (NFPA 70)
NC	NORMALLY CLOSED
NO	NORMALLY OPEN
NTS	NOT TO SCALE
OHE	OVERHEAD ELECTRIC
OL	OVERLOAD

ELECTRICAL ABBREVIATIONS (CONTINUED)

PB	PULL BOX
PC	PHOTO CELL
PDB	POWER DISTRIBUTION BLOCK
PNL	PANEL
RCPT	RECEPTACLE
R	RELAY
S	STARTER
SPD	SURGE PROTECTION DEVICE
SPST	SINGLE POLE SINGLE THROW
TVSS	TRANSIENT VOLTAGE SURGE SUPPRESSOR
TYP	TYPICAL
UG	UNDERGROUND
UGE	UNDERGROUND ELECTRIC
UL	UNDERWRITER'S LABORATORIES
V	VOLTS
W/	WITH
W/O	WITHOUT
WP	WEATHER PROOF
XFER	TRANSFER
XFMR	TRANSFORMER

AIRPORT EQUIPMENT/FACILITY ABBREVIATIONS

ASOS	AUTOMATED SURFACE OBSERVING SYSTEM
ATCT	AIR TRAFFIC CONTROL TOWER
AWOS	AUTOMATED WEATHER OBSERVING SYSTEM
CCR	CONSTANT CURRENT REGULATOR
DME	DISTANCE MEASURING EQUIPMENT
FAR	FEDERAL AVIATION REGULATION
GS	GLIDE SLOPE FACILITY
HIRL	HIGH INTENSITY RUNWAY LIGHT
ILS	INSTRUMENT LANDING SYSTEM
IM	INNER MARKER
LIR	LOW IMPACT-RESISTANT
LOC	LOCALIZER FACILITY
MALS	MEDIUM INTENSITY APPROACH LIGHTING SYSTEM
MALSR	MEDIUM INTENSITY APPROACH LIGHTING SYSTEM WITH RUNWAY ALIGNMENT INDICATING LIGHTS
MIRL	MEDIUM INTENSITY RUNWAY LIGHT
MITL	MEDIUM INTENSITY TAXIWAY LIGHT
NDB	NON-DIRECTIONAL BEACON
PAPI	PRECISION APPROACH PATH INDICATOR
PLASI	PULSE LIGHT APPROACH SLOPE INDICATOR
RAIL	RUNWAY ALIGNMENT INDICATING LIGHTS
REIL	RUNWAY END IDENTIFIER LIGHT
RVR	RUNWAY VISUAL RANGE
VADI	VISUAL APPROACH DESCENT INDICATOR
VASI	VISUAL APPROACH SLOPE INDICATOR
VOR	VERY HIGH FREQUENCY OMNIDIRECTIONAL RANGE FACILITY
WC	WIND CONE

NOTES:

- ALL ELECTRICAL EQUIPMENT SHALL BE INSTALLED IN CONFORMANCE WITH NFPA 70 - NATIONAL ELECTRICAL CODE (NEC) MOST CURRENT ISSUE IN FORCE, THE RESPECTIVE EQUIPMENT MANUFACTURER'S DIRECTIONS AND ALL OTHER APPLICABLE LOCAL CODES, LAWS, ORDINANCES, AND REQUIREMENTS IN FORCE. ANY INSTALLATIONS WHICH VOID THE U.L. LISTING, ETL LISTING (OR OTHER THIRD PARTY LISTING) AND/OR THE MANUFACTURER'S WARRANTY OF A DEVICE WILL NOT BE PERMITTED.
- ALL VAULT WORK, POWER OUTAGES, AND/OR SHUT DOWN OF EXISTING SYSTEMS SHALL BE COORDINATED WITH THE AIRPORT MANAGER. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).
- COLOR CODE PHASE AND NEUTRAL CONDUCTOR INSULATION FOR NO. 6 AWG OR SMALLER. PROVIDE COLORED INSULATION OR COLORED MARKING TAPE FOR PHASE AND NEUTRAL CONDUCTORS FOR NO. 4 AWG AND LARGER. INSULATED GROUND CONDUCTORS SHALL HAVE GREEN COLORED INSULATION FOR ALL CONDUCTOR AWG AND/OR KCMIL TO COMPLY WITH NEC 250.119. NEUTRAL CONDUCTORS SHALL HAVE WHITE COLORED INSULATION FOR NO. 6 AWG AND SMALLER TO MEET THE REQUIREMENTS OF NEC 200.6. STANDARD COLORS FOR POWER WIRING AND BRANCH CIRCUITS SHALL BE AS FOLLOWS:  
  

120/240 VAC, 1 PHASE, 3 WIRE	
PHASE A	BLACK
PHASE B	RED
NEUTRAL	WHITE
GROUND	GREEN
- SEE RESPECTIVE SITE PLANS FOR SITE LEGEND INFORMATION.
- LTFMC DENOTES LIQUID TIGHT FLEXIBLE METAL CONDUIT UL LISTED, SUNLIGHT RESISTANT, & SUITABLE FOR GROUNDING. LIQUID TIGHT FLEXIBLE METAL CONDUIT AND ASSOCIATED FITTINGS SHALL BE U.L. LISTED TO MEET THE REQUIREMENTS OF NEC 350.6. LIQUID TIGHT FLEXIBLE METAL CONDUIT THAT IS USED FOR FLEXIBILITY (INCLUDING CONNECTIONS TO CCR'S & TRANSFORMERS) SHALL REQUIRE AN EXTERNAL BONDING JUMPER OR INTERNAL EQUIPMENT GROUNDING CONDUCTOR PER NEC 350.60. EXTERNAL BONDING JUMPERS USED WITH CCR INSTALLATIONS SHALL BE #6 AWG COPPER (MINIMUM). DO NOT INSTALL LTFMC THAT IS NOT UL LISTED. CONFIRM LTFMC BEARS THE UL LABEL PRIOR TO INSTALLATION.

NOV 23, 2011 9:01 AM HAGL000382  
 p:\s\spi-svr306\hanson.dom\hanson\_projects\Documents\11A0080D\CAD\Aircraft\SheetE-001

REVISION	
DATE	


LITCHFIELD MUNICIPAL AIRPORT  
 LITCHFIELD, ILLINOIS  
 I.L.P. PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
Filename	E-001.dwg
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	KNL 07/28/11
DRAWN	BAK 07/28/11
REVIEWED	CAH 11/04/11

**HANSON**  
 © Copyright Hanson Professional Services Inc. 2011  
 Hanson Professional Services Inc.  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2986  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide

REPLACE MRL'S ON  
 RUNWAY 9-27  
 ELECTRICAL LEGEND  
 AND ABBREVIATIONS





**NOTES**


1. ALL WORK, AND/OR POWER OUTAGES, SHALL BE COORDINATED WITH THE AIRPORT MANAGER.
2. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS
3. ALL WORK, POWER OUTAGES AND/OR SHUT DOWN OF EXISTING SYSTEMS SHALL BE COORDINATED WITH THE AIRPORT MANAGER. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY AND HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).
4. ALL EXISTING AIRFIELD LIGHTING SYSTEMS (THAT ARE NOT SCHEDULED FOR REMOVAL AND REPLACEMENT) SHALL BE OPERABLE DURING NIGHTFALL UNLESS OTHERWISE APPROVED BY THE AIRPORT MANAGER AND/OR OTHERWISE DETAILED HEREIN. CONTRACTOR SHALL PROVIDE ALL TEMPORARY WORK AS NECESSARY TO MAINTAIN OPERATION OF THE AIRFIELD LIGHTING SYSTEMS AT NIGHTFALL. CONTRACTOR SHALL COORDINATE TRANSFER OF EXISTING AIRFIELD CIRCUITS TO MINIMIZE DOWNTIME.
5. EQUIPMENT DESIGNATED FOR REMOVAL SHALL BE TURNED OVER TO THE AIRPORT. IN THE EVENT THE AIRPORT DOES NOT WANT THE RESPECTIVE EQUIPMENT, THE CONTRACTOR SHALL DISPOSE OF IT OFF SITE.

ITEM AT800591  
UPGRADE AIRPORT  
ROTATING BEACON  
IS UNDER ADDITIVE  
ALTERNATE NO. 2

EXISTING ELECTRICAL ONE-LINE DIAGRAM FOR AIRPORT ROTATING BEACON

NOV 23, 2011 9:02 AM HAGL000382  
p:\s\spi-svr306\hanson\_dom\hanson\_projects\Documents\11\Jobs\11A0080D\CAD\_Airport\Sheet\E-602-ELEC

REVISION		<b>LITCHFIELD MUNICIPAL AIRPORT LITCHFIELD, ILLINOIS</b>	A.I.P. PROJ.: 3-17-0063-B18 IL PROJ.: 3LF-4130
DATE			
Hanson Project No. 11A0080D Filename E-602-ELEC.dwg Scale NOT TO SCALE Date 10/28/2011		LAYOUT KNL 10/06/11 DRAWN JFC 10/06/11 REVIEWED CAH 11/04/11	
© Copyright Hanson Professional Services Inc. 2011 <b>Hanson Professional Services Inc.</b> 1525 South Sixth Street Springfield, Illinois 62703-2886 Ph: (217) 788-2450 Fax: (217) 788-2503 www.hanson-inc.com Offices Nationwide		REPLACE MRL'S ON RUNWAY 9-27 EXISTING ELECTRICAL ONE-LINE DIAGRAM FOR AIRPORT ROTATING BEACON	
23		23 of 34 sheets	



**ITEM AT800591  
UPGRADE AIRPORT  
ROTATING BEACON  
IS UNDER ADDITIVE  
ALTERNATE NO. 2**

**NOTES**

1. ALL WORK, POWER OUTAGES, AND/OR SHUT DOWN OF EXISTING SYSTEMS SHALL BE COORDINATED WITH THE AIRPORT MANAGER. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY & HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).
2. ALL ELECTRICAL EQUIPMENT SHALL BE INSTALLED IN CONFORMANCE WITH NFPA 70 - NATIONAL ELECTRICAL CODE (NEC) MOST CURRENT ISSUE IN FORCE, THE RESPECTIVE EQUIPMENT MANUFACTURER'S DIRECTIONS AND ALL OTHER APPLICABLE LOCAL CODES, LAWS, ORDINANCES AND REQUIREMENTS IN FORCE. ANY INSTALLATIONS WHICH VOID THE U.L. LISTING, ETL LISTING, (OR OTHER THIRD PARTY LISTING) AND/OR THE MANUFACTURER'S WARRANTY OF A DEVICE WILL NOT BE PERMITTED.
3. ALL CONDUCTORS/WIRING SHALL BE COPPER.
4. CONTRACTOR SHALL CONFIRM POWER REQUIREMENTS WITH THE ACTUAL NAMEPLATE ON EACH PIECE OF RESPECTIVE EQUIPMENT, AND ADJUST CIRCUIT BREAKER, WIRE SIZES, WIRE QUANTITIES, & CONDUIT SIZES TO CONFORM WITH NEC & MANUFACTURER'S RECOMMENDATIONS WHERE APPLICABLE. WIRE SIZES SHOWN ON THE PLANS ARE MINIMUM.
5. HIGH VOLTAGE & LOW VOLTAGE CIRCUITS SHALL NOT BE INSTALLED IN THE SAME WIREWAY, CONDUIT, HANDHOLE, JUNCTION BOX, OR RACEWAY.
6. EQUIPMENT NOT LABELED AS EXISTING IS NEW.
7. ALL WORK SHOWN ON THIS SHEET WILL BE PAID FOR UNDER ITEM AT800591 UPGRADE AIRPORT ROTATING BEACON PER LUMP SUM.

PROPOSED ELECTRICAL ONE-LINE DIAGRAM FOR AIRPORT ROTATING BEACON & TOWER UPGRADES

REVISION	DATE	REVISION AS PER I.D.A. COMMENTS
11/23/11		

**LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS**

IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18


Hanson Project No.	11A0080D
Filename	E-603-ELEC.dwg
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	KNL 10/06/11
DRAWN	JFC/BAK 10/06/11
REVIEWED	CAH 11/04/11

**HANSON**  
Professional Services Inc. 2011  
1525 South Sixth Street  
Springfield, Illinois 62703-2886  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide

REPLACE MRL'S ON  
RUNWAY 9-27


PROPOSED ELECTRICAL  
ONE-LINE DIAGRAM FOR  
AIRPORT ROTATING BEACON

NOV 23, 2011 9:04 AM HAGL000382  
p:\s\spi-svr306\hanson\_dom\hanson\_projects\Documents\11A0080D\CAD\Airport\Sheet\E-603-ELEC



CONTROL PANEL FOR AIRPORT ROTATING BEACON

- NOTES**
- 15 AMP & 20 AMP INPUT POWER/BRANCH CIRCUITS SHALL BE #10 AWG COPPER THWN FROM THE RESPECTIVE POWER SOURCE TO THE LIGHTING CONTACTOR PANEL. 30 AMP INPUT POWER/BRANCH CIRCUITS SHALL BE #8 AWG COPPER THWN (MIN.) FROM THE RESPECTIVE POWER SOURCE TO THE LIGHTING CONTACTOR PANEL.
  - INPUT CONTROL CIRCUITS SHALL BE #12 AWG COPPER THWN.
  - FOR 120 VAC BRANCH CIRCUITS THE NEUTRAL CONDUCTOR SHALL NOT BE SWITCHED THROUGH THE RELAY CONTACTS. USE TERMINAL BLOCKS TO TRANSITION FROM VAULT BRANCH CIRCUIT WIRING TO FIELD WIRING.
  - THE AIRPORT ROTATING BEACON CIRCUIT SHALL HAVE PHASE "A" SWITCHED THROUGH THE LIGHTING CONTACTOR. PHASE "B" SHALL BE UNSWITCHED FROM THE POWER SOURCE TO THE LOAD CENTER AT THE AIRPORT ROTATING BEACON.
  - PROVIDE #10 AWG COPPER BONDING JUMPER FROM PANEL ENCLOSURE FRAME TO ENCLOSURE DOOR.
  - PROVIDE 3-POSITION MAINTAINED CONTACT "HAND-OFF-AUTO" SELECTOR SWITCH FOR EACH LIGHTING CONTACTOR & MOUNT ON LIGHTING CONTACTOR PANEL ENCLOSURE DOOR. SELECTOR SWITCH SHALL BE SQUARE D CLASS 9001, TYPE KS43FBH13, OR APPROVED EQUAL. INCLUDE LEGEND PLATE TO IDENTIFY THE DEVICE CONTROLLED (EX: "WIND CONE" OR "AIRPORT ROTATING BEACON").
  - INCLUDE LEGEND PLATE ON CONTROL PANEL ENCLOSURE OUTER DOOR LABELED "NOTICE: CONTACTORS HAVE REMOTE LOCATED CONTROLS AND MAY ACTIVATE AT ANY TIME".
  - 120/240 VAC PHASE "A" CONDUCTORS SHALL HAVE BLACK COLORED INSULATION. 120/240 VAC PHASE "B" CONDUCTORS SHALL HAVE RED COLORED INSULATION. NEUTRAL CONDUCTORS SHALL HAVE WHITE COLORED INSULATION. INSULATED EQUIPMENT GROUND WIRES SHALL HAVE GREEN COLORED INSULATION.
  - CONTROL PANELS FOR AIRFIELD NAVAIDS SHALL BE MANUFACTURED BY A UL 508 INDUSTRIAL CONTROL PANEL BUILDER OR AN FAA APPROVED L-821 PANEL BUILDER, AND SHALL BE MANUFACTURED IN THE UNITED STATES TO COMPLY WITH THE AIRPORT IMPROVEMENT PROGRAM BUY AMERICAN REQUIREMENT AND THE "BUY AMERICAN ACT". CUS BERTHOLD ELECTRIC (1900 WEST CARROLL AVENUE, CHICAGO, IL 60612, PHONE: 312-243-5767) IS AN APPROVED UL 508 INDUSTRIAL CONTROL PANEL BUILDER.
  - FUSING FOR CONTROL WIRING SHALL BE 10 AMP, 600 VAC, BUSSMANN CATALOG FNQ-R-10, OR APPROVED EQUAL, WITH FUSE BLOCKS, WITH BOX LUG TERMINALS, SIZED AS REQUIRED FOR THE RESPECTIVE APPLICATIONS. INCLUDE HARDWARE FOR MOUNTING. PROVIDE ONE BOX (5 MINIMUM QUANTITY) OF EACH TYPE AND SIZE OF FUSE, UPON COMPLETION OF THE JOB FOR USE AS SPARES.
  - LIGHTING CONTACTOR CONTROL PANEL FOR THE AIRPORT ROTATING BEACON WILL BE CONSIDERED INCIDENTAL TO ITEM AT800591 UPGRADE AIRPORT ROTATING BEACON.



CONTROL PANEL FOR AIRPORT ROTATING BEACON SCHEMATIC

REVISION	DATE

LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS


IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D	LAYOUT	KNL	10/26/11
Filename	E-606.dwg	DRAWN	BAK	10/26/11
Scale	NOT TO SCALE	REVIEWED	CAH	11/04/11
Date	10/28/2011			

**HANSON**  
 © Copyright Hanson Professional Services Inc. 2011  
 Hanson Professional Services Inc.  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2986  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide

REPLACE MRL'S ON  
RUNWAY 9-27  
AIRPORT ROTATING BEACON  
LIGHTING CONTACTOR  
PANEL DETAILS

NOV 23, 2011 9:06 AM HAGL000382  
 p:\s\spi-svr306\hanson.dcm\hanson\Projects\Documents\11A0080D\CAD\Airport\Sheet\E-606




**NOTES**

1. ALL VAULT WORK, AND/OR POWER OUTAGES, SHALL BE COORDINATED WITH THE AIRPORT MANAGER AND THE AIRPORT DIRECTOR OF OPERATIONS.
2. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS
3. ALL VAULT WORK, POWER OUTAGES AND/OR SHUT DOWN OF EXISTING SYSTEMS SHALL BE COORDINATED WITH THE AIRPORT MANAGER. ONCE SHUT DOWN, THE CIRCUITS SHALL BE LABELED AS SUCH TO PREVENT ACCIDENTAL ENERGIZING OF THE RESPECTIVE CIRCUITS. ALL PERSONNEL SHALL FOLLOW U.S. DEPARTMENT OF LABOR OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) 29 CFR PART 1910 OCCUPATIONAL SAFETY AND HEALTH STANDARDS FOR ELECTRICAL SAFETY AND LOCKOUT/TAGOUT PROCEDURES INCLUDING, BUT NOT LIMITED TO, 29 CFR SECTION 1910.147 THE CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT).
4. ALL EXISTING AIRFIELD LIGHTING SYSTEMS (THAT ARE NOT SCHEDULED FOR REMOVAL AND REPLACEMENT) SHALL BE OPERABLE DURING NIGHTFALL UNLESS OTHERWISE APPROVED BY THE AIRPORT MANAGER AND/OR OTHERWISE DETAILED HEREIN. CONTRACTOR SHALL PROVIDE ALL TEMPORARY WORK AS NECESSARY TO MAINTAIN OPERATION OF THE AIRFIELD LIGHTING SYSTEMS AT NIGHTFALL. CONTRACTOR SHALL COORDINATE TRANSFER OF EXISTING AIRFIELD CIRCUITS TO MINIMIZE DOWNTIME.
5. EQUIPMENT DESIGNATED FOR REMOVAL SHALL BE TURNED OVER TO THE AIRPORT. IN THE EVENT THE AIRPORT DOES NOT WANT THE RESPECTIVE EQUIPMENT, THE CONTRACTOR SHALL DISPOSE OF IT OFF SITE.
6. THE EXISTING REILS ON RUNWAY 9-27 SHALL BE REMOVED. THE REILS ON RUNWAY END 9 SHALL BE REPLACED WITH NEW REILS. REMOVAL OF EXISTING REILS SYSTEMS WILL BE PAID FOR UNDER ITEM AR125907, REMOVE REILS PER PAIR.

EXISTING ELECTRICAL ONE-LINE DIAGRAM FOR VAULT, RWY 9-27 REILS & NDB

NOV 23, 2011 9:07 AM HAGL000382  
p:\s\spi-svr306\hanson.dom\hanson\_projects\Documents\11A0080D\CAD\Aircraft\Sheet E-601-ELEC

REVISION					
DATE					
<b>LITCHFIELD MUNICIPAL AIRPORT LITCHFIELD, ILLINOIS</b>					
I.L. PROJ.: 3LF-4130 A.I.P. PROJ.: 3-17-0063-B18					
Hanson Project No. 11A0080D	E-601-ELEC.dwg	Scale NOT TO SCALE	Date 10/28/2011	LAYOUT KNL 10/05/11	DRAWN JFC/BAK 10/05/11
				REVIEWED CAH 11/04/11	
<p style="font-size: x-small;">© Copyright Hanson Professional Services Inc. 2011 Hanson Professional Services Inc. 1525 South Sixth Street Springfield, Illinois 62703-2886 Ph: (217) 788-2450 Fax: (217) 788-2503 www.hanson-inc.com Offices Nationwide</p>					
<b>REPLACE MRL'S ON RUNWAY 9-27</b>			<b>EXISTING ELECTRICAL ONE-LINE FOR VAULT, RWY 9-27 REILS &amp; NDB</b>		
<b>26</b>					
26 of 34 sheets					



**NEW FLOOR PLAN FOR VAULT**  
 0 1' 2' 4'  
 HALF SIZE SCALE: 1/4" = 1'-0"  
 FULL SIZE SCALE: 1/2" = 1'-0"

- KEYED NOTES**
- EXISTING CCR FOR RUNWAY 18-36 & TAXIWAY "C".
  - EXISTING TAXIWAY "B" CCR. SEE GENERAL NOTE 1.
  - NEW RUNWAY 9-27 & TAXIWAY A CCR, SEE GENERAL NOTE 1. EXISTING CCR SHALL BE RELOCATED TO STORAGE.
  - REPLACE EXISTING CUTOUT FOR RUNWAY 9-27 & TAXIWAY "A" WITH A NEW SERIES PLUG CUTOUT. SEE GENERAL NOTE 1.
  - REPLACE EXISTING CUTOUT FOR TAXIWAY "B" WITH A NEW SERIES PLUG CUTOUT. SEE GENERAL NOTE 1.
  - REMOVE EXISTING RUNWAY 9-27 REIL CIRCUITS FROM DUCT. REROUTE RUNWAY 18-36 & TAXIWAY "C" HOMERUN THROUGH HIGH VOLTAGE DUCT TO VAULT. INSTALL NEW RUNWAY 9-27 HOMERUN THROUGH HIGH VOLTAGE DUCT TO VAULT. ADJUST/REROUTE TAXIWAY "B" HOMERUN CABLES THROUGH HIGH VOLTAGE DUCT TO ACCOMMODATE INTERFACE TO NEW HIGH VOLTAGE HANDHOLE.
  - REMOVE RUNWAY 18-36 & TAXIWAY "C" LIGHTING HOMERUN CIRCUIT FROM HANDHOLE, LOW VOLTAGE DUCT, & PULL BOX. REROUTE RUNWAY 18-36 & TAXIWAY "C" LIGHTING HOMERUN CIRCUITS THROUGH HIGH VOLTAGE DUCT, & HIGH VOLTAGE HANDHOLES TO VAULT.
  - EXISTING 1/8" THICK x 3/4" WIDE GROUND BUS LOCATED BEHIND CONSTANT CURRENT REGULATORS SHALL BE REPLACED WITH A 1/4 INCH THICK x 2 INCH WIDE x 8 FEET LONG COPPER GROUND BUS. SEE "CCR GROUND BUS RISER" FOR DETAILS.
  - FURNISH AND INSTALL A UL RATED, 10 POUND CARBON DIOXIDE FIRE EXTINGUISHER SUITABLE FOR USE ON CLASS C FIRES, IN THE VAULT. PER NFPA 10 "PORTABLE FIRE EXTINGUISHERS" CLASS C FIRES ARE FIRES THAT INVOLVE ENERGIZED ELECTRICAL EQUIPMENT. FIRE EXTINGUISHER SHALL BE AMEREX 330, KIDDE MODEL PRO10CDM, OR APPROVED EQUAL. CONFIRM MODEL NUMBERS WITH THE RESPECTIVE FIRE EXTINGUISHER MANUFACTURER.
  - REMOVE BOOST TRANSFORMERS DESIGNATED AS FOR USE WITH RUNWAY 9-27 REILS, AND TURN OVER TO THE AIRPORT.
  - FURNISH & INSTALL NEW RELAY INTERFACE PANEL FOR RUNWAY 9-27 & TAXIWAY "A" CCR.
  - THE EXISTING IEC RATED TERMINAL BLOCKS IN THE LIGHTING CONTACTOR PANEL SHALL BE REPLACED WITH NEMA RATED TERMINAL BLOCKS. TERMINAL BLOCKS SHALL BE NEMA TYPE RATED 85 AMPS AT 600 VOLTS, SUITABLE FOR THE FOLLOWING WIRE COMBINATIONS: 1 #4 AWG, 1 #6 AWG, 1-2 #8 AWG, 1-4 #10 AWG, 1-5 #12 AWG. TERMINAL BLOCKS SHALL BE SQUARE D CLASS 9080 TYPE GC6 OR APPROVED EQUAL. IEC TERMINAL BLOCKS ARE NOT ACCEPTABLE. INCLUDE MOUNTING HARDWARE AND ACCESSORIES.
  - REMOVE ABANDONED GODFREY L-854 RADIO RECEIVER & TURN OVER TO THE AIRPORT.
  - INSTALL A DIVIDER PANEL BETWEEN THE HIGH VOLTAGE AND LOW VOLTAGE SIDES OF THE HANDHOLE. DIVIDER PANEL SHALL BE POLYMER CONCRETE, FIBERGLASS, PVC, OR CONCRETE.

**GENERAL NOTES**

- SEE "NEW ELECTRICAL ONE-LINE DIAGRAM FOR VAULT" FOR LOW VOLTAGE INPUT POWER WIRING REQUIREMENTS TO CONSTANT CURRENT REGULATORS. SEE "HIGH VOLTAGE WIRING SCHEMATIC" FOR CCR OUTPUT WIRING REQUIREMENTS. SEE "RUNWAY 9-27 LIGHTING CONTROL SCHEMATIC" FOR CONTROL WIRING REQUIREMENTS TO RUNWAY 9-27 & TAXIWAY "A" CCR.
- MAINTAIN SEPARATION OF HIGH VOLTAGE WIRING FROM LOW VOLTAGE WIRING TO COMPLY WITH NEC 300.3(c)(2). HIGH VOLTAGE AND LOW VOLTAGE WIRING SHALL NOT BE INSTALLED IN THE SAME RACEWAY, CONDUIT, WIREWAY, PULL BOX, SPLICE CAN OR HANDHOLE.
- CONSTANT CURRENT REGULATORS AND THEIR RESPECTIVE SERIES PLUG CUTOUTS SHALL BE CLEARLY LABELED TO IDENTIFY THE RESPECTIVE REGULATOR DESIGNATION, RUNWAY OR TAXIWAY SERVED, POWER SOURCE OR CIRCUIT, AND VOLTAGE SYSTEM.
- BOND EACH WIREWAY TO VAULT GROUND BUS WITH #6 AWG COPPER BONDING JUMPER.
- BOND EACH CCR FRAME/HOUSING TO VAULT GROUND BUS WITH #6 AWG COPPER BONDING JUMPER.
- MAINTAIN SEPARATION OF HIGH VOLTAGE AND LOW VOLTAGE CIRCUITS. LOW VOLTAGE WIRING SHALL ENTER THE RESPECTIVE CCR AT THE LOW VOLTAGE SECTION. HIGH VOLTAGE WIRING SHALL ENTER THE RESPECTIVE CCR AT THE HIGH VOLTAGE SECTION.
- THE CONTRACTOR SHALL SECURE, IDENTIFY AND PLACE ANY TEMPORARY EXPOSED WIRING IN CONDUIT TO PREVENT ELECTROCUTION AND FIRE IGNITION SOURCES AS PER THE REQUIREMENTS OF FFA AC 150/5370-2E OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION, PART 3-6, C.

THE LOCATION, SIZE, AND TYPE OF MATERIAL OF EXISTING UNDERGROUND AND/OR ABOVEGROUND UTILITIES INDICATED ON THE PLANS ARE NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS, OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE OWNER'S REPRESENTATIVE AND/OR THE RESIDENT ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY DAMAGE TO SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

ALL UTILITY CABLES AND LINES SHALL BE LOCATED BY THE RESPECTIVE UTILITY. CONTACT JULIE (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS) FOR UTILITY INFORMATION, PHONE: 1-800-892-0123. CONTACT THE FAA (FEDERAL AVIATION ADMINISTRATION) FOR ASSISTANCE IN LOCATING FAA CABLES AND UTILITIES. LOCATION OF FAA POWER, CONTROL, AND COMMUNICATION CABLES SHALL BE COORDINATED WITH AND/OR LOCATED BY THE FAA. ALSO CONTACT AIRPORT DIRECTOR/MANAGER AND AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. ALSO COORDINATE WORK WITH ALL ABOVEGROUND UTILITIES.

REVISION	DATE

**LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS**  
 I.L. PROJ.: 3LF-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No. 11A00800	File Name E-101.dwg	Scale NOT TO SCALE	Date 10/28/2011
LAYOUT	KNL	10/31/11	
DRAWN	BAK	10/31/11	
REVIEWED	CAH	11/04/11	

**HANSON**  
 Professional Services Inc. 2011  
 Hanson Professional Services Inc.  
 1525 South Sixth Street  
 Springfield, Illinois 62705-2886  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide


REPLACE MRL'S ON  
RUNWAY 9-27  
 PROPOSED FLOOR PLAN  
FOR VAULT

NOV 23, 2011 9:08 AM H:\GLO00382  
 p:\s\spc-svr306\hanson\dom\hanson\Projects\Documents\11\jobs\11A00800\CAD\Airport\Sheet\E-101



NOTES

1. ALL VAULT WORK AND/OR POWER OUTAGES SHALL BE COORDINATED WITH THE AIRPORT MANAGER.
2. ALL ELECTRICAL EQUIPMENT SHALL BE INSTALLED IN CONFORMANCE WITH NFPA 70-NATIONAL ELECTRIC CODE (NEC) MOST CURRENT ISSUE IN FORCE, THE RESPECTIVE EQUIPMENT MANUFACTURER'S DIRECTIONS AND ALL OTHER APPLICABLE LOCAL CODES, LAWS, ORDINANCES AND REQUIREMENTS IN FORCE. ANY INSTALLATIONS WHICH VOID THE U.L. LISTING, ETL LISTING, (OR OTHER THIRD PARTY LISTING) AND/OR THE MANUFACTURER'S WARRANTY OF A DEVICE WILL NOT BE PERMITTED.
3. ALL EQUIPMENT SHOWN NOT LABELED AS EXISTING IS NEW.
4. CONTRACTOR SHALL CONFIRM POWER REQUIREMENTS WITH THE ACTUAL NAMEPLATE ON EACH CONSTANT CURRENT REGULATOR (OR OTHER RESPECTIVE EQUIPMENT) AND ADJUST CIRCUIT BREAKER, WIRE SIZES & CONDUIT SIZES TO CONFORM WITH NEC & MANUFACTURER'S RECOMMENDATIONS WHERE APPLICABLE. WIRE SIZES SHOWN ON THE PLANS ARE MINIMUM.
5. HIGH VOLTAGE & LOW VOLTAGE CIRCUITS SHALL NOT BE INSTALLED IN THE SAME RACEWAY OR JUNCTION BOX.
6. ALL CONDUCTORS/WIRING SHALL BE COPPER.
7. BRANCH CIRCUITS TO NEW REGULATOR & REWIRED REGULATORS SHALL BE INSTALLED IN THE RESPECTIVE LOW VOLTAGE WIREWAY/DUCT, WITH GRSC AT TRANSITIONS AND UL LISTED LIQUID TIGHT FLEXIBLE METAL CONDUIT AT FINAL CONNECTIONS TO THE REGULATOR. CONDUITS SHALL BE SIZED IN ACCORDANCE WITH NEC.
8. BOND NEW & EXISTING REGULATORS TO THE RESPECTIVE VAULT GROUND BUS WITH A DEDICATED #6 AWG BONDING JUMPER.
9. LTFMC DENOTES LIQUID TIGHT FLEXIBLE METAL CONDUIT UL LISTED, SUNLIGHT RESISTANT, & SUITABLE FOR GROUNDING. LIQUID TIGHT FLEXIBLE METAL CONDUIT THAT IS USED FOR FLEXIBILITY (INCLUDING CONNECTIONS TO CCR'S & TRANSFORMERS) SHALL REQUIRE AN EXTERNAL BONDING JUMPER OR INTERNAL EQUIPMENT GROUNDING CONDUCTOR PER NEC 350.6. EXTERNAL BONDING JUMPERS USED WITH CCR INSTALLATIONS SHALL BE #6 AWG COPPER (MINIMUM). DO NOT INSTALL LTFMC THAT IS NOT UL LISTED. CONFIRM LTFMC BEARS THE UL LABEL PRIOR TO INSTALLING IT.
10. LOW VOLTAGE INPUT POWER WIRING AND CONTROL WIRING SHALL ENTER THE CCR AT THE LOW VOLTAGE SECTION IN ACCORDANCE WITH THE CCR MANUFACTURER'S INSTRUCTIONS. HIGH VOLTAGE OUTPUT SERIES CIRCUIT WIRING SHALL EXIT THE CCR AT THE HIGH VOLTAGE SECTION IN ACCORDANCE WITH THE CCR MANUFACTURER'S INSTRUCTIONS.
11. THE EXISTING IEC RATED TERMINAL BLOCKS IN THE LIGHTING CONTACTOR PANEL SHALL BE REPLACED WITH NEMA RATED TERMINAL BLOCKS. TERMINAL BLOCKS SHALL BE NEMA TYPE RATED 85 AMPS AT 600 VOLTS, SUITABLE FOR THE FOLLOWING WIRE COMBINATIONS: 1 #4 AWG, 1 #6 AWG, 1-2 #8 AWG, 1-4 #10 AWG, 1-5 #12 AWG. TERMINAL BLOCKS SHALL BE SQUARE D CLASS 9080 TYPE GC6 OR APPROVED EQUAL. IEC TERMINAL BLOCKS ARE NOT ACCEPTABLE. INCLUDE MOUNTING HARDWARE AND ACCESSORIES.
12. VAULT WORK WILL BE PAID FOR UNDER ITEM AR109200 INSTALL ELECTRICAL EQUIPMENT PER LUMP SUM.



PROPOSED ELECTRICAL ONE-LINE DIAGRAM FOR VAULT & WIND CONE

REVISION	
DATE	

LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS

IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18


Hanson Project No.	11A0080D
Filename	E-604.dwg
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	KNL 10/26/11
DRAWN	BAK 10/26/11
REVIEWED	CAH 11/04/11

**HANSON**  
Professional Services Inc. 2011  
Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2886  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide


REPLACE MRL'S ON  
RUNWAY 9-27

PROPOSED ELECTRICAL  
ONE-LINE DIAGRAM FOR  
VAULT & WIND CONE

NOV 23, 2011 9:09 AM HAGL000382  
p:\s\spi-svr306\hanson.d\hanson\Projects\Documents\11A0080D\CAD\Aircraft\Sheet E-604



CONTROL PANEL FOR PRIMARY WIND CONE




CONTROL PANEL FOR PRIMARY WIND CONE SCHEMATIC


- NOTES**
- 15 AMP & 20 AMP INPUT POWER/BRANCH CIRCUITS SHALL BE #10 AWG COPPER THWN FROM THE RESPECTIVE POWER SOURCE TO THE LIGHTING CONTACTOR PANEL. 30 AMP INPUT POWER/BRANCH CIRCUITS SHALL BE #8 AWG COPPER THWN (MIN.) FROM THE RESPECTIVE POWER SOURCE TO THE LIGHTING CONTACTOR PANEL.
  - INPUT CONTROL CIRCUITS SHALL BE #12 AWG COPPER THWN.
  - FOR 120 VAC BRANCH CIRCUITS THE NEUTRAL CONDUCTOR SHALL NOT BE SWITCHED THROUGH THE RELAY CONTACTS. USE TERMINAL BLOCKS TO TRANSITION FROM VAULT BRANCH CIRCUIT WIRING TO FIELD WIRING.
  - PROVIDE #10 AWG COPPER BONDING JUMPER FROM PANEL ENCLOSURE FRAME TO ENCLOSURE DOOR.
  - PROVIDE 3-POSITION MAINTAINED CONTACT "HAND-OFF-AUTO" SELECTOR SWITCH FOR EACH LIGHTING CONTACTOR & MOUNT ON LIGHTING CONTACTOR PANEL ENCLOSURE DOOR. SELECTOR SWITCH SHALL BE SQUARE D CLASS 9001, TYPE KS43FBH13, OR APPROVED EQUAL. INCLUDE LEGEND PLATE TO IDENTIFY THE DEVICE CONTROLLED (EX: "WIND CONE" OR "AIRPORT ROTATING BEACON").
  - INCLUDE LEGEND PLATE ON CONTROL PANEL ENCLOSURE OUTER DOOR LABELED "NOTICE: CONTACTORS HAVE REMOTE LOCATED CONTROLS AND MAY ACTIVATE AT ANY TIME".
  - 120/240 VAC PHASE "A" CONDUCTORS SHALL HAVE BLACK COLORED INSULATION. 120/240 VAC PHASE "B" CONDUCTORS SHALL HAVE RED COLORED INSULATION. NEUTRAL CONDUCTORS SHALL HAVE WHITE COLORED INSULATION. INSULATED EQUIPMENT GROUND WIRES SHALL HAVE GREEN COLORED INSULATION.
  - CONTROL PANELS FOR AIRFIELD NAVAIDS SHALL BE MANUFACTURED BY A UL 508 INDUSTRIAL CONTROL PANEL BUILDER OR AN FAA APPROVED L-821 PANEL BUILDER, AND SHALL BE MANUFACTURED IN THE UNITED STATES TO COMPLY WITH THE AIRPORT IMPROVEMENT PROGRAM BUY AMERICAN REQUIREMENT AND THE "BUY AMERICAN ACT". GUS BERTHOLD ELECTRIC (1900 WEST CARROLL AVENUE, CHICAGO, IL 60612, PHONE: 312-243-5767) IS AN APPROVED UL 508 INDUSTRIAL CONTROL PANEL BUILDER.
  - FUSING FOR CONTROL WIRING SHALL BE 10 AMP, 600 VAC, BUSSMANN CATALOG FNQ-R-10, OR APPROVED EQUAL, WITH FUSE BLOCKS, WITH BOX LUG TERMINALS, SIZED AS REQUIRED FOR THE RESPECTIVE APPLICATIONS. INCLUDE HARDWARE FOR MOUNTING. PROVIDE ONE BOX (5 MINIMUM QUANTITY) OF EACH TYPE AND SIZE OF FUSE, UPON COMPLETION OF THE JOB FOR USE AS SPARES.
  - LIGHTING CONTACTOR CONTROL PANEL FOR THE PRIMARY WIND CONE WILL BE CONSIDERED INCIDENTAL TO ITEM AS107812 L-807-WC-12' INTERNALLY LIT.

NOV 23, 2011 9:10 AM HAGL000382  
 pw:\spi-svr306\hanson\_dom\hanson\_projects\Documents\11A0080D\CAD\Aircraft\Sheet\E-607-ELE

REVISION	
DATE	
<b>LITCHFIELD MUNICIPAL AIRPORT LITCHFIELD, ILLINOIS</b>	
IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18	
Hanson Project No. 11A0080D	
Filename E-605.dwg	
Scale NOT TO SCALE	
Date 10/28/2011	
LAYOUT KNL 10/26/11	
DRAWN BAK 10/26/11	
REVIEWED CAH 11/04/11	
<b>HANSON</b> © Copyright Hanson Professional Services Inc. 2011 <b>Hanson Professional Services Inc.</b> 1525 South Sixth Street Springfield, Illinois 62703-2986 Ph: (217) 788-2450 Fax: (217) 788-2503 www.hanson-inc.com Offices Nationwide	
REPLACE MRL'S ON RUNWAY 9-27	WIND CONE LIGHTING CONTACTOR PANEL DETAILS
<b>29</b> 29 of 34 sheets	



- NOTES**
1. ALL ELECTRICAL EQUIPMENT WILL BE WIRED IN ACCORDANCE WITH THE SCHEMATIC WIRING DIAGRAM, ALL APPLICABLE CODES, AND AS SPECIFIED HEREIN.
  2. ALL CONTROL CABLE WILL BE NO. 12 AWG, 600 VOLT CABLE.
  3. ALL ELECTRICAL EQUIPMENT WILL BE PROPERLY LABELED AND ALL ELECTRICAL CABLES WILL BE TAGGED.
  4. ALL ELECTRICAL CABLES INSIDE THE VAULT WILL BE IN CONDUIT OR DUCT.
  5. THE RUNWAY 9-27 & TAXIWAY A LIGHTING CIRCUITS WILL BE CONTROLLED BY THE L-854 RADIO CONTROL UNIT & PHOTOCELL IN THE FOLLOWING MANNER:  
 PHOTOCELL - ACTIVATE RADIO CONTROL  
 3 CLICKS - 10% BRIGHTNESS  
 5 CLICKS - 30% BRIGHTNESS  
 7 CLICKS - 100% BRIGHTNESS
  6. L-854 RADIO CONTROL UNIT IS EXISTING. CONSTANT CURRENT REGULATOR FOR RUNWAY 9-27 & TAXIWAY A, INTERFACE PANEL, & CUTOUPS SHALL BE NEW. INTERFACE EXISTING CONTROL SYSTEM TO NEW CONSTANT CURRENT REGULATOR. FIELD VERIFY EXISTING CONTROL CIRCUITS.
  7. EQUIPMENT GROUND WIRES SHALL BE INCLUDED WITH EACH BRANCH/FEEDER CIRCUIT & EACH CONTROL CIRCUIT.
  8. CONTRACTOR SHALL CONFIRM EXISTING CONTROL SYSTEM FOR RUNWAY 9-27 & TAXIWAY A CCR PRIOR TO DISCONNECTING THE EXISTING CCR. REPORT ANY DEVIATIONS FROM PROPOSED CONTROL METHOD TO PROJECT ENGINEER.
  9. COLOR CODING FOR THE CONTROL WIRING TO EACH CONSTANT CURRENT REGULATOR SHALL BE CONSISTENT FOR ALL REGULATORS. COLOR CODING SHALL BE AS FOLLOWS:  
 CC - RED  
 10% - ORANGE (WHERE APPLICABLE)  
 30% - YELLOW  
 100% - BLUE  
 NEUTRAL - WHITE  
 EQUIPMENT GND. - GREEN
- ALSO TAG THE CONTROL WIRES WITH THE RESPECTIVE DESIGNATION (CC, 10%, 30%, 100%)
10. "N" DESIGNATES NEUTRAL CONNECTION OR NEUTRAL CONDUCTOR.



TYP. INTERFACE PANEL DETAIL

- SHEET LEGEND**
- 17 EXISTING 120 VAC CONTROL POWER CIRCUIT FOR L-854 RADIO FROM VAULT PANELBOARD CKT 17.
  - 5 NEW 240 VAC FEEDER CIRCUIT FOR RUNWAY 9-27 & TAXIWAY A CCR FROM VAULT PANEL CKT 5, 7.
  - N N DESIGNATES NEUTRAL FROM THE RESPECTIVE PANEL THAT POWERS THE DEVICE. FOR CONTROL CIRCUIT INPUTS TO CCR'S N SHALL BE FROM THE RESPECTIVE INTERFACE PANEL CIRCUIT NEUTRAL CONNECTION.

REVISION	DATE

**LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS**

I.L. PROJ.: 3LF-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
Filename	E-607.dwg
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	KNL 10/26/11
DRAWN	BAK 10/26/11
REVIEWED	CAH 11/04/11


**HANSON**  
 © Copyright Hanson Professional Services Inc. 2011  
**Hanson Professional Services Inc.**  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2986  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide

REPLACE MRL'S ON  
RUNWAY 9-27

RUNWAY 9-27 LIGHTING  
CONTROL SCHEMATIC

RUNWAY 9-27 & TAXIWAY A LIGHTING CONTROL WIRING SCHEMATIC

NOV 23, 2011 9:12 AM HAGL000382 p:\sps-306\hanson\_dom\hanson\_projects\Documents\11A0080D\11A0080D\CAD\Aircraft\Sheet\E-607



HIGH VOLTAGE WIRING SCHEMATIC



"DANGER - HIGH VOLTAGE" SIGN

FURNISH AND INSTALL "DANGER - HIGH VOLTAGE" LABELS/SIGNS FOR EACH CUTOUT ENCLOSURE, EACH CONSTANT CURRENT REGULATOR, AND THE HIGH VOLTAGE WIREWAY, TO COMPLY WITH FAA AC 150/5340-26B "MAINTENANCE OF AIRPORT VISUAL AID FACILITIES".

- LEGEND**
- "I" DENOTES PLUG CUTOUT WITH PLUG INSERTED
  - "P" DENOTES PLUG CUTOUT WITH PLUG PULLED
  - "CCR" DENOTES CONSTANT CURRENT REGULATOR

**NOTES:**

1. PROVIDE PHENOLIC ENGRAVED LEGEND PLATES FOR EACH CONSTANT CURRENT REGULATOR NOTING THE REGULATOR DESIGNATION AND THE RUNWAY AND/OR TAXIWAY SERVED.
2. EACH PLUG CUTOUT CABINET SHALL BE FURNISHED WITH A PHENOLIC ENGRAVED LEGEND PLATE THAT IDENTIFIES THE RESPECTIVE CIRCUIT OR REGULATOR. INCLUDE AN ADDITIONAL LEGEND PLATE LABELED "CAUTION OPERATE CUTOUTS WITH CCR SHUT OFF". FURNISH & INSTALL A WARNING LABEL FOR CUTOUT ENCLOSURE TO WARN PERSONS OF POTENTIAL ARC FLASH HAZARDS, PER THE REQUIREMENTS OF NEC 110.16 "FLASH PROTECTION".
3. PROVIDE PHENOLIC ENGRAVED LEGEND PLATES FOR EACH CUTOUT TO IDENTIFY THE RESPECTIVE CUTOUT INPUT CONNECTION AND THE RESPECTIVE CUTOUT OUTPUT CONNECTION.
4. BOND EACH REGULATOR FRAME TO VAULT GROUND BUS WITH A DEDICATED #6 AWG COPPER BONDING JUMPER.
5. PROVIDE ADEQUATE WORKING SPACE IN FRONT OF EACH CUTOUT ENCLOSURE TO MEET NEC CLEARANCE REQUIREMENTS..
6. LIQUID TIGHT FLEXIBLE METAL CONDUIT AND ASSOCIATED FITTINGS SHALL BE U.L. LISTED TO MEET THE REQUIREMENTS OF NEC 350.6, SUITABLE FOR GROUNDING AND SUNLIGHT RESISTANT. LIQUID TIGHT FLEXIBLE METAL CONDUIT THAT IS USED FOR FLEXIBILITY (INCLUDING CONNECTIONS TO CCR'S & TRANSFORMERS) SHALL REQUIRE AN EXTERNAL BONDING JUMPER OR INTERNAL EQUIPMENT GROUNDING CONDUCTOR PER NEC 350.60. EXTERNAL BONDING JUMPERS USED WITH CCR INSTALLATIONS SHALL BE #6 AWG COPPER (MINIMUM). DO NOT INSTALL LIQUID TIGHT FLEXIBLE METAL CONDUIT THAT IS NOT UL LISTED. CONFIRM LIQUID TIGHT FLEXIBLE METAL CONDUIT BEARS THE UL LABEL PRIOR TO INSTALLING IT.
7. SERIES PLUG CUTOUTS SHALL BE TYPE S-1, RATED 5000 VOLTS, 20-AMP, AND SHALL COMPLY WITH FAA AC 150/5340-4C. SERIES PLUG CUTOUTS SHALL BE RATED SUITABLE FOR NORMAL OPERATION WITH HANDLE REMOVED OR HANDLE INSERTED. CUTOUTS SHALL DISCONNECT THE INPUT FROM THE OUTPUT, SHORT THE INPUT TERMINALS, AND SHORT THE OUTPUT TERMINALS WHEN THE HANDLE/PLUG IS REMOVED. SERIES PLUG CUTOUTS SHALL BE CROUSE-HINDS CAT. NO. 30775, OR APPROVED EQUAL. THE RESPECTIVE MANUFACTURER SHALL CERTIFY IN WRITING THAT THEIR CUTOUT IS SUITABLE AND RATED FOR THE RESPECTIVE APPLICATION.
8. HIGH VOLTAGE & LOW VOLTAGE CIRCUITS SHALL NOT BE INSTALLED IN THE SAME WIREWAY.
9. SPLICES FOR RUNWAY AND TAXIWAY SERIES CIRCUITS SHALL BE FAA APPROVED TYPE L-823 CONNECTORS AND SHALL BE INSTALLED IN HIGH VOLTAGE HANDHOLES, SPLICE BOXES OR THE HIGH VOLTAGE WIREWAY.

REVISION	
DATE	

LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS


IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D
Filename	E-608.dwg
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	KNL 10/26/11
DRAWN	BAK 10/26/11
REVIEWED	CAH 11/04/11

**HANSON**  
 © Copyright Hanson Professional Services Inc. 2011  
 Hanson Professional Services Inc.  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2986  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide

REPLACE MRL'S ON  
RUNWAY 9-27

HIGH VOLTAGE WIRING  
SCHEMATIC



**NOTES FOR CCR GROUND BUS RISER**

1. CONNECTIONS TO GROUND BUS BARS SHALL BE WITH 2-HOLE TONGUE LONG BARREL COMPRESSION LUGS BOLTED TO THE BUS BAR.
2. CONSTANT CURRENT REGULATORS SHALL BE SHUT OFF PRIOR TO DISCONNECTING EXISTING FRAME GROUNDS AND SHALL REMAIN OFF UNTIL GROUNDING UPGRADES AND NEW GROUND CONNECTIONS ARE COMPLETED.
3. ALL WORK SHOWN ON THIS SHEET SHALL BE PAID FOR UNDER ITEM AR109200 "INSTALL ELECTRICAL EQUIPMENT" PER LUMP SUM.

**CCR GROUND BUS RISER**

**LEGEND PLATE SCHEDULE**

DEVICE	LABEL
LIGHTING CONTACTOR PANEL FOR AIRPORT ROTATING BEACON	AIRPORT ROTATING BEACON CONTROL PANEL 120/240 VAC, 1 PH, 3W
LIGHTING CONTACTOR PANEL FOR PRIMARY L-807 WIND CONE	WIND CONE CONTROL PANEL 120 VAC, 1 PH, 2W
LIGHTING CONTACTOR PANEL FOR AIRPORT ROTATING BEACON	NOTICE CONTACTOR HAS REMOTE LOCATED CONTROLS AND MAY ACTIVATE AT ANY TIME
LIGHTING CONTACTOR PANEL FOR WIND CONE	NOTICE CONTACTOR HAS REMOTE LOCATED CONTROLS AND MAY ACTIVATE AT ANY TIME
RUNWAY 9-27 & TAXIWAY A CCR	RWY 9-27 AND TXY A
TAXIWAY B CCR	TAXIWAY B
RUNWAY 18-36 & TAXIWAY C CCR	RWY 18-36 AND TXY C
CUTOUT FOR RUNWAY 9-27 & TAXIWAY A	RWY 9-27 AND TXY A
CUTOUT FOR TAXIWAY B	TAXIWAY B

**LEGEND PLATE SCHEDULE CONTINUED**

DEVICE	LABEL
CUTOUT FOR RUNWAY 18-36 & TAXIWAY C	RWY 18-36 AND TXY C
EACH CUTOUT ENCLOSURE (PROVIDE 3 LEGEND PLATES)	CAUTION OPERATE CUTOUT WITH CCR SHUT OFF
LOW VOLTAGE WIREWAY	LOW VOLTAGE
HIGH VOLTAGE WIREWAY	HIGH VOLTAGE
EACH CUTOUT INPUT SIDE CONNECTION (PROVIDE 3 LEGEND PLATES)	INPUT
EACH CUTOUT OUTPUT SIDE CONNECTION (PROVIDE 3 LEGEND PLATES)	OUTPUT
VAULT GROUND BUS (PROVIDE 2 LEGEND PLATES 1/2" HIGH WHITE LETTERS GREEN BACKGROUND; INSTALL ABOVE OR BELOW GROUND BUS)	VAULT GROUND BUS
GROUNDING ELECTRODE CONDUCTORS TERMINATED ON VAULT GROUND BUS. (PROVIDE 3 LEGEND PLATES & SECURE TO CONDUCTORS WITH NYLON STRING OR CABLE TIES)	DO NOT DISCONNECT

NOTE: LEGEND PLATES SHALL BE WEATHERPROOF ENGRAVED PLASTIC OR PHENOLIC MATERIAL, 1/4" HIGH BLACK LETTERS ON A WHITE BACKGROUND UNLESS NOTED OTHERWISE. SECURE WITH WEATHERPROOF ADHESIVE AND MACHINE SCREWS. FURNISH ADDITIONAL LEGEND PLATES WHERE REQUIRED BY CODE, FOR ADDITIONAL EQUIPMENT, AS DETAILED HEREIN ON THE PLANS, AND AS NOTED IN THE SPECIAL PROVISION SPECIFICATIONS.

FURNISH & INSTALL A WEATHERPROOF WARNING LABEL FOR EACH SAFETY SWITCH, PANELBOARD, LOAD CENTER, CUTOUT, & CONTROL PANEL TO WARN PERSONS OF POTENTIAL ELECTRIC ARC FLASH HAZARDS, PER THE REQUIREMENTS OF NEC 110.16 "FLASH PROTECTION". LABELS SHALL BE HAZARD COMMUNICATION SYSTEMS, LLC (190 OLD MILFORD RD., BOX 1174, MILFORD, PA 18337, PHONE: 1-877-748-0244) PART NO. H6010-9VWHBJ OR APPROVED EQUAL.

NOV 23, 2011 9:14 AM HAGL000382  
p:\s\lpi-svr306\hanson.dom\hanson\_projects\Documents\11\Jobs\11A0080D\CAD\Aircraft\SheetE-609

REVISION	DATE

LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS

IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18


Hanson Project No.	11A0080D
Filename	E-609.dwg
Scale	NOT TO SCALE
Date	10/28/2011
LAYOUT	KNL 10/26/11
DRAWN	BAK 10/26/11
REVIEWED	CAH 11/4/11

**HANSON**  
© Copyright Hanson Professional Services Inc. 2011  
Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2886  
Ph: (217) 788-2450 Fax: (217) 788-2503  
www.hanson-inc.com  
Offices Nationwide


REPLACE MRL'S ON  
RUNWAY 9-27

CCR GROUND BUS RISER &  
LEGEND PLATE SCHEDULE







CABLE TO GROUND ROD




CABLE TO GROUND ROD



CABLE TO GROUND ROD



CABLE TO CABLE HORIZONTAL PARALLEL TAP




CABLES TO GROUND ROD

**DETAIL NOTES**

- ALL BELOW GRADE CONNECTIONS TO GROUND RODS & GROUND RING CONDUCTORS SHALL BE EXOTHERMIC WELD TYPE CONNECTIONS. EXOTHERMIC WELDS SHALL BE CADWELD AS MANUFACTURED BY ERICO PRODUCTS, SOLON, OHIO, ULTRAWELD AS MANUFACTURED BY HARGER LIGHTNING PROTECTION & GROUNDING EQUIPMENT, GRAYSLAKE, IL, THERMOWELD AS MANUFACTURED BY CONTINENTAL INDUSTRIES, TULSA, OKLAHOMA, OR APPROVED EQUAL. VERIFY PROPER SIZES, MOLDS, TYPES, AND REQUIREMENTS FOR THE RESPECTIVE APPLICATION WITH THE MANUFACTURER, AND INSTALL PER THEIR DIRECTIONS.
- FOR APPLICATIONS TO GALVANIZED STEEL OR PAINTED STEEL, REMOVE GALVANIZING AND/OR PAINT & CLEAN THE SURFACE TO EXPOSE BARE STEEL BEFORE MAKING EXOTHERMIC WELD CONNECTION.
- INDIVIDUAL GROUNDING ELECTRODE CONDUCTORS SHALL NOT BE INSTALLED IN METAL CONDUIT. INSTALL GROUNDING ELECTRODE CONDUCTORS IN SCHED 40 PVC CONDUIT AS REQUIRED IN FOUNDATIONS, FOR PROTECTION, WHERE ENTERING ENCLOSURES, ETC. WHERE PLASTIC CONDUIT IS USED FOR INDIVIDUAL GROUND WIRES, DO NOT COMPLETELY ENCIrcLE THE CONDUIT WITH FERROUS AND/OR MAGNETIC MATERIALS. WHERE METAL CLAMPS ARE INSTALLED USE NYLON BOLTS, NUTS, WASHERS, & SPACERS TO INTERRUPT A COMPLETE METALLIC PATH FROM ENCIrcLING THE CONDUIT.

EXOTHERMIC WELD DETAILS




2 HOLE LONG BARREL COMPRESSION LUG TABLE			
WIRE SIZE	BURNDY CAT. NO.	THOMAS & BETTS CAT. NO.	PENN-UNION CAT. NO.
#8 AWG STRANDED	YA8C-2TC38	256-30695-1157	BBLU-8D-2TC38
#6 AWG SOLID	YA8C-2TC38 OR YGA6C-2TC38E2G1		
#6 AWG STRANDED	YA6C-2TC38	256-30695-1158	BBLU-6D-2TC38
#4 AWG STRANDED	YA4C-2TC38	256-30695-1159	BBLU-4D-2TC38
#2 AWG STRANDED	YA2C-2TC38	256-30695-1160	BBLU-2D-2TC38
#2 AWG SOLID	YA3C-2TC38	256-30695-1160	BBLU-3D-2TC38
#1/0 AWG STRANDED	YA25-2TC38	256-30695-1162	BBLU-1/0D-2TC38
#2/0 AWG STRANDED	YA26-2TC38	256-30695-1116	BBLU-2/0D-2TC38
#3/0 AWG STRANDED	YA27-2TC38	54816BE	BBLU-3/0D-2TC38
#4/0 AWG STRANDED	YA28-2TC38	256-30695-1117	BBLU-4/0D-2TC38

**NOTES**

- ALL CONNECTIONS TO GROUND BUS BAR SHALL BE WITH 2 HOLE TONGUE LONG BARREL COMPRESSION LUGS BOLTED TO THE BUS BAR.
- GROUND WIRE CONNECTIONS TO EQUIPMENT SHALL BE WITH 2 HOLE TONGUE LONG BARREL COMPRESSION LUGS BOLTED TO THE DEVICE OR WITH THE RESPECTIVE EQUIPT MANUFACTURER'S LUG OR TERMINAL WHERE APPLICABLE.
- GROUNDING ELECTRODE CONDUCTORS, BONDING JUMPERS, & INDIVIDUAL GROUND WIRES SHALL NOT BE INSTALLED IN METAL CONDUIT. WHERE PLASTIC CONDUIT IS USED FOR INDIVIDUAL GROUND WIRES, DO NOT COMPLETELY ENCIrcLE THE CONDUIT WITH FERROUS AND/OR MAGNETIC MATERIALS. WHERE METAL CLAMPS ARE INSTALLED USE NYLON BOLTS, NUTS, WASHERS, & SPACERS TO INTERRUPT A COMPLETE METALLIC APTh FROM ENCIrcLING THE CONDUIT.
- ALL CONNECTIONS SHALL BE COATED WITH A CORROSION PREVENTATIVE COMPOUND (SANCHEM INC. NO-OX-ID "A-SPECIAL", BURNDY PENETROX E, OR EQUAL) BEFORE JOINING. ALL COPPER BUS BARS SHALL BE CLEANED PRIOR TO MAKING CONNECTIONS TO REMOVE SURFACE OXIDATION. CLEAN SURFACES, OF RESPECTIVE DEVICES TO BE BONDED, TO BARE METAL, PER NEC 250-12.

GROUNDING LUG CONNECTION DETAIL



PIPE GROUNDING CLAMP TABLE	
BURNDY CAT. NO.	PIPE SIZE
GAR3902-BU	1/2" - 1"
GAR3903-BU	1 1/4" - 2"
GAR3904-BU	2 1/2" - 3 1/2"
GAR3905-BU	4" - 5"
GAR3906-BU	6"

**NOTES**

- PIPE GROUNDING CLAMPS SHALL HAVE BRONZE HARDWARE, BE CORROSION RESISTANT, SUITABLE FOR DIRECT BURIAL IN EARTH OR CONCRETE, & UL467 LISTED.

PIPE/CONDUIT GROUNDING CLAMP DETAIL

NOV 23, 2011 9:15 AM HAGL000382  
p:\s\spi-svr306\hanson.d\m\hanson\Projects\Documents\11\Jobs\11A0080D\CAD\AircraftSheet\E-504

REVISION	DATE

**LITCHFIELD MUNICIPAL AIRPORT  
LITCHFIELD, ILLINOIS**

I.L. PROJ.: 3LF-4130      A.I.P. PROJ.: 3-17-0063-B18

Hanson Project No.	11A0080D	LAYOUT	KNL	07/28/11
Filename	E-504.dwg	DRAWN	BAK	07/28/11
Scale	NOT TO SCALE	REVIEWED	CAH	11/04/11
Date	10/28/2011			

**HANSON**  
 © Copyright Hanson Professional Services Inc. 2011  
**Hanson Professional Services Inc.**  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2986  
 Ph: (217) 788-2450 Fax: (217) 788-2503  
 www.hanson-inc.com  
 Offices Nationwide


REPLACE MRL'S ON  
RUNWAY 9-27

GROUNDING DETAILS

**GROUNDING NOTES**

1. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL GROUNDING AS MAY BE NECESSARY OR REQUIRED TO MAKE A COMPLETE GROUNDING SYSTEM AS REQUIRED BY THE LATEST NATIONAL ELECTRICAL CODE (NFPA 70) IN FORCE AND AS DETAILED HEREIN. THE RELIABILITY OF THE GROUNDING SYSTEM IS DEPENDENT ON CAREFUL, PROPER INSTALLATION AND CHOICE OF MATERIALS. IMPROPER PREPARATION OF SURFACES TO BE JOINED TO MAKE AN ELECTRICAL PATH, LOOSE JOINTS OR CORROSION CAN INTRODUCE IMPEDANCE THAT WILL SERIOUSLY IMPAIR THE ABILITY OF THE GROUND PATH TO PROTECT PERSONNEL AND EQUIPMENT AND TO ABSORB TRANSIENTS THAT CAN CAUSE NOISE IN COMMUNICATIONS CIRCUITS. THE FOLLOWING FUNCTIONS ARE PARTICULARLY IMPORTANT TO ENSURE A RELIABLE GROUND SYSTEM:
2. FURNISH AND INSTALL GROUND RODS AS DETAILED HEREIN. GROUND RODS FOR AIRFIELD LIGHTING (RUNWAY LIGHTING, TAXIWAY LIGHTING, TAXI GUIDANCE SIGNS, & DISTANCE REMAINING SIGNS) SHALL BE MINIMUM 5/8-IN. DIAMETER BY 8-FT LONG, UL-LISTED COPPER CLAD WITH 10-MIL MINIMUM COPPER COATING. GROUND RODS FOR OTHER APPLICATIONS SHALL BE MINIMUM 3/4-IN. DIAMETER BY 10-FT LONG, UL-LISTED, COPPER CLAD WITH 10-MIL MINIMUM COPPER COATING. GROUND RODS SHALL BE SPACED OR AS DETAILED ON THE RESPECTIVE PLANS, AND IN NO CASE SPACED LESS THAN ONE ROD LENGTH APART. ALL CONNECTIONS TO GROUND RODS AND THE GROUND RING SHALL BE MADE WITH EXOTHERMIC WELD TYPE CONNECTORS, CADWELD BY ERICO PRODUCTS, INC., SOLON, OHIO, (PHONE 1-800-248-9353), THERMOWELD BY CONTINENTAL INDUSTRIES, INC., TULSA, OKLAHOMA (PHONE 918-663-1440), ULTRAWELD BY HARGER, GRAYSLAKE, ILLINOIS (PHONE 1-800-842-7437), OR APPROVED EQUAL. EXOTHERMIC WELD CONNECTIONS SHALL BE INSTALLED IN CONFORMANCE WITH THE RESPECTIVE MANUFACTURER'S DIRECTIONS USING MOLDS AS REQUIRED FOR EACH RESPECTIVE APPLICATION. BOLTED CONNECTIONS WILL NOT BE PERMITTED AT GROUND RODS OR AT BURIED GROUNDING ELECTRODE CONDUCTORS.
3. CONTRACTOR SHALL TEST EACH MADE ELECTRODE GROUND ROD/GROUND FIELD/GROUND RING WITH AN INSTRUMENT SPECIFICALLY DESIGNED FOR TESTING GROUND FIELD SYSTEMS. IF GROUND RESISTANCE EXCEEDS 10 OHMS, CONTACT THE ENGINEER FOR FURTHER DIRECTION. COPIES OF GROUND FIELD TEST RESULTS SHALL BE FURNISHED TO THE RESIDENT ENGINEER, UPON REQUEST, FOR REVIEW AND RECORD PURPOSES.
4. ALL PRODUCTS ASSOCIATED WITH THE GROUNDING SYSTEM SHALL BE UL-LISTED AND LABELED.
5. ALL BOLTED OR MECHANICAL CONNECTIONS SHALL BE COATED WITH A CORROSION PREVENTATIVE COMPOUND BEFORE JOINING, SANCHEM INC. "NO-OX-ID "A-SPECIAL" COMPOUND, BURNDY PENETROX E, OR EQUAL.
6. METALLIC SURFACES TO BE JOINED SHALL BE PREPARED BY THE REMOVAL OF ALL NON-CONDUCTIVE MATERIAL, PER 2011 NATIONAL ELECTRICAL CODE ARTICLE 250-12. ALL COPPER BUS BARS MUST BE CLEANED PRIOR TO MAKING CONNECTIONS TO REMOVE SURFACE OXIDATION.
7. METALLIC RACEWAY FITTINGS SHALL BE MADE UP TIGHT TO PROVIDE A PERMANENT LOW IMPEDANCE PATH FOR ALL CIRCUITS. METAL CONDUIT TERMINATIONS IN ENCLOSURES SHALL BE BONDED TO THE ENCLOSURE WITH UL-LISTED FITTINGS SUITABLE FOR GROUNDING. PROVIDE GROUNDING BUSHINGS WITH BONDING JUMPERS FOR ALL METAL CONDUITS ENTERING SERVICE EQUIPMENT (METER BASE, CT CABINET, MAIN SERVICE BREAKER ENCLOSURE, ETC.). PROVIDE GROUNDING BUSHINGS WITH BONDING JUMPERS FOR ALL METAL CONDUITS ENTERING AN ENCLOSURE THROUGH CONCENTRIC OR ECCENTRIC KNOCKOUTS THAT ARE PUNCHED OR OTHERWISE FORMED SO AS TO IMPAIR THE ELECTRICAL CONNECTION TO GROUND. STANDARD LOCKNUTS OR BUSHINGS SHALL NOT BE THE SOLE MEANS FOR BONDING WHERE A CONDUIT ENTERS AN ENCLOSURE THROUGH A CONCENTRIC OR ECCENTRIC KNOCKOUT
8. ALL CONNECTIONS, LOCATED ABOVE GRADE, BETWEEN THE DIFFERENT TYPES OF GROUNDING CONDUCTORS SHALL BE MADE USING UL-LISTED DOUBLE COMPRESSION CRIMP TYPE CONNECTORS OR UL-LISTED BOLTED GROUND CONNECTORS. FOR GROUND CONNECTIONS TO ENCLOSURES, CASES AND FRAMES OF ELECTRICAL EQUIPMENT NOT SUPPLIED WITH GROUND LUGS THE CONTRACTOR SHALL DRILL REQUIRED HOLES FOR MOUNTING A BOLTED GROUND CONNECTOR. ALL BOLTED GROUND CONNECTORS SHALL BE BURNDY, THOMAS AND BETTS, OR EQUAL. TIGHTEN CONNECTIONS TO COMPLY WITH TIGHTENING TORQUES IN UL STANDARD 486A TO ASSURE PERMANENT AND EFFECTIVE GROUNDING.
9. ALL METAL EQUIPMENT ENCLOSURES, CONDUITS, CABINETS, BOXES, RECEPTACLES, MOTORS, ETC. SHALL BE BONDED TO THE RESPECTIVE GROUNDING SYSTEM.
10. PROVIDE ALL BOXES FOR PROPOSED OUTLETS, SWITCHES, CIRCUIT BREAKERS, ETC. WITH GROUNDING SCREWS. PROVIDE ALL PANELBOARD, SWITCHGEAR, ETC., ENCLOSURES WITH GROUNDING BARS WITH INDIVIDUAL SCREWS, LUGS, CLAMPS, ETC., FOR EACH OF THE GROUNDING CONDUCTORS THAT ENTER THEIR RESPECTIVE ENCLOSURES.
11. EACH NEW FEEDER CIRCUIT AND/OR BRANCH CIRCUIT SHALL INCLUDE AN EQUIPMENT GROUND WIRE. METAL RACEWAY OR CONDUIT SHALL NOT MEET THIS REQUIREMENT. THE EQUIPMENT GROUND WIRE FROM EQUIPMENT SHALL NOT BE SMALLER THAN ALLOWED BY 2011 NEC TABLE 250-122 "MINIMUM SIZE CONDUCTORS OR GROUNDING RACEWAY AND EQUIPMENT." WHEN CONDUCTORS ARE ADJUSTED IN SIZE TO COMPENSATE FOR VOLTAGE DROP, EQUIPMENT-GROUNDING CONDUCTORS SHALL BE ADJUSTED PROPORTIONATELY ACCORDING TO CIRCULAR MIL AREA. ALL EQUIPMENT GROUND WIRES SHALL BE COPPER, EITHER BARE OR INSULATED GREEN IN COLOR. WHERE THE EQUIPMENT GROUNDING CONDUCTORS ARE INSULATED, THEY SHALL BE IDENTIFIED BY THE COLOR GREEN, AND SHALL BE THE SAME INSULATION TYPE AS THE PHASE CONDUCTORS.
12. ALL EXTERIOR METAL CONDUIT, WHERE NOT ELECTRICALLY CONTINUOUS BECAUSE OF MANHOLES, HANDHOLES, NON-METALLIC JUNCTION BOXES, ETC., SHALL BE BONDED TO ALL OTHER METAL CONDUIT IN THE RESPECTIVE DUCT RUN, AND AT EACH END, WITH A COPPER-BONDING JUMPER SIZED IN CONFORMANCE WITH 2011 NEC 250-102. WHERE METAL CONDUITS TERMINATE IN AN ENCLOSURE (SUCH AS A MOTOR CONTROL CENTER, SWITCHBOARD, ETC) WHERE THERE IS NOT ELECTRICAL CONTINUITY WITH THE CONDUIT AND THE RESPECTIVE ENCLOSURE, PROVIDE A BONDING JUMPER FROM THE RESPECTIVE ENCLOSURE GROUND BUS TO THE CONDUIT SIZED PER 2008 NEC 250-102.
13. IT IS THE INTENT OF THIS SPECIFICATION THAT ALL MOTOR FRAMES, PUMP BASES ELECTRICAL EQUIPMENT ENCLOSURES, PANEL HOUSINGS, CONDUITS, BOXES, ETC. HAVE A CONTINUOUS COPPER WIRE GROUND CONNECTION AND SHALL BE POSITIVELY BONDED TO THE RESPECTIVE GROUNDING SYSTEM. CONDUIT CONNECTORS WILL NOT BE CONSIDERED AS ADEQUATE GROUNDING.
14. PROVIDE A POSITIVE GROUND BOND FOR ALL OUTLET BOXES, ELECTRICAL EQUIPMENT ENCLOSURES, GROUNDING RECEPTACLES, TOGGLE SWITCHES, ETC. INSTALL A GROUNDING CONDUCTOR IN ALL WIRE AND CABLE RACEWAYS. GROUND CONDUCTOR TO HAVE 600-VOLT INSULATION AND BE IDENTIFIED BY A CONTINUOUS GREEN COLOR COATING. THEY SHALL BE USED SOLELY FOR GROUNDING PURPOSES AND BE ENTIRELY SEPARATE FROM WHITE GROUNDED NEUTRAL CONDUCTOR, EXCEPT AT SUPPLY SIDE OF SERVICE DISCONNECTING MEANS, WHERE GROUNDING AND NEUTRAL SYSTEMS ARE TO BE CONNECTED TO SERVICE GROUND.
15. EACH AND ALL GROUNDED CASED AND METAL PARTS ASSOCIATED WITH ELECTRICAL EQUIPMENT SHALL BE TESTED FOR CONTINUITY OF CONNECTION WITH GROUND BUS SYSTEM BY CONTRACTOR IN PRESENCE OF OWNER'S REPRESENTATIVE.
16. ALL CONNECTIONS BETWEEN THE DIFFERENT TYPES OF GROUNDING CONDUCTORS ABOVE GRADE SHALL BE MADE USING BOLTED GROUND CONNECTORS. GROUND LUGS SHALL BE PROVIDED IN ALL ENCLOSURES AND WIRING TERMINATION JUNCTION BOXES. EQUIPMENT GROUNDS AND GROUNDING CONDUCTOR SHALL BE CONNECTED TO THESE GROUND LUGS. FOR GROUND CONNECTIONS TO ENCLOSURES, CASES AND FRAMES OF ELECTRICAL EQUIPMENT NOT SUPPLIED WITH GROUND LUGS THE CONTRACTOR SHALL DRILL REQUIRED HOLES FOR MOUNTING A BOLTED GROUND CONNECTOR. ALL BOLTED GROUND CONNECTORS SHALL BE BURNDY, OR EQUAL.
17. BOND ALL NONCURRENT-CARRYING PARTS OF METAL EQUIPMENT TO GROUND SYSTEM.
18. BUILDING STRUCTURAL STEEL SYSTEM SHALL BE BONDED TO ELECTRICAL GROUND SYSTEM.
19. INSTALL GROUNDING ELECTRODE CONDUCTORS, LIGHTNING PROTECTION DOWN CONDUCTORS AND SEPARATE GROUND CONDUCTORS IN SCHEDULE 40 OR SCHEDULE 80 PVC CONDUIT OR EXPOSED WHERE ACCEPTABLE TO LOCAL CODES. WHERE GROUNDING ELECTRODE CONDUCTORS, LIGHTNING PROTECTION DOWN CONDUCTORS OR INDIVIDUAL GROUND CONDUCTORS ARE RUN IN PVC CONDUIT, DO NOT COMPLETELY ENIRCLE CONDUIT WITH FERROUS AND/OR MAGNETIC MATERIALS. USE NON-METALLIC REINFORCED FIBERGLASS STRUT SUPPORT. WHERE METAL CONDUIT CLAMPS ARE INSTALLED, USE NYLON BOLTS, NUTS, WASHERS AND SPACERS TO INTERRUPT A COMPLETE METALLIC PATH FROM ENCIRCLING THE CONDUIT. THIS IS REQUIRED TO AVOID GIRDLING OF GROUND CONDUCTORS. GIRDLING OF A GROUND CONDUCTOR IS THE RESULT OF PLACING THE CONDUCTOR IN A RING OF MAGNETIC MATERIAL. THIS RING COULD BE A METALLIC CONDUIT, U-BOLT OR STRUT SUPPORT PIPE CLAMP, OR OTHER SUPPORT HARDWARE. THE RESULT OF GIRDLING GROUND CONDUCTORS SIGNIFICANTLY INCREASES THE INDUCTIVE IMPEDANCE OF THE GROUND CONDUCTOR. INDUCTIVE AND CAPACITIVE IMPEDANCE IS A TYPE OF RESISTANCE THAT OPPOSES THE FLOW OF ALTERNATING CURRENT. ANY INCREASE IN THE IMPEDANCE OF A GROUND CONDUCTOR REDUCES ITS ABILITY TO EFFECTIVELY MITIGATE RADIO FREQUENCY NOISE IN THE GROUND SYSTEM. THE CONDITION WHERE A GROUND CONDUCTOR IS GIRDLED DURING A LIGHTNING STRIKE RESULTS IN PHENOMENA KNOWN AS SURGE IMPEDANCE LOADING. SURGE IMPEDANCE LOADING IS A RESULT OF VOLTAGE AND CURRENT REACHING 500,000 VOLTS AND 10,000 AMPS FOR A SHORT DURATION. GIRDLING FURTHER INCREASES THE IMPEDANCE AT LIGHTNING FREQUENCIES OF 100 KILOHERTZ TO 100 MEGAHERTZ. AT THESE POWER AND FREQUENCY LEVELS ANY INCREASE IN THE IMPEDANCE OF THE GROUND CONDUCTOR MUST BE CONTROLLED. DURING LIGHTNING DISCHARGE CONDITIONS A LOW INDUCTIVE IMPEDANCE PATH IS MORE IMPORTANT THAN A LOW DC RESISTANCE PATH.
20. IF LOCAL CODES DICTATE THAT INDIVIDUAL GROUNDING CONDUCTORS MUST BE RUN IN METAL CONDUIT OR RACEWAY, THEN THE CONDUIT OR RACEWAY MUST BE BONDED AT EACH END OF THE RUN WITH A BONDING JUMPER SIZED EQUAL TO THE INDIVIDUAL GROUNDING CONDUCTOR OR AS REQUIRED BY 2008 NEC 250-102. NOTE THIS DOES NOT APPLY TO AC EQUIPMENT GROUNDING CONDUCTORS RUN WITH AC CIRCUITS.
21. WHERE A CONFLICT IS DETERMINED WITH RESPECT TO GROUNDING REQUIREMENTS PER MANUFACTURER INSTALLATION INSTRUCTIONS, NEC, AND/OR THE CONTRACT DOCUMENTS, CONTACT THE RESIDENT ENGINEER OR PROJECT ENGINEER FOR FURTHER DIRECTIONS.

NOV 23, 2011 9:17 AM H4GL000382  
 pw:\sps-svr306\hanson.dcm\hanson\_projects\Documents\11A0080D\CAD\Aircraft\SheetE-004

REVISION					
DATE					
<p><b>LITCHFIELD MUNICIPAL AIRPORT LITCHFIELD, ILLINOIS</b></p>					
<p>IL PROJ.: 31F-4130 A.I.P. PROJ.: 3-17-0063-B18</p>					
Hanson Project No.	11A0080D	LAYOUT	KNL	07/28/11	
Filename	E-004.dwg	DRAWN	BAK	07/28/11	
Scale	NOT TO SCALE	REVIEWED	CAH	11/04/11	
Date	10/28/2011				
 <p>© Copyright Hanson Professional Services Inc. 2011  <b>Hanson Professional Services Inc.</b>                  1525 South Sixth Street                  Springfield, Illinois 62703-2986                  Ph: (217) 788-2450 Fax: (217) 788-2503                  www.hanson-inc.com                  Offices Nationwide</p>					
<p>REPLACE MRL'S ON RUNWAY 9-27</p>			<p>GROUNDING NOTES</p>		
<p><b>34</b></p>					
<p>34 of 34 sheets</p>					