

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED 20% STATE			
20200100	EARTH EXCAVATION	CU YD	150	150			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	879	879			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	9			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9			
25200110	SODDING, SALT TOLERANT	SO YD	879	879			
25200200	SUPPLEMENTAL WATERING	UNIT	2	2			
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	17	17			
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	59350	59350			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	132	132			
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3467	3467			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	128	128			
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	171	171			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED 20% STATE			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	15	15			
42001300	PROTECTIVE COAT	SO YD	2778	2778			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	16623	16623			
42400800	DETECTABLE WARNINGS	SO FT	1122	1122			
44000100	PAVEMENT REMOVAL	SO YD	4	4			
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SO YD	5385	5385			
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	82540	82540			
44000600	SIDEWALK REMOVAL	SO FT	16204	16204			
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	1004	1004			
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	402	402			
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	602	602			
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	7	7			
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	5	5			
60262700	INLETS TO BE RECONSTRUCTED	EACH	5	5			* = SPECIALTY ITEMS

FILE NAME	USER NAME	DESIGNED	REVISED
PROJECT	PROJECT	CHECKED	REVISED
PLOT SCALE	PLOT DATE	DATE	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 43 (HARLEM AVE) - 26th ST TO I-55		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SUMMARY OF QUANTITIES		348	(2424&3138)RS-3	COOK	75	3
SCALE:		SHEET NO. OF SHEETS		STA. TO STA.		CONTRACT NO. 62C19

Rev 1-04-17

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED 20% STATE					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1098	1098					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	550	550					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	550	550					
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	6	6					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2262	2262					
* 89502376	REBUILD EXISTING HANDHOLE	EACH	17	17					
X4060004	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, 9.5, N80	TON	8617	8617					
X0320050	CONSTRUCTION LAYOUT (SPECIAL)	LSUM	1	1					
△ X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	500	500					
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	57	57					
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3126	3126					
△ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	26	26					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52					

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED 20% STATE					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	LSUM	1	1					
∅ Z0076600	TRAINEES	Hour	500	500					
∅ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	Hour	500	500					

8617 8617 △

∅ 0042
* = SPECIALTY ITEMS
△ = NON-PARTICIPATING WORK (100% STATE)

FILE NAME =	USER NAME = curjow	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 43 (HARLEM AVE) - 26th ST TO I-55 SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
pw\1102428\BORT\EG\Illinois\gov\PW1007\Documents\NDT	Office\Dir\rd\Projects\212640\CAD\rd\Drawings\212640	CHECKED -	REVISED -			348	(2424&3138)RS-3	COOK	75	5
	PLOT SCALE = 100,0000' / 1"	DATE -	REVISED -			CONTRACT NO. 62C19				
	PLOT DATE = 10/28/2016					FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev 1-04-17