

SUMMARY OF QUANTITIES				CONSTRUCTION CODE					
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS	BIKE LANE	LANDSCAPE	SEWER	WATER MAIN
				0004 15% STATE 85% LOCAL	0021 15% STATE 85% LOCAL	0028 80% ITEP 20% LOCAL	0031 15% STATE 85% LOCAL	0043 15% STATE 85% LOCAL	0043 100% LOCAL
35101582	AGGREGATE BASE COURSE, TYPE B 2"	SQ YD	41						41
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	28917	21687		7230			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	48	36		12			
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	165	123		42			
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	75	60		15			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	334	265		69			
40600990	TEMPORARY RAMP	SQ YD	250	250					
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1260						1260
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	3931	2948		983			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2734	2050		684			
40700100	BITUMINOUS MATERIALS (TACK COAT)	POUND	3121	2341		780			
40701841	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8"	SQ YD	3534	2650		884			
42000401	PORLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	5528	4423		1105			
42300100	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 5 INCH	SQ YD	1102	551		551			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	23870	17720		5850			300
42400800	DETECTABLE WARNINGS	SQ FT	2761	2485		276			
44000100	PAVEMENT REMOVAL	SQ YD	25918	17568		5850			2500
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	4563	3423		1140			
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	30402	22802		7600			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1316	601		605			110
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	23540	8905		13326			1309
44000600	SIDEWALK REMOVAL	SQ FT	26252	2589		23299			364
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	444	333		111			
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	753	333		420			
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	600	400		200			
44201299	DOVELE BARS 1 1/2"	EACH	2193	2193					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	482	361		121			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	482	361		121			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	600	400		200			
44213000	PATCHING REINFORCEMENT	SQ YD	1797	1437		360			
44213200	SAW CUTS	FOOT	5000	5000					
44213202	TIE BARS 1"	EACH	2193	2193					
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	50					50	
550B0340	STORM SEWERS, CLASS B, TYPE 2 12"	FOOT	507					507	

△ SPECIALTY ITEM

FILE NAME = N:\EVANSTON\140138.02\Civil\500.140138.02	USER NAME = mmichalowicz	DESIGNED -	REVISED - 12/30/2016	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CHICAGO AVE/SHERIDAN RD. SUMMARY OF QUANTITIES	F.A.J. RTE. 2853	SECTION 14-00273-00-BT	COUNTY COOK	TOTAL SHEETS 274	SHEET NO. 6	
PLOT SCALE = 3'	DRAWN -	REVISED -	SCALE: IN=BS.			SHEET 1 OF 1	SHEETS STA.	TO STA.	ILLINOIS FED. AID PROJECT		
PLOT DATE = 11/15/2016	CHECKED -	REVISED -									
	DATE -	REVISED -									