

SUMMARY OF QUANTITIES				CONSTRUCTION CODE					
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS	BIKE LANE	LANDSCAPE	SEWER	WATER MAIN
				0004 15% STATE 85% LOCAL	0021 15% STATE 85% LOCAL	0028 80% ITEP 20% LOCAL	0031 15% STATE 85% LOCAL	0043 15% STATE 85% LOCAL	0043 100% LOCAL
Z0062456	TEMPORARY PAVEMENT	SQ YD	1400	1400					
Z0073345	SLEEPER SLAB	FOOT	177	177					
Δ Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	7		7				
Δ A2002024	TREE, AESCULUS GLABRA (OHIO BUCKEYE), 3" CALIPER, BALLED AND BURLAPPED	EACH	11				11		
Δ A2004428	TREE, GINKGO BILOBA (GINKGO), 3-1/2" CALIPER, BALLED AND BURLAPPED	EACH	8				8		
Δ A2005024	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 3" CALIPER, BALLED AND BURLAPPED	EACH	13				13		
Δ A2005924	TREE, PLATANUS X ACERIFOLIA BLOODGOOD (BLOODGOOD LONDON PLANETREE), 3" CALIPER, BALLED AND BURLAPPED	EACH	10				10		
Δ A2008618	TREE, ULMUS MORTON GLOSSY (TRIUMPH ELM), 3" CALIPER, BALLED AND BURLAPPED	EACH	17				17		
Δ B2001124	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5				5		
Δ B2001420	TREE, CORNUS MAS (CORNELIAN CHERRY DOG WOOD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6				6		
Δ B2003414	TREE, MALUS FLORIBUNDA (JAPANESE FLOWERING CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2				2		
Δ K1005875	TREE TRANSPLANT	EACH	9				9		
Δ X0323071	SPARE FULL ACTUATED CONTROLLER, SPECIAL	EACH	1		1				
Δ X0323577	SANITARY SEWER TELEVISION INSPECTION, VIDEOTAPING AND RECORDING	FOOT	4326						4326
X0323677	STREET SWEEPING	HOUR	5						5
Δ X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	2608		2608				
Δ X0324599	ROD AND CLEARN EXISTING CONDUIT	FOOT	500		500				
Δ X0325476	RADAR VEHICLE DETECTION SYSTEM	EACH	1		1				
Δ X0326225	PAINT NEW PEDESTRIAN PUSH-BUTTON POST	EACH	1		1				
X0326863	BRICK SIDEWALK	SQ FT	230	230					
Δ X0327466	TRAFFIC COUNTER POST, GALVANIZED STEEL	EACH	15	13		2			
X0327611	REMOVE AND REINSTALL BRICK PAVER	SQ FT	1148	861		287			
Δ X0327615	COMBINED SEWER REMOVAL 8"	FOOT	29						29
X0327979	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	7090						7090
X4200950	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	16583	13267		3316			
X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	500	500					
Δ X5610651	ABANDON EXISTING WATER MAIN, FILL WITH CLSM	FOOT	3059						3059
Δ X5610706	WATER MAIN REMOVAL, 6"	FOOT	52						52
Δ X5610708	WATER MAIN REMOVAL, 8"	FOOT	52						52
Δ X5610748	WATER MAIN LINE STOP 8"	EACH	1						1
Δ X5620116	WATER SERVICE CONNECTION (SHORT)	EACH	18						18

Δ SPECIALTY ITEM

FILE NAME = N:\EVANSTON\140138.02\Civil\500.140138.02	DESIGNED -	REVISOR -	STATE OF ILLINOIS	F.A.U. RTE. 2853	SECTION 14-00273-00-BT	COUNTY COOK	TOTAL SHEETS 274	SHEET NO. 12
USER NAME = mmichalowiez	DRAWN -	REVISOR -	DEPARTMENT OF TRANSPORTATION	CHICAGO AVE/SHERIDAN RD.				
PLOT SCALE = 3"	CHECKED -	REVISOR -		SUMMARY OF QUANTITIES				
PLOT DATE = 11/15/2016	DATE -	REVISOR -		SCALE: 1/4"=1'-0"	SHEET 1 OF 1 SHEETS	STA. TO STA.	CONTRACT NO. 61D36	[ILLINOIS] FED. AID PROJECT