

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% Federal	20% State
				BRIDGE	ROADWAY
				0047	0004
				SN 052-0031	URBAN
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	42	0	42
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	144	0	144
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	160	0	160
40600990	TEMPORARY RAMP	SQ YD	27	0	27
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	27	0	27
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	113	0	113
50102400	CONCRETE REMOVAL	CU YD	11.2	11.2	0
50157300	PROTECTIVE SHIELD	SQ YD	218	218	0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	12.6	12.6	0
50300300	PROTECTIVE COAT	SQ YD	843	843	0
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2,490	2,490	0
50800702	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 2	L SUM	1	1	0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,970	1,970	0

1

MODEL: Default  
FILE NAME: P122-1005-03 WD3 Bridge Rehab01.DOTCAD\_Sheets\052-0031\64R54-INT-500\_01.dgn

**Kaskaskia**  
Engineering Group, LLC  
Professional Engineering Group

USER NAME = jheimer	DESIGNED -	REVISED -
PLOT SCALE = 1.9999' / in.	DRAWN -	REVISED -
PLOT DATE = 10/12/2022	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
US 30 OVER UPRR**

SCALE:	SHEET 1 OF 4 SHEETS	STA.	TO STA.
--------	---------------------	------	---------

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	(111-VBR)BDR	LEE	39	3
			CONTRACT NO. 64R54	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% Federal	20% State
				BRIDGE	ROADWAY
				0047	0004
				SN 052-0031	URBAN
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	482	0	482
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	0	2
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	0	2
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	6,794	0	6,794
X0326649	LINEAR DELINEATOR PANELS, 6 INCH	EACH	29	0	29
X5030250	BRIDGE DECK GROOVING (LONGITUDINAL)	SQ YD	559	559	0
<del>X5060602</del>	<del>CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES NO. 2</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>	<del>0</del>
X5060601	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1	0
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	1,133	0	1,133
X4820110	HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT (SPECIAL)	SQ YD	755	0	755
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	2,270	2,270	0
Z0001905	STRUCTURAL STEEL REPAIR	POUND	2,270	2,270	0
Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SQ YD	814	814	0
<del>Z0010501</del>	<del>CLEANING AND PAINTING STEEL BRIDGE NO. 1</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>	<del>0</del>
Z0012164	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	814	814	0
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	50	50	0
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2	0	2

\*= SPECIALTY ITEM

MODEL: Default; FILE NAME: P122-1005-03 WD3 Bridge Rehab01.DOTCAD\_Sheets\MS2-0031\64R54-INT-S00\_03.dgn

**Kaskaskia**  
Engineering Group, LLC  
Professional Engineering Firm  
200 North 2nd Street  
Moline, Illinois 61704  
617-321-2877  
www.kaskaskiaeng.com

USER NAME = jheimer	DESIGNED -	REVISED -
PLOT SCALE = 1.9999' / in.	DRAWN -	REVISED -
PLOT DATE = 10/12/2022	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES US 30 OVER UPRR			
SCALE:	SHEET 3	OF 4 SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
573	(111-VBR)BDR	LEE	39	5
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64R54	