



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 9, 2023

SUBJECT: Route FAS 669 (Oakland Road)
Section 22-00140-00-RS
Douglas County
Contract No. 91623
Item 076
January 20, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised sheets 2, 5 and 6 of the Plans.**
- 2. Revised the Schedule of Prices.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	22-00140-00-RS	D-DOUGLAS	46	2
JOB # C-95-007-23		PROJ. NO ALJW(716)		
SUMMARY OF QUANTITIES- INDEX OF SHEETS				

Summary of Quantity
22-00140-00-RS

Pav. Code	Pav. Item	Unit	Quantity
40200800	Aggregate Surface Course, Type B	TON	46
40600290	Bituminous Materials (Tack Coat)	POUND	23348
40600982	Hot-Mix Asphalt Surface Removal - Butt Joint	SQ YD	487
40602965	Hot-Mix Asphalt Binder Course, IL-9.5FG, N50	TON	2905
40604050	Hot-Mix Asphalt Surface Course, IL-9.5FG, Mix "C", N50	TON	3874
40800029	Bituminous Materials (Tack Coat)	POUND	861
40800050	Incidental Hot-Mix Asphalt Surfacing	TON	375
42000060	Welded Wire Reinforcement	SQ YD	873
44000151	Hot-Mix Asphalt Surface Removal, 1/2"	SQ YD	34589
44201298	Dowel Bars 1-1/4" (18 Inches Long)	EACH	280
44213200	Saw Cuts	FOOT	1023
44213204	Tie Bars 3/4" (24 Inches Long)	EACH	358
48101200	Aggregate Shoulders, Type B	Ton	2702
67100100	Mobilization	LSUM	1
78001110	Paint Pavement Marking - Line 4"	FOOT	33960
X4420675	Class B Patches, Type IV, 9 Inch (Special)	SQ YD	873
X7010215	Traffic Control and Protection, (Special)	LSUM	1
Z0017099	Dowel Bar Assembly	EACH	41

REvised 1/6/2023

A SPECIALTY ITEMS

PREPARED BY: JEC

CHECKED BY: GD

INDEX OF SHEETS

- 1 COVER SHEET
- 2 SUMMARY OF QUANTITIES, STANDARDS, INDEX OF SHEETS
- 3 GENERAL NOTES
- 4 EXISTING TYPICAL SECTIONS
- 4 - PROPOSED TYPICAL SECTIONS
- 5 7 SCHEDULES
- 8 STRIP MAP
- 9 18 DETAILS
- 19 22 DISTRICT 5 DETAILS
- 23 46 IDOT STANDARDS

STANDARD DRAWINGS

- 000001-08 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001001-02 AREAS OF REINFORCEMENT BARS
- 001006 DECIMAL OF INCH AND FOOT
- 420701-03 PAVEMENT WELDED WIRE REINFORCEMENT
- 701201-05 LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS > 45 MPH
- 701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701306-04 LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS, DAY ONLY FOR SPEEDS > 45 MPH
- 701311-03 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS DAY ONLY
- 701336-07 LANE CLOSURE, 2L, 2W, WORK AREAS IN SERIES, FOR SPEEDS > 45 MPH
- 701901-08 TRAFFIC CONTROL DEVICES
- 780001-05 TYPICAL PAVEMENT MARKINGS
- BLR 24-2 MAIL BOX TURN OUT - LOCAL ROADS

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	22-00140-00-RS	DOUGLAS	46	5
JOB # C-95-007-23		PROJ. NO AULW(716)		

SCHEDULES

PATCHING SCHEDULE

PATCH #	STATION	to STATION	LT/RT	Length (FEET)	Width (FEET)	AREA (SQ.FT.)	42000060 WELDED WIRE REINFORCEMENT (SQ YD)	44201298 DOWEL BARS 1-1/4" (18 INCHES LONG) (EACH)	44213200 SAW CUTS (FOOT)	44213204 TIE BARS 3/4" (24 INCHES LONG) (EACH)	X4420676 CLASS B PATCHES, TY IV 9 INCHES (SPECIAL) (SQ YD)	Z0017099 DOWEL BAR ASSEMBLY (EACH)	PATCH #
1	266+47.6	267+70.5	LT	122.9	11	1352.34	150.26	20.00	144.94	61.47	150.26	8	1
2	296+74.7	297+39.3	LT	64.6	11	710.38	78.93	20.00	86.58	32.29	78.93	4	2
3	323+32.8	323+57.7	RT	25.0	11	274.45	30.49	20.00	46.95	12.48	30.49	1	3
4	338+23.5	338+93.7	RT	70.2	11	771.65	85.74	20.00	92.15	35.08	85.74	4	4
5	334+27.0	334+74.0	LT	47.0	11	517.00	57.44	20.00	69.00	23.50	57.44	3	5
6	334+27.0	334+74.0	RT	47.0	11	517.00	57.44	20.00	69.00	23.50	57.44	3	6
7	355+66.2	356+32.1	RT	65.9	11	724.90	80.54	20.00	87.90	32.95	80.54	4	7
8	368+77.0	369+12.0	LT	35.0	11	385.00	42.78	20.00	57.00	17.50	42.78	2	8
9	368+77.0	369+12.0	RT	35.0	11	385.00	42.78	20.00	57.00	17.50	42.78	2	9
10	386+36.0	386+74.0	LT	38.0	11	418.00	46.44	20.00	60.00	19.00	46.44	2	10
11	386+36.0	386+74.0	RT	38.0	11	418.00	46.44	20.00	60.00	19.00	46.44	2	11
12	393+04.0	393+53.0	LT	49.0	11	539.00	59.89	20.00	71.00	24.50	59.89	3	12
13	393+04.0	393+53.0	RT	49.0	11	539.00	59.89	20.00	71.00	24.50	59.89	3	13
14	393+79.0	394+06.7	LT	27.7	11	305.14	33.90	20.00	49.74	13.87	33.90	1	14
Subtotal							872.98	280.00	1,022.26	357.13	872.98	40.94	
Quantity							873	280	1,023	358	873	41	

PREPARED BY: JAMES E CRANE PE
CHECKED BY: GD

10/12/2022

PAVEMENT SCHEDULE

STATION	TO STATION	AREA (SQ YD)	LENGTH (FOOT)	40600290 BITUMINOUS MATERIALS (TACK COAT) (POUND)	40600982 HMA SURFACE REMOVAL BUTT JOINT (SQ YD)	40602965 HMA BINDER COURSE IL-9.5FG N50 (1-1/2") (TON)	40604050 HMA SURFACE COURSE IL-9.5 FG MIX "C", N50 (2") (TON)	44000151 HMA SURFACE REMOVAL 1/2 INCH (SQ YD)	48100100 AGGREGATE SHOULDERS TYPE B (TON)
FAS 669 (CH-7)									
254+00.00	254+50.00	122.2	50.0	82.5	122.2	10.3	13.7	122.2	9.6
254+50.00	395+00.00	34,344.4	14,050.0	23,182.5	2,884.9	3,846.6	3,846.6	34,344.4	2,688.2
395+00.00	395+50.00	122.2	50.0	82.5	122.2	10.3	13.7	122.2	9.6
SUBTOTAL				23,347.5	244.4	2,905.5	3,874.0	34,588.9	2,707.4
TOTAL QUANTITY				23,348.0	244.0	2,905.0	3,874.0	34,589.0	2,707.0

PREPARED BY: JEC
CHECKED BY: GD

REVISD

1/6/2023

