

SI	SP	CODE NO.	ITEM	UNIT	TOTAL QUANTITY
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	70
		35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	200
		40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	12,446
		40600370	LONGITUDINAL JOINT SEALANT	FOOT	8,290
		40600990	TEMPORARY RAMP	SQ YD	194
		40604052	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N70	TON	3,098
		42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	2,453
		42400800	DETECTABLE WARNINGS	SQ FT	172
	*	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	27,658
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	804
		44000600	SIDEWALK REMOVAL	SQ FT	2,002
		44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	40
		44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	100
		44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	150

SI	SP	CODE NO.	ITEM	UNIT	TOTAL QUANTITY
		44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	50
	*	56109210	WATER VALVES TO BE ADJUSTED	EACH	2
		60255500	MANHOLES TO BE ADJUSTED	EACH	1
		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	804
		67100100	MOBILIZATION	L SUM	1
	*	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
	*	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
		70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,679
		70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	280.0
	X	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	60.0
	X	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13,053
	X	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	225
	X	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	758
	*	X7240600	REMOVE AND RE-ERECT EXISTING SIGN	EACH	2
		Z0013798	CONSTRUCTION LAYOUT	L SUM	1

NOTES: SI = SPECIALTY ITEM
SP = SEE PROJECT SPECIFIC SPECIAL PROVISIONS

MODEL: P:\proj\11819125 - Old Vincennes Trail Rest Area\cadd\microstation\CADD Sheets\11819125-118-S000.dgn
 FILE NAME: 11819125 - Old Vincennes Trail Rest Area\cadd\microstation\CADD Sheets\11819125-118-S000.dgn



USER NAME = brian.hell	DESIGNED -	REVISED - 01/05/2023
PLOT SCALE = 40.0000' / 1"	DRAWN -	REVISED -
PLOT DATE = 11/4/2022	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE. 1964	SECTION 21-00073-00-RS	COUNTY ST. CLAIR	TOTAL SHEETS 25	SHEET NO. 3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 97794	