

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE											90% FED. / 10% STATE				
				URBAN ROADWAY		RETAINING WALLS								CORNER GARDENS	SIGNING	SAFETY	LIGHTING	SURVEILLANCE	SIGNALS
				100% STATE	100% STATE	016-W882	016-W886	016-W894 016-W964	016-W901	016-W903 016-W906	016-W907	016-W887 016-W965	016-WWRR	Y007	Y002-1C	SFTY-3N	Y030-E1	Y032-1F	Y031-1F
42001300	PROTECTIVE COAT	SO YD	38,887	9,973	28,914														
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SO YD	299		299														
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SO YD	2,858	2,858															
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SO FT	1,032		1,032														
44000100	PAVEMENT REMOVAL	SO YD	32,408	32,075	333														
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	705	705															
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	25,419	25,419															
44000600	SIDEWALK REMOVAL	SO FT	34,360	34,360															
44000700	APPROACH SLAB REMOVAL	SO YD	287	287															
44002000	CONCRETE CURB REMOVAL	FOOT	159	159															
44003100	MEDIAN REMOVAL	SO FT	281	281															
44004250	PAVED SHOULDER REMOVAL	SO YD	7,671	7,671															
44201337	CLASS C PATCHES, TYPE I, 9 INCH	SO YD	4	4															
48200010	BITUMINOUS SHOULDERS, 1 1/2"	SO YD	472		472														
48202400	BITUMINOUS SHOULDERS, SUPERPAVE, 6"	SO YD	488	488															
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SO YD	311	311															
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1							1									
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1								1								
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1										1						
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1					1											
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1					1											
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1					1											
50102400	CONCRETE REMOVAL	CU YD	152						20	38	80		6	3	5				
50200100	STRUCTURE EXCAVATION	CU YD	22,627			802	6,162	5,072	44	4,004	930	5,040	13	44			516		
50300225	CONCRETE STRUCTURES	CU YD	7,068			320	2,547	1,199		1,192	330	1,384	7				89		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	836		2		204	123	85	245	40	90	21	15			11		
50300300	PROTECTIVE COAT	SO YD	9,740		308	560	2,967	1,423	392	1,360	383	1,407	62	76			202		
50300510	RUSTICATION FINISH	SO FT	42,553			140	16,697	6,528	760	9,031	1,164	7,515	158	136			424		
50800105	REINFORCEMENT BARS	LB	12,370														12,370		
50800205	REINFORCEMENT BARS, EPOXY COATED	LB	993,160		28,120	45,240	306,120	170,640	10,500	166,570	40,060	203,330	3,310	2,880			16,390		

* DENOTES SPECIALTY ITEMS

REVISIONS	NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (FRONTAGE ROAD & RAMPS)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: AMM
DATE: October 29, 2004 CHECKED BY: RMG



11/29/2004 9:23:51 AM