

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	90% FEDERAL / 10% STATE											CORNER GARDENS	SIGNING	SAFETY	LIGHTING	SURVEILLANCE	SIGNALS	
				URBAN ROADWAY		RETAINING WALLS															
				IDOT	J000	016-W882	016-W886	016-W894 016-W964	016-W901	016-W903 016-W906	016-W907	016-W887 016-W965	016-W907	016-W907							016-W907
				J000-2A	J000	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y002-1C	SFTY-3N	Y030-1E	Y032-1F	Y031-1F	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	8																8		
X0320080	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM	FOOT	1,683																	1,683	
X0320772	WATER MAIN REMOVAL 12"	FOOT	183		183																
X0322124	STORM SEWERS (WATER MAIN REQUIREMENTS) 8 INCH	FOOT	390		390																
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	294		294																
X0323314	MANHOLE, TYPE A, CITY OF CHICAGO	EACH	7		7																
X0323315	MANHOLE, TYPE B, CITY OF CHICAGO	EACH	4		4																
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	374	146	228																
X0323768	ELECTRICAL HANDHOLE, 30", 24" FRAME AND LID	EACH	7																	7	
X0323814	SANITARY SEWER REMOVAL, 18"	FOOT	322		322																
X0323900	CONCRETE FOUNDATION, TYPE 1	FOOT	4																4		
X0323907	COMMUNICATIONS VAULT	EACH	4																4		
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	65,060			24,790	8,680		12,080	2,850	16,482		178								
X0324112	BARRIER BASE	FOOT	466	466																	
X0324159	WHITEWASHING FOR CONCRETE PAVEMENT	SQ YD	9,257	9,257																	
X0324165	COMBINED SEWERS, ESVCP, TYPE 2, 12"	FOOT	10		10																
X0324166	COMBINED SEWERS, ESVCP, TYPE 2, 15"	FOOT	35		35																
X0324347	COMBINED SEWERS, RCCP, TYPE 2, 24"	FOOT	1,509		1,509																
X0324350	COMBINED SEWERS, ESVCP, TYPE 2, 18"	FOOT	329		329																
X0324354	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SAND	FOOT	2,492																	2,492	
X0324415	CONDUIT ENCASED, REINFORCED CONCRETE, 1-4" DIA., CNC	FOOT	107															21	86		
X0324420	PVC CONDUIT IN TRENCH, 4" DIA. (SCHEDULE 40)	FOOT	3,936																	3,936	
X0324421	RACKING CABLES IN MANHOLE OR HANDHOLE	EACH	9																	9	
X0324424	TRENCH AND BACKFILL WITH SCREENINGS AND/OR SOIL	FOOT	74																	74	
X0324433	LIGHT TOWER SERVICE PAD, 6"	SQ FT	105															105			
X0324435	CLEAN EXISTING MANHOLE OR HANDHOLE	EACH	2																2	2	
X0324469	CONDUIT ENCASED, REINFORCED CONCRETE, 2-4" DIA., CNC	FOOT	258															251	7		
X0324470	CONDUIT ENCASED, REINFORCED CONCRETE, 3-4" DIA., CNC	FOOT	30															10	20		
X0324471	CONDUIT ENCASED, REINFORCED CONCRETE, 4-4" DIA., CNC	FOOT	421															40	381		
X0324472	CONDUIT ENCASED, REINFORCED CONCRETE, 5-4" DIA., CNC	FOOT	72															29	43		

• DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (FRONTAGE ROAD & RAMPS)

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: AMM
DATE: October 29, 2004 CHECKED BY: RMG



Rev. 1-10-05

17/29/2004 9:23:55 AM