F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2021-922PT.1-AC	COOK	460	15
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62693

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	URBAN QUANTITY	90% FED 10% STATE URBAN ROADWAY IDOT J000-2A	100% STATE URBAN ROADWAY J000	90% FEDERAL / 10% STATE RETAINING WALLS Y007 016-W882	Y007 016-W886	Y007 016-W894 016-W964	Y007 016-W901	Y007 016-W903 016-W906	Y007 016-W907	Y007 016-W887 016-W965	Y007 016-WWRR		SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F	SIGNALS Y031-1F
*	X0324871	CONDUIT IN TRENCH, 4" DIA., COILABLE NON-METALLIC	FOOT	10															10	
*	X8101300	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL, PVC COATED	FOOT	132														132		
*	X0324515	ELECTRICAL HANDHOLE, 36", 30" FRAME AND LID	EACH	2																2
*	X0324793	LIGHT TOWER SERVICE PAD, SPECIAL	SQ FT	959														959		
*	X0324791	UTILITY TRANSFORMER PAD, 4"	EACH	1														1		
*	X0324872	CAST IN PLACE TACTILE/DETECTABLE WARNING SURFACE SYSTEM FOR RAMPS FOR PEOPLE WITH DISABILITIES	SQ FT	83		83														
*	X0324873	CONDUIT ENCASED, REINFORCED CONCRETE, 7-4" DIA., CNC	FOOT	155														66	89	
*	X0324874	CONDUIT ENCASED, REINFORCED CONCRETE, 3-2" DIA., RGC & 2-4" DIA., CNC	FOOT	3														1	2	
*	X0324501	CONDUIT ENCASED, REINFORCED CONCRETE, 3-2" DIA., RGC & 3-4" DIA., CNC	FOOT	83														28	55	
*	X0324875	DRILL EXISTING RETAINING WALL	EACH	2														2		
	X0321963	MICRO-PILES	EACH	917				829				88								
△1	X0323432	MICROPILE LOAD TEST	EACH	4				3				1								
	X0323433	MICROPILE PROOF LOAD TEST	EACH	9				7				2								

* DENOTES SPECIALTY ITEMS

△Rev. 1-10-05

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (FRONTAGE ROAD & RAMPS)

SUMMARY OF QUANTITIES

SCALE: NONE | DRAWN BY: NJH
DATE: October 29, 2004 | CHECKED BY: RMG

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO, ILLINOIS 60601-5212, PHONE: (312) 938-0300

MN-P40468\CMN\MC-CNTR\30\SM\Contract\S3083C0102A.SMT
11/29/2004 9:53:48 AM