F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2021-922PT.1-AC	COOK	460	13
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62693

SUMMARY OF QUANTITIES

				90% FED. / 10% STATE	100% STATE	← 90% FEDERAL / 10% STATE →								100% STATE	90% FED. / 10% STATE				
				URBAN ROADWAY		RETAINING WALLS								CORNER GARDENS	SIGNING	SAFETY	LIGHTING	SURVEILLANCE	SIGNALS
			URBAN	IDOT		016-W882	016-W886	016-W894 016-W964	016-W901	016-W903 016-W906	016-W907	016-W887 016-W965	016-WWRR						
CODE NO.	ITEM	UNIT	QUANTITY	J000-2A	J000	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y007	Y002-1C	SFTY-3N	Y030-1E	Y032-1F	Y031-1F
* X0324499	CONDUIT ENCASED, REINFORCED CONCRETE, 1-2" DIA. RGC & 5-4" DIA., CNC	FOOT	34														12	22	
* X0324504	CONDUIT ENCASED, REINFORCED CONCRETE, 1-2" DIA. RGC & 2-4" DIA., CNC	FOOT	26															26	
* X0324646	CONDUIT ENCASED, REINFORCED CONCRETE, 6-4" DIA., CNC	FOOT	243														81	162	
* X0324648	INNERDUCT IN CONDUIT, 1 1/4 INCH	FOOT	4,953																4,953
* X0324677	FIBER OPTIC HYBRID CABLE IN CONDUIT 6SM/6MM	FOOT	4,953																4,953
* X0324652	TRACER CABLE	FOOT	4,833																4,833
* X0324666	TESTING OF FIBER OPTIC CABLE	LSUM	1																1
X0324669	STORM SEWERS, ESVCP, TYPE 2, 8"	FOOT	406		406														
X0324675	TEMPORARY PAVEMENT, 10" (SPECIAL)	SQ YD	333		333														
X0324697	SOIL STABILIZERS	POUND	426,488	426,488															
X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	333	333															
X0324699	SPECIAL EXCAVATION AND REPLACEMENT FOR CONDUIT UNDER CTA TRACK	FOOT	36																36
X0712400	TEMPORARY PAVEMENT (INTERSTATE)	SQ YD	7,195	7,195															
* X0934000	PVC CONDUIT IN TRENCH, 4" DIA. (SCHEDULE 80)	FOOT	1,196																1,196
X2502930	SEEDING, CLASS 5 (MODIFIED) MILKWEED	ACRE	0.75	0.75															
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	22		22														
X4023000	TEMPORARY ACCESS (ROAD)	EACH	9		9														
X4834090	PORTLAND CEMENT CONCRETE SHOULDERS 14"	SQ YD	243	243															
X6061003	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.48 (MODIFIED)	FOOT	3,203	3,203															
X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	2,326	2,326															
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	395	395															
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	13,369		13,369														
X6370910	CONCRETE BARRIER, SINGLE FACE, 32" HEIGHT	FOOT	428	428															
X6640050	CHAIN LINK FENCE, 42" ATTACHED TO STRUCTURE (SPECIAL)	FOOT	4,399			75	1,535	462	415	1,420		327	86	79					
X6643200	CHAIN LINK FENCE, 42" GATE (SPECIAL)	EACH	5				2	1		1		1							
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	LSUM	1	1															
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	206	206															
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	39	23	16														
X7040600	FURNISH TEMPORARY CONCRETE BARRIER	FOOT	742		742														

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
63rd ST TO 59th ST (FRONTAGE ROAD & RAMPS)

SUMMARY OF QUANTITIES

SCALE: NONE | DRAWN BY: AMM
DATE: October 29, 2004 | CHECKED BY: RMG

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO, ILLINOIS 60601-5202, PHONE: (312) 938 0300

m:\p\0466\civil\1\c-contr\c\sf\general\sg09c008.dgn
11/29/2004 9:23:55 AM