

ROADWAY REMOVAL SCHEDULE

STATION TO STATION			PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	
WENTWORTH AVENUE			SQ YD	SQ YD	FOOT	SQ FT	
			SHEET				
131+44.62	TO	133+00.00	1	167	19	107	523
133+00.00	TO	138+00.00	2	778	43	500	2,684
138+00.00	TO	143+00.00	3	850	31	498	2,505
143+00.00	TO	143+68.47	4	106		69	406
TOTALS				1,901	93	1,174	6,118

ROADWAY ITEMS SCHEDULE

STATION TO STATION			SUB-BASE GRANULAR MATERIAL, TYPE B 8"	PORTLAND CEMENT CONC. PAVEMENT, 10" (JOINTED)	PROTECTIVE COAT	BITUMINOUS SHOULDERS, 1/2"	AGGREGATE BASE COURSE, TYPE B, 4"	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12 (MODIFIED)	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	COMBINATION CONCRETE CURB & GUTTER, TYPE B-V.12	TEMPORARY PAVEMENT	
WENTWORTH AVENUE			SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ FT	FOOT	SQ YD	
			SHEET									
131+44.62	TO	133+00.00	1	422	384	475	16	16	155	294	107	40
133+00.00	TO	138+00.00	2	1,878	1,667	1,896			500	57	500	
138+00.00	TO	143+00.00	3	1,931	1,724	1,944			500		492	
143+00.00	TO	143+68.47	4	238	213	243			69		69	
TOTALS				4,469	3,988	4,558	16	16	1,224	351	1,168	40

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE FACTOR *	EMBANKMENT	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-)	POROUS GRANULAR EMBANKMENT	FURNISHED EXCAVATION
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
WENTWORTH						
STAGE 1	29	25	57	-32	74	32
STAGE 2	95	81	52	29		
TOTAL	124	106	109	-3	74	32

* THE SHRINKAGE FACTOR USED TO CALCULATE EARTHWORK QUANTITIES IS 15%.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
 59th ST TO 57th ST (WENTWORTH AVENUE)

SCHEDULE OF QUANTITIES

SCALE: NONE DRAWN BY: AMM
 DATE: OCTOBER 29, 2004 CHECKED BY: JAL



10/27/2004 09:25:25 AM