FAS ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
1197	105 BR-2 & 105-T	WHITESIDE	59	9
STA.		TO STA.		
EXISTING CONDITIONS:				

PAVEMENT SCHEDULE

LOCATION	LENGTH	BIT SUR RM (VAR DP) (SQ YD)	PAVEMENT REMOVAL (SQ YD)	SUB GRAN MAT A 12 (SQ YD)	BR APPR PAVT CON (FLX) (SQ YD)	LEV BIND MM SUPER N50 (TON)	LEV BIND HM SUPER N50 (TON)	BC SC SUPER "C" N50 (TON)	BC BC SUP IL-19.0 N50 (TON)	BC BC WIDE SUP 10 (SQ YD)	AGG SHLDS B (TON)	AGG SURF CSE B (TON)	BR APPR PAVT (SQ YD)	SUB GRAN MAT B (TON)	CALCIUM CHLORIDE APPLIED (TON)
SECTION 105 BR-2															
224+00.00 224+90.00	90.00	246.00													
224+00.00 228+71.72	471.72										193.40				
230+63.27 232+00.00	136.73										103.50				
230+75.00 232+00.00	123.00	248.60													
228+65.50 229+58.29	92.79		234.00												
230+05.43 230+69.49	64.06		168.00												
228+65.50 228+71.72	6.20			20.00	17.97										
230+63.27 230+69.49	6.20			20.00	17.97										
224+00.00 225+00.00	100.00					4.60	0.5								
231+00.00 231+50.00	50.00					1.00	0.5								
224+00.00 228+65.50	465.50							151.20		118.96					
230+69.49 232+00.00	130.51							42.40		23.20					
225+00.00 228+65.50	365.50								482.80						
230+69.49 231+00.00	30.51								4.80						
228+71.72 229+01.72	30.00												106.97		
230+33.27 230+63.27	30.00												106.97		
226+10.00 LT												53.05			
228+70.50 LT				2.50											
228+63.50 RT				2.50											
230+71.50 LT				2.50											
230+64.50 RT				2.70											
MELLOTT'S RD.														50	
SUBTOTAL SECTION 105 BR-2		494.60	402.00	50.20	35.94	5.60	1.0	193.60	487.60	142.16	296.90	53.05	213.94	50	0
ROUNDED SUBTOTAL SECTION 105 BR-2		495	402	51	36	6	1	194	488	143	297	54	214	50	0
SECTION 105-T															
425+38.00 426+05.00	67.00	177.90													
425+38.00 427+75.17	237.17										137.50				
428+50.83 429+44.05	93.22										91.60				
428+56.83 429+00.00	43.00	112.70													
427+69.17 428+56.83	87.66		230.40												
427+69.17 427+75.17	6.00			19.30	17.33										
428+50.83 428+56.83	6.00			19.30	17.33										
426+00.00 426+50.00	50.00					3.80	0.5								
428+56.83 429+00.00	43.17					0.40	0.5								
425+38.00 427+69.17	231.17							75.10		53.94					
428+56.83 429+00.00	43.17							14.00		11.99					
426+50.00 427+69.17	119.17								67.80						
427+75.17 428+05.17	30.00												106.67		
428+20.83 428+50.83	30.00												106.67		
427+73.70 LT				2.50											
427+73.70 RT				2.50											
428+52.30 LT				2.50											
428+52.30 RT				2.50											
429+40.00 RT												56.03			
MELLOTT'S RD.														50	14
SUBTOTAL SECTION 105-T		290.60	230.40	48.60	34.66	4.20	1.0	89.10	67.80	65.93	229.20	56.03	213.34	50	14
ROUNDED SUBTOTAL SECTION 105-T		291	231	49	35	5	1	90	68	66	230	57	214	50	14
TOTAL		786	633	100	71	11	2	284	556	209	527	111	428	100	14

BRIDGE APPROACH PAVEMENT (DRAIN DETAIL) STANDARD 609006

CONTRACT 64421

LOCATION	TYPE B INLET BOX, STANDARD 609006 (EACH)	PIPE DRAINS 12" (FOOT)	METAL END SECTIONS 12" (EACH)	CONCRETE THRUST BLOCKS (EACH)
SECTION 105 BR-2				
230+43.0 RT	1	16	1	1
230+51.5 LT	1	16	1	1
SCHEDULE TOTAL	2	32	2	2

PIPE CULVERT SCHEDULE

LOCATION STATION	OFFSET	TO STATION	OFFSET	PIPE CULVERTS CLASS D TYPE 1, 18" (FOOT)	METAL END SECTIONS 18" (EACH)
SECTION 105 BR-2					
225+86.40	29.7 LT	226+34.20	29.7 LT	48	2
228+00.00	32.4 LT	228+65.50	37.0 LT	66	2
231+00.00	31.9 LT	231+53.31	31.9 LT	54	2
231+00.00	33.0 RT	231+53.31	31.1 RT	54	2
231+00.00	31.1 LT	231+00.00	33.0 RT	54	2
SUBTOTAL SECTION 105 BR-2				222	8
SECTION 105-T					
427+11.50	30.5 LT	427+69.17	33.2 LT	58	2
428+89.60	29.0 LT	429+62.00	29.9 LT	73	2
426+85.50	28.0 RT	427+32.13	33.6 RT	47	2
428+56.83	33.0 RT	429+58.88	30.0 RT	103	2
SUBTOTAL SECTION 105-T				281	8
SCHEDULE TOTAL				503	16

TREE REMOVAL SCHEDULE

LOCATION	TREE REMOVAL (6-15 UNITS DIAMETER) (UNITS)
SECTION 105 BR-2	
230+02.5 39.52 LT	14
229+79.8 46.60 RT	14
230+38.0 37.20 RT	12
230+38.0 37.20 RT	12
230+38.0 37.20 RT	12
230+38.0 37.20 RT	12
230+38.0 37.20 RT	12
230+38.0 37.20 RT	6
230+38.0 37.20 RT	6
SUBTOTAL SECTION 105 BR-2	100
SECTION 105-T	
428+21.0 34.30 RT	10
428+21.0 34.30 RT	6
428+21.0 34.30 RT	6
SUBTOTAL SECTION 105-T	22
SCHEDULE TOTAL	122

PERMANENT SURVEY MARKERS TYPE II SCHEDULE

LOCATION	PERMANENT SURVEY MARKERS TYPE II (EACH)
SECTION 105 BR-2	1
SECTION 105-T	1
SCHEDULE TOTAL	2

NOTE: LOCATIONS TO BE DETERMINED BY THE ENGINEER

DELINEATOR SCHEDULE

STATION	OFFSET	DELINEATORS (EACH)
SECTION 105 BR-2		
230+43.00	30.8 RT	1
230+51.50	31.6 LT	1
SCHEDULE TOTAL		2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAS ROUTE 203 (MOLINE ROAD)
SECTION 105 BR-2
WHITESIDE COUNTY

SCHEDULE OF QUANTITIES

DRAWN BY: HLC

PLAN	BY	DATE
SURVEYED		
PLOTTED		
ALIGNMENT CHECKED		
RT OF WAY CHECKED		
CADD FILE NAME		
NOTE BOOK NO.		

$$DATE$$
$$DGN_TIME$$
$$DGN_SPEC$$
$$REF1$$
$$REF2$$