

6442

F. A. S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
1197	105 BR-2 & 105-T	WHITESIDE	59	46
STA. 224+00 & 429+00		TO STA. 232+00 & 425+38		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

TREE REPLACEMENT SCHEDULE

GENERAL NOTES:

- 1. TREE LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT.
- 2. MULCH SHALL BE HARDWOOD WOOD CHIPS, 5 FOOT WIDTH, 4 INCHES THICK WITH WEED BARRIER FABRIC.
- 3. ALTERNATE SITE: TBD BY DISCTRICT 2.

SCIENTIFIC NAME	COMMON NAME	SIZE	UNIT	LOCATION	QUANTITY
TREE, QUERCUS BICOLOR	SWAMP WHITE OAK	1-3/4" CALIPER, BALLED & BURLAPPED	EACH	SEE ABOVE NOTE	12

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES)
UNLESS OTHERWISE NOTED.

Tue Nov 04 09:55:26 2003
c:\projects\d2stnds\z90pt4.dgn