

SUMMARY OF QUANTITIES

80% FED.
20% STATE
X071-2A

80% FED.
20% STATE
X071-2A

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	S.N. 027-0094
20200100	EARTH EXCAVATION	CU YD	312	312	
20300100	CHANNEL EXCAVATION	CU YD	640	640	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	99		99
25000200	SEEDING, CLASS 2	ACRE	0.25	0.25	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23	
25100115	MULCH, METHOD 2	ACRE	0.53	0.53	
28000300	TEMPORARY DITCH CHECKS	EACH	1	1	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
28000250	TEMPORARY EROSION CONTROL SEEDINGS	POUND	28	28	
28000400	PERIMETER EROSION BARRIER	FOOT	1,776	1,776	
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,050	155	895
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	895		895
35500600	BITUMINOUS BASE COURSE 9"	SQ YD	660	660	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	55	55	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	376	376	
40600300	AGGREGATE (PRIME COAT)	TON	8	8	
40600990	TEMPORARY RAMP	SQ YD	128	128	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	222	222	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	44	44	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	854	854	
44000100	PAVEMENT REMOVAL	SQ YD	290	290	
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	538	538	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	76	76	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	238		238
50300100	FLOOR DRAINS	EACH	16		16
50300225	CONCRETE STRUCTURES	CU YD	62.9		62.9

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	S.N. 027-0094
50300255	CONCRETE SUPERSTRUCTURE	CU YD	144.4		144.4
50300260	BRIDGE DECK GROOVING	SQ YD	437		437
50300300	PROTECTIVE COAT	SQ YD	539		539
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	1908		1908
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	40,210		40,210
51201100	FURNISHING METAL PILE SHELLS 14"	FOOT	945		945
51202600	DRIVING AND FILLING SHELLS	FOOT	945		945
51203200	TEST PILE METAL SHELLS	EACH	3		3
51500100	NAME PLATES	EACH	1		1
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	325	325	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	379	379	
67000400	ENGINEER'S FIELD OFFICE	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	70	70	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	90	90	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7,200	7,200	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	450	450	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	24	24	

*SPECIALTY ITEMS

SUMMARY OF QUANTITIES
 FAP 697 (IL. RTE. 9) OVER
 WALL TOWN DRAINAGE DITCH
 SECTION 17BR-1
 FORD COUNTY
 S.N. 027-0094

4440 ASH GROVE SPRINGFIELD, IL. 62707 (217) 793-8600 casino@famvid.com	OZYURT AND STONE, Inc. CONSULTING ENGINEERS	JOB NO.: 0306.2 FILE: SUM001.DWG DATE: 08-17-0
---	---	--