

| ROUTE NO. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-----------|---------|----------|--------------|-----------|
| FAP 330 | 16BR | KANKAKEE | 37 | 3 |

X080-2A SUMMARY OF QUANTITIES

X080-2A CONTRACT NO. 66365

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION TYPE | |
|----------|---------------------------------------------------------|--------|----------------|---------------------------|---------------------------------|
| | | | | 80% FED 20% STATE ROADWAY | 80% FED 20% STATE S.N. 046-0047 |
| 20200100 | EARTH EXCAVATION | CU YD | 314 | 314 | |
| 25000200 | SEEDING, CLASS 2 | ACRE | 0.20 | 0.20 | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 18 | 18 | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 18 | 18 | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 18 | 18 | |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 1618 | 1618 | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDINGS | POUND | 20 | 20 | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 730 | 730 | |
| 40200800 | AGGREGATE SURFACE COURSE, TYPE B | TON | 34 | 34 | |
| 42001165 | BRIDGE APPROACH PAVEMENT | SQ YD | 270 | 270 | |
| 42001430 | BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) | SQ YD | 54 | 54 | |
| 44000006 | BITUMINOUS SURFACE REMOVAL 1 1/2" | SQ YD | 990 | 990 | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 208 | 208 | |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 11 | 11 | |
| 48202700 | BITUMINOUS SHOULDERS SUPERPAVE 9" | SQ YD | 466 | 466 | |
| 50101500 | REMOVAL OF EXISTING SUPERSTRUCTURES | EACH | 1 | | 1 |
| 50102400 | CONCRETE REMOVAL | CU YD | 3.6 | | 3.6 |
| 50200100 | STRUCTURE EXCAVATION | CU YD | 3.4 | | 3.4 |
| 50300225 | CONCRETE STRUCTURES | CU YD | 5.4 | | 5.4 |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 503 | | 503 |
| 50300300 | PROTECTIVE COAT | SQ YD | 561 | | 561 |
| 50301245 | FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5") | SQ FT | 79.4 | | 79.4 |
| 50400305 | PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH) | SQ FT | 4521 | | 4521 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 7050 | | 7050 |
| 50901005 | STEEL BRIDGE RAIL, TYPE SM | FOOT | 228 | | 228 |
| 51500100 | NAME PLATES | EACH | 1 | | 1 |
| 58700200 | BRIDGE SEAT SEALER | SQ FT | 30 | | 30 |
| 59000100 | EPOXY CRACK SEALING | FOOT | 59 | | 59 |
| 63000000 | STEEL PLATE BEAM GUARDRAIL, TYPE A | FOOT | 325 | 325 | |
| 63100087 | TRAFFIC BARRIER TERMINAL, TYPE 6A | EACH | 4 | 4 | |
| 63100167 | TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) | EACH | 4 | 4 | |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 525 | 525 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 4 | 4 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70100405 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 | EACH | 1 | 1 | |
| 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 | |

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION TYPE | |
|------------|---------------------------------------------------------------|--------|----------------|---------------------------|---------------------------------|
| | | | | 80% FED 20% STATE ROADWAY | 80% FED 20% STATE S.N. 046-0047 |
| 70100500 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 | L SUM | 1 | 1 | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 60 | 60 | |
| 70106500 | TEMPORARY BRIDGE TRAFFIC SIGNALS | EACH | 1 | 1 | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 52 | 52 | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 1060 | 1060 | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 130 | 130 | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 48 | 48 | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 462.5 | 462.5 | |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 412.5 | 412.5 | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 710 | 710 | |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 80 | 80 | |
| * 78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 350 | 350 | |
| * 78001130 | PAINT PAVEMENT MARKING - LINE 6" | FOOT | 50 | 50 | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 5 | 5 | |
| * 78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 2 | 2 | |
| 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 11 | 11 | |
| 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 4 | 4 | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 234 | 234 | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 5 | 5 | |
| X0323557 | BRIDGE JOINT SYSTEM (EXPANSION), 1" | FOOT | 81 | | 81 |
| X3553100 | TEMPORARY BITUMINOUS BASE COURSE 8" | SQ YD | 271 | 271 | |
| X4066424 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D" N50 | TON | 83 | 83 | |
| X5030305 | CONCRETE WEARING SURFACE, 5" | SQ YD | 482 | | 482 |
| Z0001900 | ASBESTOS BEARING PAD REMOVAL | EACH | 90 | | 90 |
| Z0002600 | BAR SPLICERS | EACH | 213 | | 213 |
| Z0005215 | BITUMINOUS STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL | SQ YD | 164 | 164 | |
| ⊙ Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | 2 | |
| ⊙ Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | 2 | |

*SPECIALTY ITEMS
⊙SFTY-3N

SUMMARY OF QUANTITIES
 FAP ROUTE 330 (U.S. RTE. 45/52)
 OVER SOUTH BRANCH ROCK CREEK
 SECTION 16BR
 KANKAKEE COUNTY
 S.N. 046-0047

| | | |
|--------------------------------------------------------------------------------|-------------------------------------------------------|------------------------------------------------------|
| 4440 ASH GROVE SPRINGFIELD, IL 62711 (217) 793-8600 oasinc@tamvid.com | OZYURT AND STONE, INC. CONSULTING ENGINEERS | JOB NO.: 0306.3 FILE: SUM001DGN DATE: 09-07-04 |
|--------------------------------------------------------------------------------|-------------------------------------------------------|------------------------------------------------------|