

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	(1)R1TS	KANKAKEE	22	4
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 66416

NO.	DESCRIPTION	UNIT	TOTAL ESTIMATED QUANTITY	①	②	③
				ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNALS
				1000-1A	Y031-1F	Y030-1E
•73000100	WOOD SIGN SUPPORT	FOOT	80	---	80	---
•78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156	156	---	---
•78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5840	5840	---	---
•78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	680	680	---	---
•78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	637	637	---	---
•78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	125	125	---	---
•78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	84	84	---	---
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	68	68	---	---
•80500200	SERVICE INSTALLATION, TYPE B	EACH	1	---	1	---
•80803540	TRAFFIC SIGNAL WOOD POLE, 25 FT., CLASS 5	EACH	1	---	1	---
•81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	264	---	264	---
•81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1153	---	1153	---
•81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	105	---	105	---
•81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	8	---	8	---
•81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	104	---	104	---
•81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	133	---	133	---
•81400400	CONCRETE HANDHOLE	EACH	6	---	6	---
•81400600	CONCRETE DOUBLE HANDHOLE	EACH	1	---	1	---
•81500200	TRENCH AND BACKFILL FOR ELECTRIC WORK	FOOT	1349	---	1349	---
•81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	383	---	---	383
•82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	3	---	---	3
•85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	---	1	---
•87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	892	---	892	---
•87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	928	---	928	---
•87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN NO. 14, 1 PAIR	FOOT	2363	---	2363	---
•87301805	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6 2C	FOOT	11	---	11	---
•87502490	TRAFFIC SIGNAL POST GALVANIZED STEEL, 15 FT.	EACH	2	---	2	---
•87702840	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1	---	1	---
•87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1	---	1	---
•87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1	---	1	---
•87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6	---	6	---
•87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5	---	3.5	---
•87800400	CONCRETE FOUNDATION, TYPE E, 30 INCH DIAMETER	FOOT	10	---	10	---
•87800415	CONCRETE FOUNDATION, TYPE E, 36 INCH DIAMETER	FOOT	24	---	24	---
•88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	10	---	10	---
•88500100	INDUCTIVE LOOP DETECTOR	EACH	9	---	9	---
•88600100	DETECTOR LOOP, TYPE 1	FOOT	1000	---	1000	---
•X0323370	TRAFFIC SIGNAL BATTERY BACKUP	EACH	1	---	1	---
X3550210	BITUMINOUS BASE COURSE SUPERPAVE 5 1/2"	SQ YD	74	74	---	---
X3550710	BITUMINOUS BASE COURSE SUPERPAVE 10 1/2"	SQ YD	1622	1622	---	---
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	1101	1101	---	---
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	644	644	---	---
•X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1	---	1	---
•X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	5	---	5	---
•X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1	---	1	---
•X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	3	---	3	---

- ① 90% FED & 10% STATE
- ② 90% FED, 6.7% STATE & 3.3% COUNTY
- ③ 100% COUNTY

IL ROUTE 17  
AND CH 38 / LOWE ROAD  
SUMMARY OF QUANTITIES  
FAP ROUTE 330, FAU ROUTE 6209  
SEC. NO. (1)R1TS  
KANKAKEE COUNTY

• SPECIALTY ITEM