

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(2,3)RS-2	KENDALL	10	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES


CODE NO.	ITEM	UNIT	CONSTRUCTION CODE TYPE:		
			KENDALL COUNTY		
			TOTAL 80% FED 20% STATE	SN 047-2011 SFTY-2A	ROADWAY I000
20400800	FURNISHED EXCAVATION	CU YD	85.9		85.9
* 25000210	SEEDING, CLASS 2A	ACRE	0.29		0.29
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	25.92		25.92
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	25.92		25.92
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	25.92		25.92
* 25100105	MULCH, METHOD 1	ACRE	0.29		0.29
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	12213	9.6	12203.4
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	44.3	0.04	44.26
40600895	CONSTRUCTING TEST STRIP	EACH	1		1
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	3734.7		3734.7
40600990	TEMPORARY RAMP	SQ YD	160		160
40600300	AGGREGATE (PRIME COAT)	TON	305.45	0.2	305.25
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	576.2		576.2
44000003	BITUMINOUS SURFACE REMOVAL 3/4"	SQ YD	142276.8		142276.8
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	3314.2	119.5	3194.7
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	975.2		975.2
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	172		172
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	206.6		206.6
48101200	AGGREGATE SHOULDERS, TY B	TONS	6798		6798
66700095	PERMANENT SURVEY MARKERS	EACH	1		1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		4
67100100	MOBILIZATION	L SUM	1		1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16387	6	16381
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	156		156
70300625	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	FOOT	218490	132	218358
70300635	TEMPORARY PAINT PAVEMENT MARKING - LINE 6"	FOOT	27308	16	27292
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	1300		1300
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1821	1	1820

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	CONSTRUCTION CODE TYPE:		
			KENDALL COUNTY		
			TOTAL 80% FED 20% STATE	SN 047-2011 SFTY-2A	ROADWAY I000
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	156		156
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	136910	66	136844
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	13654	8	13646
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	1300		1300
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	717		717
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	1	1	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	717		717
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	12390.3	10	12380.3
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	6128.8		6128.8
X4066740	LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON	73.7		73.7

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_