

F.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	124RS-6, 125RS-3 & 4	LIVINGSTON	15	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT #66459

CODE NO. NO.	ITEM	UNIT	80% FED. 20% STATE CONSTRUCTION CODE TYPE	
			TOTAL QUANTITY	ROADWAY 1000
			20400805	FURNISHED EXCAVATION, SPECIAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	25,544	25,544
40600300	AGGREGATE (PRIME COAT)	TON	639	639
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	48	48
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	2,267	2,267
40600990	TEMPORARY RAMP	SQ YD	502	502
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	833	833
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	161,446	161,446
44201851	CLASS D PATCHES, TYPE II 17 INCHES	SQ YD	1,362	1,362
44201855	CLASS D PATCHES, TYPE III 17 INCHES	SQ YD	78	78
44201857	CLASS D PATCHES, TYPE IV 17 INCHES	SQ YD	72	72
44301300	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM C	FOOT	48,838	48,838
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,114	1,114
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	11	11
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1	1
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14,386	14,386
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	184	184
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	95,536	95,536
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	12,249	12,249
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	108	108
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,625	1,625
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	184	184
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17,941	17,941
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,845	2,845
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	108	108
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	77,595	77,595
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	9,404	9,404
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	616	616
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	616	616
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	13,514	13,514
X4066740	LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON	80	80
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	6,341	6,341
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY