

P.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	124RS-6, 125RS-3 & 4	LIVINGSTON	15	8
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT #66459

PAVEMENT MARKINGS SCHEDULE																				
STA. TO STA.	LENGTH	PAINT PAVEMENT MARKING			THERMOPLASTIC PAVEMENT MARKING					SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING					RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PVMT MKR REMOVAL		
		4" WHITE	4" YELLOW	6" YELLOW	4" WHITE	4" YELLOW	6" YELLOW	24" WHITE	LETTERS & SYMBOLS			4" WHITE	4" YELLOW	6" YELLOW	24" WHITE	LETTERS & SYMBOLS				
		FT	FT	FT	FT	FT	FT	FT	SQ FT			FT	SQ FT	FT	FT	FT			FT	SQ FT
1276+50	1280+50	400.0				400	100	36	61.2	80.0	13.2							5	5	
1280+50	1295+58	1,508.0								301.6	49.8							19	19	
1295+58	1298+82	324.0			81					64.8	10.7							4	4	
1298+82	1440+26	14,144.0	28,288		3,536					4,243.2	466.8	28,288		3,536				177	177	
1440+26	1446+97	671.0	1,342		168					201.3	22.1	1,342		168				8	8	
1446+97	1449+90	293.0	586		73					87.9	9.7	586		73				4	4	
1449+90	1457+50	760.0	1,520		190					228.0	25.1	1,520	760	190				10	10	
1457+50	1552+85	9,535.0	19,070		2,384					2,860.5	314.7	19,070		2,384				119	119	
1552+85	1564+11	1,126.0			2,252					337.8	37.2	2,252		282				14	14	
1564+11	1568+71	460.0			920	460	115			138.0	15.2	920	460	115				6	6	
1568+71	1571+15	244.0			488	488		72	122.4	73.2	8.1	488	488		72.0	122.4		3	3	
1571+15	1575+28	413.0			826	413	103			123.9	13.6	826	413	103				5	5	
1575+28	1630+25	5,497.0			10,994					1,649.1	181.4	10,994		1,374				69	69	
1630+25	1646+50	1,625.0								325.0	53.6			406				20	20	
1646+50	1650+00	350.0			700					105.0	11.6	700		88				4	4	
1650+00	1723+49	7,349.0	14,698		1,837					2,204.7	242.5	14,698		1,837				92	92	
1723+49	1731+82	833.0	1,666	833	208					249.9	27.5	1,666	833	208				10	10	
1731+82	1732+83	101.0			202					30.3	3.3	202		25				1	1	
1732+83	1740+28	745.0	1,490	745	186					223.5	24.6	1,490	745	186				9	9	
1740+28	1768+90	2,862.0	5,724		716					858.6	94.4	5,724		716				36	36	
SUBTOTALS			74,586.0	3,009.0	9,404	16,180.0	1,761.0	2,845	108.0	183.6		14,386.3	1,624.9	90,766.0	4,770.0	12,249	108.0	183.6	616	616
TOTALS			77,595	9,404	17,941	2,845	108	183.6		14,386.3	1,624.9	95,536	12,249	108	183.6	616	616			

NOTE: THE FOLLOWING NO PASSING ZONES SHOULD BE FIELD VERIFIED BY THE ENGINEER PRIOR TO RESURFACING.

NB - STA. 1276+50 TO STA. 1280+50
 NB - STA. 1449+90 TO STA. 1457+50

NB - STA. 1568+71 TO STA. 1571+15
 NB - STA. 1732+83 TO STA. 1740+28

NB - STA. 1276+50 TO STA. 1280+53
 SB - STA. 1440+26 TO STA. 1446+97

SB - STA. 1564+11 TO STA. 1575+28
 SB - STA. 1723+49 TO STA. 1731+82

MAINLINE SCHEDULE											
STA. TO STA.	BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE, MIX. 'C', N70	LEVELING BINDER (MM) SUPERPAVE N70	LEVELING BINDER (HM) SUPERPAVE N70	BITUMINOUS SURFACE REMOVAL 1 1/2 "	MIXTURE FOR CRACKS, JOINTS & FLANGWAYS	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	TEMP. RAMPS	AGGREGATE SHOULDER TYPE B	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM C	
	TONS	TONS	TONS	SQ YD	TONS	GAL	TONS	SQ YD	TONS	FT	
1276+50	1288+75	297.3	0.0	1.8	3,538.9	1.1	283.1	7.1	14.4	0.0	1,225.0
1288+75	1295+58	153.0	0.0	0.9	1,821.3	0.5	145.7	3.6	13.3	0.0	683.0
STRUCTURE OMISSION											
1297+99	1307+50	266.3	133.1	1.6	3,170.0	1.0	507.2	12.7	16.7	22.6	951.0
1307+50	1313+75	186.7	78.8	1.1	2,222.2	0.7	327.8	8.2		14.8	625.0
1313+75	1562+42	6,962.8	3,481.4	41.4	82,890.0	24.9	13,262.4	331.6		590.0	24,867.0
1562+42	1568+98	183.7	91.8	1.1	2,186.7	0.7	349.9	8.7		15.6	656.0
1568+98	1570+22	34.7	17.4	0.2	413.3	0.1	66.1	1.7	16.7	2.9	124.0
RAILROAD OMISSION											
1570+32	1606+54	1,014.2	507.1	6.0	12,073.3	3.6	1,931.7	48.3	16.7	85.9	3,622.0
1606+54	1630+50	670.9	335.4	4.0	7,986.7	2.4	1,277.9	31.9		56.8	2,396.0
1630+50	1646+25	352.8	0.0	2.1	4,200.0	1.3	336.0	8.4		37.4	1,575.0
1646+25	1650+04	106.1	53.1	0.6	1,263.3	0.4	202.1	5.1		9.0	379.0
1650+04	1653+05	84.3	42.1	0.5	1,003.3	0.3	160.5	4.0		7.1	301.0
1653+05	1657+22	116.8	58.4	0.7	1,390.0	0.4	222.4	5.6		9.9	417.0
1657+22	1745+53	2,472.7	1,236.3	14.7	29,436.7	8.8	4,709.9	117.7	16.7	209.5	8,831.0
STRUCTURE OMISSION											
1747+04	1768+90	612.1	306.0	3.6	7,286.7	2.2	1,165.9	29.1	33.3	51.9	2,186.0
TOTALS		13,514	6,341	80	160,882	48	24,949	624	128	1,114	48,838

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ.
 DATE

DRAWN BY
 CHECKED BY