

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
649		LIVINGSTON	15	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*116RS-4,(17,28)RS-2				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE:	I000	SFTY-2A
			80% FED 20% STATE TOTAL QUANTITY	RDWY	STR
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON		15452	48
40600300	AGGREGATE (PRIME COAT)	TON		396	5
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON		56	0.5
40600895	CONSTRUCTING TEST STRIP	EACH		1	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SO YD		260	
40600990	TEMPORARY RAMP	SO YD		329	
44000003	BITUMINOUS SURFACE REMOVAL 3/4"	SO YD		133693	518
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SO YD		57949	88
48101200	AGGREGATE SHOULDERS, TYPE B	TON		7615	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH		23	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO		4	
67100100	MOBILIZATION	L SUM		1	
70100450	TRAFFIC CONTRAL AND PROTECTION, STANDARD 701201	L SUM		1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM		1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT		19918	
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SO FT		124.8	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT		34016	
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT		29460	
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT		880	
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT		600	
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT		140	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT		2213	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT		62.4	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT		8520	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT		80	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT		440	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT		450	
* 78000620	THERMOPLASTIC PAVEMENT MARKING - LINE 18"	FOOT		36	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT		70	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT		130831	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT		14650	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH		838	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH		20	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH		838	
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON		15546	50
X4066740	LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON		93	0.5
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON		7773	26
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON		884	
Z0055300	RUMBLE STRIP	EACH		6	

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

PLOT DATE = 11/08/2004  
 FILE NAME = #FILEL#  
 PLOT SCALE = #SCALE#  
 REFERENCE = #REF#