

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
649	*	LIVINGSTON	15	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*(16)RS-4,(17,28)RS-2				

LOCATION		LENGTH FOOT	AREA SQ YD	BITUMINOUS SURFACE REMOVAL			BIT CONC SURF CSE SUPER "C", N70 TON	LEV BIND (MM) SUPER N70 TON	LEV BIND (HM) N70 TON	MIX FOR CRACKS JTS, & FLWYS TON	BIT MAT (PR CT) GALLON	AGG (PR CT) TON	AGG SHLDS TYPE B TON	TEMP RAMP SQ YD
STATION	DESCRIPTION			1 1/2"	3/4"	BUTT JT								
			SQ YD	SQ YD	SQ YD									
100+00	CENTERLINE IL ROUTE 18													
101+90	BEGIN RESURFACING													
102+20	END TAPER REMOVAL	30.0	87			87	7	4	0.1	0.1	7	1	3	14
123+05	1250E													
150+32	1300E													
157+38		5518.0	16459	16459			1383	691	8.2	4.9	1317	33	576	
157+47	SN 053-2002 (OLD STA 657+91.00)													
157+56		18.0	88	88			7	4	0.1	0.1	7	1		
203+20	1400E													
249+04		9148.0	26946	26946			2263	1132	13.5	8.1	2156	54	955	
256+35	1500E ILL 170 LT		956	956			80	40	0.5	0.3	76	2		14
256+35	1500E ILL 170 RT		806	806			68	34	0.4	0.2	64	2		14
263+66		1462.0	5774	5774			485	243	2.9	1.7	462	12	153	
309+20	1600E													
322+87.50	BACK = 322+85.10 AHEAD	5921.5	17107	87	17020		1437	718	8.6	5.1	1369	34	787	
361+80	1700E													
385+16		6230.9	18518		18518		1556	778	9.3	5.6	1481	37	828	
385+25	SN 053-2009 (OLD STA 430+10.00)													
385+34		18.0	88		88		7	4	0.1	0.1	7	1		
414+60	1800E													
458+27		7293.0	22105		22105		1857	928	11.1	6.6	1768	44	969	
458+42	SN 053-2008 (OLD STA 357+00.00)													
458+57		30.0	147		147		12	6	0.1	0.1	12	1		
466+90	1900E													
519+45	2000E													
531+59		7302.0	22136		22136		1859	930	11.1	6.6	1771	44	970	
531+75	SN 053-2007 (OLD STA 280+55.00)													
531+91		32.0	156		156		13	7	0.1	0.1	12	1		
572+20	2100E													
625+15	2200E													
669+13		13722.0	40674		40674		3417	1708	20.3	12.2	3254	81	1823	
669+26	SN 053-2006 (OLD STA 146+14.00)													
669+39		26.0	127		127		11	5	0.1	0.1	10	1		
677+70	2300E													
710+26	BEGIN ENDING TAPER	4087.0	12722		12722		1069	534	6.4	3.8	1018	25	543	
710+86	END RESURFACING	60.0	173			173	15	7	0.1	0.1	14	1	8	14
	AT BRIDGE APPROACH													
711+71.91	SN 053-0158 (OLD STA 103+79.75)													
ROUTE 17 TOTALS		60898.4		51116	133693	260	15546	7773	93.0	55.8	14805	375	7615	56
SIDEROAD AND ENTRANCE TOTALS				6833							647	21		273
TOTALS				57949	133693	260	15546	7773	93	56	15452	396	7615	329

BIT SURF REM TAPER FROM 1 1/2" TO 3/4" PAID FOR AS 1 1/2"

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	<h2 style="text-align: center;">SCHEDULES</h2> <p>SCALE: VERT. DRAWN BY HORIZ. CHECKED BY DATE</p>	