

FAS	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1379	(108B) BR-1	STARK	33	3
STA. 210+02		TO STA. 217+40		
FED. ROAD DIST. NO.		ILLINOIS	IL 91	

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	PROPOSED	ROADWAY	TOTAL
			SN 088-2500		80% FED 20% STATE
20200100	EARTH EXCAVATION	CU YD	0	1546	1546
20200500	EARTH EXCAVATION WIDENING	CU YD	0	216	216
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	136	0	136
20400800	FURNISHED EXCAVATION	CU YD	0	236	236
20800150	TRENCH BACKFILL	CU YD	0	12	12
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	264	0	264
21101615	TOPSOIL FURNISH & PLACE, 4"	SQ YD	0	5070	5070
25000300	SEEDING, CLASS 3	ACRE	0.0	0.9	0.9
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	0	108	108
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	0	108	108
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	0	108	108
25100115	MULCH, METHOD 2	ACRE	0.0	1.8	1.8
25100630	EROSION CONTROL BLANKET	SQ YD	0	878	878
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	0	270	270
28000300	TEMPORARY DITCH CHECKS	EACH	0	15	15
28000400	PERIMETER EROSION BARRIER	FOOT	0	190	190
28000500	INLET AND PIPE PROTECTION	EACH	0	2	2
28100207	STONE RIPRAP, CLASS A4	TON	0	294	294
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	0	441	441
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	0	1920	1920
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0	1	1
40600300	AGGREGATE (PRIME COAT)	TON	0	6	6
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	0	57	57
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	0	240	240
40600990	TEMPORARY RAMP	SQ YD	0	42	42
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	0	1196	1196
44000100	PAVEMENT REMOVAL	SQ YD	0	448	448
44004000	GUTTER REMOVAL	FOOT	0	313	313
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	0	113	113
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	0	1
50105200	REMOVE EXISTING CULVERTS	EACH	0	2	2
50800105	REINFORCEMENT BARS	POUND	25270	0	25270
51205200	TEMPORARY SHEET PILING	SQ FT	572	0	572
51500100	NAME PLATES	EACH	1	0	1

CODE NO.	ITEM	UNIT	PROPOSED	ROADWAY	TOTAL
			SN 088-2500		80% FED 20% STATE
54003000	CONCRETE BOX CULVERTS	CU YD	143	0	143
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTION 18"	EACH	0	4	4
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	0	106	106
63200310	GUARDRAIL REMOVAL	FOOT	0	902	902
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	0	8	8
66700095	PERMANENT SURVEY MARKERS	EACH	0	2	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	0	6	6
67100100	MOBILIZATION	L SUM	0	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	0	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	0	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	0	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	0	15	15
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	0	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	0	74	74
70300200	TEMPORARY PAVEMENT MARKING	FOOT	0	1661	1661
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	0	25	25
70400100	TEMPORARY CONCRETE BARRIER	FOOT	0.0	290	290
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	0.0	290	290
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	0	1661	1661
X0321100	GEOTEXTILE RETAINING WALL	SQ FT	120	0	120
X0323260	SEDIMENT BASINS	EACH	0	2	2
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	0	342	342
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	0	845	845
Z0002600	BAR SPLICERS	EACH	83	0	83
Z0013798	CONSTRUCTION LAYOUT	L SUM	0	1	1
<input type="checkbox"/> Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	0	2	2
<input type="checkbox"/> Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	0	2	2
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	0	110	110
Z0054500	ROCK FILL	TON	273	0	273

SFTY 3N

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NO SCALE
DATE: 06-02-03

DRAWN BY: BAD
CHECKED BY: JLG