

68128

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1375		STARK	6	4

• D4 CULVERT REPLACE 2005

SCHEDULE OF QUANTITIES

20800150	
TRENCH BACKFILL	
LOCATION	CU YD
Sta. 546+26	5
TOTAL	
5	

28100125	
STONE RIPRAP, CLASS B3	
LOCATION	SQ YD
From 25' LT Sta. 546+17.1 to 21.8' LT Sta. 546+30.3	6.6
From 26.7' RT Sta. 546+21.7 to 26.7' RT Sta. 546+30.3	4.2
TOTAL	
11	

44201789	
CLASS D PATCHES, TYPE II, 12 INCH	
LOCATION	SQ YD
LT Sta. 546+26	6.3
RT Sta. 546+26	6.9
TOTAL	
13	

50104400	
CONCRETE HEADWALL REMOVAL	
LOCATION	EACH
LT Sta. 546+26	1
RT Sta. 546+26	1
TOTAL	
2	

50105220	
PIPE CULVERT REMOVAL	
LOCATION	FT
Sta. 546+26	31.7
TOTAL	
32	

54207159	
PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE- ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	
LOCATION	FT
Sta. 546+26	33.0
TOTAL	
33	

54214719	
PRECAST REINFORCED CONCRETE FLARED END SECTIONS- ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	
LOCATION	EACH
LT Sta. 546+26	1
RT Sta. 546+26	1
TOTAL	
2	

67100100	
MOBILIZATION	
LOCATION	L SUM
Jobsite	1
TOTAL	
1	

70100450	
TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	
LOCATION	L SUM
Jobsite	1
TOTAL	
1	

70102640	
TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	
LOCATION	L SUM
Jobsite	1
TOTAL	
1	

SCHEDULE OF QUANTITIES