

SUMMARY OF QUANTITIES

SHEET 1 OF 2

LOCATION OF WORK: FAP 332
ILL ROUTE 1
RURAL
STA. 591+10
TO
STA. 600+10
S. N. 012-0071
80% FED
20% STATE

CONSTRUCTION TYPE CODE: X081-2A

CODE NO	ITEM	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	301.0
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18.0
20200100	EARTH EXCAVATION	CU YD	168.0
20400800	FURNISHED EXCAVATION	CU YD	193.0
20700220	POROUS GRANULAR EMBANKMENT	CU YD	158
28100109	STONE RIPRAP, CLASS A5	SQ YD	962
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	962
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	526.0
40600300	AGGREGATE (PRIME COAT)	TON	11.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	167.0
40600990	TEMPORARY RAMP	SQ YD	167.0
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	214.0
42001300	PROTECTIVE COAT	SQ YD	214.0
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	49.0
44000700	APPROACH SLAB REMOVAL	SQ YD	152.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	54.0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0
50200100	STRUCTURE EXCAVATION	CU YD	294
50300100	FLOOR DRAINS	EACH	18.0
50300225	CONCRETE STRUCTURES	CU YD	163.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	218.6
50300300	PROTECTIVE COAT	SQ YD	730.0
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	984.5
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	59,790.0
51201400	FURNISHING STEEL PILES HP 10X42	FOOT	264.0
51201500	FURNISHING STEEL PILES HP 10X57	FOOT	342.0
51202700	DRIVING STEEL PILES	FOOT	264.0
51205200	TEMPORARY SHEET PILING	SQ FT	753.0
51500100	NAME PLATES	EACH	1.0
X034865	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	741.0