

SUMMARY OF QUANTITIES

FILE NAME	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
314	110BR-1	MADISON	10	3
STA.		TO STA.		
CONTRACT NO.: 76865				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		X080-2A	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	75	75	
20400800	FURNISHED EXCAVATION	CU YD	125	125	
25000200	SEEDING, CLASS 2	ACRE	0.25	0.25	
25100115	MULCH, METHOD 2	ACRE	0.25	0.25	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50	50	
28000400	PERIMETER EROSION BARRIER	FOOT	1096	1096	
44001000	BITUMINOUS CONCRETE SURFACE REMOVAL	SQ YD	739	739	
50102400	CONCRETE REMOVAL	CU YD	3	3	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3.9	3.9	
50800205	REINFORCEMENT BARS, EPOXY COATED	PGUND	410	410	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	739	739	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	625	625	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	375	375	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	125	125	
70106600	TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED CONTROLLER)	EACH	1	1	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1172	1172	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	7	7	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	391	391	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	7	7	
X0301424	SILICONE JOINT SEALER	FOOT	66	66	
X0320887	POLYMER CONCRETE	CU FT	4.8	4.8	
X3560120	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 8 INCH	SQ YD	333	333	
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	62	62	
X4066775	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	50	50	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		X080-2A	
Z0002600	BAR SPLICERS	EACH	12	12	
Z0003700	BEARING PAD ADJUSTMENT	EACH	88	88	
Z0017300	DOWEL REPAIR	EACH	88	88	
Z0029300	GROUT REPAIR	FOOT	99	99	
Z0032700	KEYWAY REPAIR	FOOT	505	505	

* SPECIALTY ITEMS