

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3732	00-00215-00-BR	COOK	58	5
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	PROJECT BHM-7003(802)	
CONTRACT 83584				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			07C
				PARTICIPATING QIO			
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000 (ROADWAY)	X171-2# (BRIDGE)	Y080 (TRAINING)	1000 (ROADWAY)
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	686	556			130
66400305	CHAIN LINK FENCE, 6'	FOOT	166	166			
66400905	CHAIN LINK GATES, 4' X 6' SINGLE	EACH	2	2			
66410300	CHAIN LINK FENCE REMOVAL	FOOT	175	175			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7			
67100100	MOBILIZATION	L SUM	1	1			
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	250	250			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,000	2,550			450
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	3,600	3,060			540
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	36	12			24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,000	850			150
70400100	TEMPORARY CONCRETE BARRIER	FOOT	430	430			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	410	410			
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	4	3			1
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,020	1,020			
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	200	140			60
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	40	25			15
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	260	260			
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	120	100			20
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,300	1,000			300
X0301335	WATER MAIN REMOVAL 8"	FOOT	140	140			
X0320591	SANITARY MANHOLES TO BE REMOVED	EACH	2	2			
X0320772	WATER MAIN REMOVAL 12"	FOOT	87	87			
X0323199	SANITARY SEWER, DUCTILE IRON, 10"	FOOT	5	5			
X0323200	SANITARY SEWER, DUCTILE IRON, 12"	FOOT	5	5			
X0323557	BRIDGE JOINT SYSTEM (EXPANSION), 1"	FOOT	73		73		
X0323559	BRIDGE JOINT SYSTEM (FIXED),	FOOT	73		73		
X0487700	SANITARY SEWER REMOVAL 10"	FOOT	40	40			
X0487800	SANITARY SEWER REMOVAL 12"	FOOT	30	30			
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	14	14			

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			07C
				PARTICIPATING QIO			
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000 (ROADWAY)	X171-2# (BRIDGE)	Y080 (TRAINING)	1000 (ROADWAY)
X3550700	BITUMINOUS BASE COURSE SUPERPAVE 10"	SQ YD	1,760	1,505			255
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	2	2			
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	210	185			25
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	210	185			25
X5051200	FURNISHING AND ERECTING STRUCTURAL STEEL, SPECIAL	L SUM	1	1			
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	14	14			
XX003338	TEST HOLE	EACH	10	10			
XX003402	WATER MAIN INSULATION	FOOT	190	190			
XX004689	SANITARY SERVICE TO BE ADJUSTED	EACH	2	2			
Z0002600	BAR SPLICERS	EACH	475		475		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2			
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2			
Z0045002	PRESSURE CONNECTION 12" X 8"	EACH	2	2			
Z0047300	PROTECTIVE SHIELD	SQ YD	708		708		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
Z0076600	TRAINEES	hour	500			500	
Z0077700	WOOD FENCE TO BE REMOVED AND RE-ERECTED	FOOT	40	40			
XX006068	PVC WATERMAIN 8", SPECIAL	FOOT	105	105			
XX006069	DUCTILE IRON WATER MAIN 12", SPECIAL	FOOT	135	135			
XX006070	PVC WATER MAIN 8", SUSPENDED	FOOT	86	86			
XX006071	WATER MAIN, 12", SUSPENDED	FOOT	86	86			
Z0001100	AIR RELEASE VALVE	EACH	1	1			
XX006072	WATER MAIN EXPANSION JOINT, 12"	EACH	1	1			
XX006073	ROLLER CHAIR SUPPORT	EACH	14	14			
XX006074	TEMPORARY 10 FOOT CHAIN LINK FENCE WITH SCREENING	FOOT	280	280			
XX006075	DEPRESSED CURB RAMP ACCESSIBLE TO THE DISABLED	SQ FT	32	16			16

DATE: 11/09/04
FILENAME: N:\PROJECTS\212\Design\Misc_sheets\3212-quantities-02.dgn

CG **Clorba Group, Inc.**
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60656
Tel: 773.775.4000 Fax: 773.775.4014 Email: chicago@clorba.com

REVISIONS	
NAME	DATE

THE CITY OF EVANSTON
ASBURY AVENUE BRIDGE IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: DLP
DATE: OCTOBER, 2004 CHECKED BY: RAY